

82471

060200

---

**FINAL**  
**FEASIBILITY STUDY**

**REMEDIAL INVESTIGATION/FEASIBILITY STUDY**  
**H.O.D. LANDFILL**  
**ANTIOCH, ILLINOIS**

---

**Prepared For:**

**Waste Management of Illinois, Inc.**  
**Westchester, Illinois**

**Prepared By**

**Montgomery Watson**  
**2100 Corporate Drive**  
**Addison, Illinois 60101**

**June 1998**



**MONTGOMERY WATSON**


**FINAL**  
**FEASIBILITY STUDY**

**REMEDIAL INVESTIGATION/FEASIBILITY STUDY**  
**H.O.D. LANDFILL**  
**ANTIOCH, ILLINOIS**

**Prepared For:**

**Waste Management of Illinois, Inc.**  
**Westchester, Illinois**

Prepared by:



Thomas A. Blair, P.E.  
Project Engineer

6/3/98

Date

Approved by:



Jonas A. Dikinis  
Principal Environmental Scientist

6/3/98

Date

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION.....	1-1
1.1 AUTHORIZATION AND PURPOSE OF REPORT .....	1-1
1.2 REPORT ORGANIZATION .....	1-2
1.3 SITE CHARACTERISTICS .....	1-2
1.3.1 Site Description.....	1-2
1.3.2 Physical Characteristics.....	1-3
1.3.3 Site History.....	1-7
1.3.4 Local Demography and Land Use.....	1-10
1.4 NATURE AND EXTENT OF CONTAMINATION .....	1-11
1.4.1 Surficial Sand .....	1-11
1.4.2 Clay Diamict .....	1-11
1.4.3 Deep Sand and Gravel.....	1-11
1.4.4 Sequoit Creek Surface Water Results .....	1-12
1.4.5 Sequoit Creek Sediment Results .....	1-12
1.4.6 Surface Soils Results.....	1-12
1.5 CONTAMINANT FATE AND TRANSPORT .....	1-13
1.5.1 Primary Transport Pathways of Contaminants of Concern.....	1-13
1.5.2 Attenuating Effects.....	1-14
1.5.3 Fate and Migration of Site Contaminants in the Subsurface Landfill Gases. ....	1-14
1.6 SUMMARY OF THE BASELINE RISK ASSESSMENT .....	1-18
2.0 DEVELOPMENT OF REMEDIAL ACTION ALTERNATIVES .....	2-1
2.1 REMEDIAL ACTION OBJECTIVES.....	2-1
2.1.1 NCP and CERCLA Goals .....	2-2
2.1.2 General Site Response Action Objectives.....	2-3
2.2 APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS (ARARs) .....	2-4
2.2.1 Definitions of ARARs.....	2-4
2.2.2 Classification of ARARs .....	2-5
2.2.2.1 Chemical-Specific ARARs .....	2-5
2.2.2.2 Location-Specific ARARs.....	2-6
2.2.2.3 Action-Specific ARARs.....	2-6
2.2.3 ARARs for the HOD Site.....	2-6
3.0 REMEDIAL ACTION ALTERNATIVES .....	3-1
3.1 ACTION ITEMS COMMON TO ALL REMEDIAL ACTION ALTERNATIVES .....	3-1
3.2 GENERAL RESPONSE ACTIONS .....	3-2
3.2.1 No Further Action .....	3-3
3.2.2 Access Restrictions .....	3-3
3.2.3 Capping .....	3-3
3.2.4 Gas Collection/Treatment .....	3-4

# TABLE OF CONTENTS (Continued)

<u>Section</u>	<u>Page</u>
3.2.5 Leachate Collection/Treatment .....	3-5
3.2.6 Groundwater Monitoring.....	3-5
3.3 SUMMARY OF POTENTIAL ADDITIONAL REMEDIAL ACTION COMPONENTS.....	3-6
3.4 NO FURTHER ACTION.....	3-8
3.5 CAPPING.....	3-9
3.5.1 C1 – Landfill Cap Restoration and Maintenance.....	3-9
3.5.2 C2 – Augmentation of the Existing Landfill Cap .....	3-11
3.5.3 C3 – Reconfiguration/Supplementation of the Existing Landfill Cap.....	3-12
3.6 LANDFILL GAS COLLECTION AND TREATMENT ALTERNATIVES.....	3-14
3.6.1 G1 – No Further Action, Utilize the Existing Gas Collection System .....	3-14
3.6.2 G2 – Supplement the Existing LFG System .....	3-14
3.6.3 G3 – Active Site Upgrade of LFG System.....	3-15
3.7 LEACHATE COLLECTION ALTERNATIVES.....	3-16
3.7.1 LC1 – No Further Action, Continue To Utilize Existing System .....	3-16
3.7.2 LC2 – Toe-of-Slope Leachate Collection .....	3-16
3.7.3 LC3 – Upgrade/Supplementation of Leachate System .....	3-17
3.7.4 LC4 – Active Leachate Extraction.....	3-18
3.8 LEACHATE TREATMENT ALTERNATIVES.....	3-19
3.8.1 LT1 – No Further Action, Continue To Discharge To A Licensed POTW.....	3-19
3.8.2 LT2 – Pretreatment of Leachate, Discharge to POTW .....	3-19
3.8.3 LT3 – Treatment of Leachate, Surface Discharge.....	3-20
3.9 GROUNDWATER ALTERNATIVES.....	3-21
3.9.1 GW1 - No Further Action - Continue Groundwater Monitoring..	3-21
3.9.2 GW2 - Monitored Natural Attenuation .....	3-21
4.0 EVALUATION OF REMEDIAL ACTION ALTERNATIVES.....	4-1
4.1 CERCLA REQUIREMENTS .....	4-1
4.2 NO FURTHER ACTION EVALUATION.....	4-2
4.2 NO FURTHER ACTION EVALUATION.....	4-2
4.3 PROPOSED ACTIONS UNDER THE ILLINOIS PERMIT PROGRAM.....	4-5
4.4 EVALUATION OF ALTERNATIVES.....	4-7
4.4.1 Capping Alternatives Evaluation .....	4-7
4.4.1.1 Overall Protection of Human Health and Environment..	4-7
4.4.1.2 Compliance with ARARs.....	4-9
4.4.1.3 Long-Term Effectiveness and Permanence.....	4-9



## TABLE OF CONTENTS (Continued)

<u>Section</u>	<u>Page</u>
4.4.1.4 Reduction of Toxicity, Mobility or Volume Through Treatment.....	4-9
4.4.1.5 Short-Term Effectiveness.....	4-9
4.4.1.6 Implementability.....	4-11
4.4.1.7 Costs.....	4-11
4.4.2 Gas Collection and Treatment Alternatives Evaluation.....	4-11
4.4.2.1 Overall Protection of Human Health and Environment.....	4-12
4.4.2.2 Compliance with ARARs.....	4-12
4.4.2.3 Long-Term Effectiveness.....	4-13
4.4.2.4 Reduction of Toxicity, Mobility or Volume Through Treatment.....	4-13
4.4.2.5 Short-Term Effectiveness.....	4-14
4.4.2.6 Implementability.....	4-14
4.4.2.7 Costs.....	4-14
4.4.3 Leachate Collection Alternatives Analysis.....	4-14
4.4.3.1 Overall Protection of Human Health and Environment.....	4-15
4.4.3.2 Compliance with ARARs.....	4-15
4.4.3.3 Long-Term Effectiveness.....	4-16
4.4.3.4 Reduction of Toxicity, Mobility or Volume Through Treatment.....	4-16
4.4.3.5 Short-Term Effectiveness.....	4-17
4.4.3.6 Implementability.....	4-17
4.4.3.7 Costs.....	4-17
4.4.4 Leachate Treatment Alternatives Analysis.....	4-18
4.4.4.1 Overall Protection of Human Health and Environment.....	4-18
4.4.4.2 Compliance with ARARs.....	4-18
4.4.4.3 Long-Term Effectiveness.....	4-19
4.4.4.4 Reduction of Toxicity, Mobility, or Volume Through Treatment.....	4-19
4.4.4.5 Short-Term Effectiveness.....	4-19
4.4.4.6 Implementability.....	4-19
4.4.4.7 Costs.....	4-20
4.4.5 Groundwater Monitoring Alternatives Evaluation.....	4-20
4.4.5.1 Overall Protection of Human Health and the Environment.....	4-20
4.4.5.2 Compliance with ARARs.....	4-21
4.4.5.3 Long-term Effectiveness and Permanence.....	4-21
4.4.5.4 Reduction of Toxicity, Mobility, or Volume through Treatment.....	4-21

## TABLE OF CONTENTS (Continued)

<u>Section</u>	<u>Page</u>
4.4.5.5 Short-term Effectiveness .....	4-21
4.4.5.6 Implementability .....	4-21
4.4.5.7 Cost .....	4-21

## REFERENCES

## LIST OF TABLES

Table 1-1	Summary of Analytical Results – Leachate Samples
Table 1-2	Summary of Detected VOCs – Landfill Gas Samples
Table 1-3	Summary of Analytical Results – Round 1 and 2 Groundwater Samples
Table 1-4	Summary of Analytical Results – Private/Village Well Groundwater Samples
Table 1-5	Summary of Analytical Results – Round 1 and 2 Surface Water Samples
Table 1-6	Summary of Analytical Results – Round 2 Sediment Samples
Table 1-7	Summary of Analytical Results – Round 1 Surface Soil Samples
Table 1-8	Summary of Historical Monitoring Well VOC Data
Table 1-9	Summary of Risk Assessment Results
Table 2-1	Potential Chemical-Specific ARARs
Table 2-2	Potential Location-Specific ARARs
Table 2-3	Potential Action-Specific ARARs
Table 3-1	Summary of Remedial Action Alternatives
Table 3-2	POTW Discharge Requirements
Table 3-3	Cost Estimate Summary
Table 3-4	Leachate Treatment Processes
Table 4-1	Summary of Vinyl Chloride Detected in Village Well 4

## LIST OF FIGURES

Figure 1	Site Location Map
Figure 2	Site Features Map
Figure 3	Monitoring Well and Piezometer Location Map
Figure 4	Leachate Piezometer and Gas Probe Location Map
Figure 5	Surface Water/Sediment and Surface Soil Sampling Location Map (Round I and II)
Figure 6	Village Water Supply Well Location Map
Figure 7	Private Water Supply Well Sampling Locations

## **TABLE OF CONTENTS**

### **(Continued)**

Figure 8	Existing Conditions – Landfill Cover
Figure 9	Cross Section A-A' and Conceptual Details of Cap Alternatives C2 & C3
Figure 10	Existing Gas and Leachate Extraction Devices
Figure 11	Alternative G2 – Upgrade/Supplementation of LFG System
Figure 12	Alternative G3 – Activation of LFG System Alternative LC4 - Active Leachate Extraction
Figure 13	Alternative LC2 – Toe-of-Slope Leachate Collection
Figure 14	Alternative LC3 – Upgrade/Supplementation of Leachate System
Figure 15	Sample Locations – Proposed Groundwater Monitoring Plan

## **LIST OF APPENDICES**

Appendix A	TSC Testing Reports
Appendix B	Capping Timing Estimate
Appendix C	HELP Model Output
Appendix D	Cost Estimates



## **1.0 INTRODUCTION**

### **1.1 AUTHORIZATION AND PURPOSE OF REPORT**

This Feasibility Study (FS) has been prepared on behalf of Waste Management Illinois, Inc. (WMII), for the H.O.D. Landfill Site (Site) in Antioch, Illinois. This study has been conducted under Administrative Order By Consent (AOC) Docket No. V-W-90-C-71, which was signed on August 20, 1990. The purpose of the FS is to provide information that will assist in the selection of a remedial action alternative that is consistent with the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) and the National Oil and Hazardous Substances Contingency Plan (NCP). This FS has been prepared in accordance with the U.S. Environmental Protection Agency's (U.S. EPA's) Guidance for Conducting Remedial Investigations and Feasibility Studies for CERCLA Municipal Landfill Sites, using U.S. EPA's "Presumptive Remedy" approach.

The Presumptive Remedy approach is one tool of acceleration within the Superfund program. It recognizes that certain categories of sites have similar characteristics, such as types of contaminants present, types of disposal practices, or environmental impacts. Presumptive Remedies are preferred technologies for common categories of sites, based on historical patterns of remedy selection and U.S. EPA's scientific and engineering evaluation of performance data on technology implementation. The Presumptive Remedy for landfills is outlined in OSWER Directive 9355.0-49FS, "Presumptive Remedies for CERCLA Municipal Landfill Sites."

U.S. EPA has established containment as the Presumptive Remedy for landfill sites, based on the volume and heterogeneous nature of the materials deposited at a landfill, and the generally low, long-term threat that may be presented. Primary containment measures include landfill capping, collection and/or treatment of landfill gas (LFG), and control of landfill leachate and affected groundwater, if applicable.

On February 14, 1997, U.S. EPA approved the final remedial investigation (RI) for the Site (Montgomery Watson, January 1997). The data collected and presented in the RI are considered sufficient to evaluate remedial alternatives for the Site. A summary of the RI is presented in Sections 1.3, 1.4 and 1.5 herein. U.S. EPA approved the Baseline Risk Assessment (Baseline RA) on October 29, 1997. A summary of the Baseline RA findings is included in Section 1.6. The approved RI and Baseline RA describe Site conditions that are consistent with continued evaluation as a municipal landfill site.

## **1.2 REPORT ORGANIZATION**

The FS is organized into four sections, as follows:

- Section 1 contains background information for the Site, including a site description and history, a summary of the nature and extent of contaminants identified during the RI, a qualitative discussion of potential contaminant fate and transport, and a summary of the Baseline RA.
- Section 2 summarizes the remedial alternative development process, defines the general site response action objectives and ARARs, and introduces the general response actions.
- Section 3 contains the complete description of the remedial action alternatives developed using the presumptive remedy approach.
- Section 4 contains a detailed evaluation of the remedial action alternatives.

## **1.3 SITE CHARACTERISTICS**

### **1.3.1 Site Description**

The Site is located within the eastern boundary of the Village of Antioch in Lake County in northeastern Illinois (Township 46 North, Range 10 East, SE 1/4, SE 1/4, Section 8 and West 1/2, SW 1/4 of Section 9, Figure 1).

The Site consists of approximately 51 acres of landfilled area out of the total 121.47 acres of property owned by WMII that make up the facility. Although the landfilled area is continuous, it consists of two separate landfill areas, identified as the "old" and the "new" landfills. The "old landfill" consists of 24.2 acres situated on the western third of the property. The "new landfill" consists of 26.8 acres located immediately east of the "old landfill." The two landfill areas have been legally delineated with a division line established under special permit conditions (No. 1975-22-DE and No. 75-329) issued by the Illinois Environmental Protection Agency (IEPA), Division of Land Pollution Control. These Site features are shown on Figure 2.

The landfill cover is continuous across the filled areas of the Site. The landfill cover ranges in thickness from a total of 49 inches to 87 inches based on borings and test pits performed during the RI. Final cover compaction testing indicated that all samples were greater than the 90% compaction specification. These results may be found in Appendix A. Refuse was generally encountered beneath the existing landfill cover. The landfill cover supports a healthy vegetative layer. Since the closure of the Site in 1984 and the capping of the Site in 1989, precipitation has resulted in erosional rills and gullies in some areas of the landfill cover. Several areas of differential settlement and stressed vegetation have developed since

the cap construction. Minor leachate seeps, animal burrows, and LFG emission areas have also been observed since the cap construction.

LFG is being produced and is currently passively vented through a system of wells at the Site. Although the wells are fitted with flares, the flares are currently not totally effective at controlling the LFG produced. LFG is also migrating horizontally through the unsaturated areas of the subsurface, in the southwest corner of the landfill, and was found to be escaping through some areas of the existing landfill cover. LFG production in a municipal solid waste landfill is typically greatest in the first seven to fifteen years following cap construction, and typically decreases each year thereafter.

The leachate generated by the Site contains constituents typical of municipal landfill leachate. Leachate removal began in 1987. Based upon 1993 records, approximately 450,000 gallons of leachate are removed from the landfill each year. Leachate level measurements are collected at the Site, and indicate that the Site is in compliance with the leachate maintenance levels established in the IEPA's permit for the Site. According to the permit, the leachate levels within the landfill are to be maintained below the water level measured contemporaneously in well US11D. Leachate is removed from extraction manholes MHE and MHW one to two times per week.

### **1.3.2 Physical Characteristics**

**Climate.** The Site is located within a continental climatic belt characterized by frequent variations in temperature, humidity and wind direction. The average daily minimum temperature is 15° F in January and the average daily maximum temperature is 83° F in July. The average annual precipitation is 32.5 inches. The wettest months are April through September (USDA, 1970).

**Physiography.** The Site is situated within the Valparaiso Morainic System (Willman, 1975). The topography of the area is generally characterized by gentle slopes with poorly defined surface drainage patterns, depressions, and wetlands. The maximum relief in Lake County is 340 feet.

The topography in the vicinity of the Site is generally flat. The most prominent topographic feature in the general area is the landfill. The maximum elevation of the landfill is approximately 800 feet mean sea level (MSL). The elevation of Sequoit Creek is approximately 762 feet MSL. Therefore, maximum ground surface relief at the Site is approximately 40 feet.

**Surface Hydrology.** Surface drainage around the Site is generally toward the Fox River, located approximately five miles to the west. Locally, surface water flows from the Site toward Sequoit Creek. Sequoit Creek originally flowed northwest from Silver Lake to a point that is now the approximate center and northern boundary of the Site, and then flowed west toward the Village of Antioch. However, sometime between 1964 and 1967, Sequoit Creek was rerouted to flow west from Silver Lake along what is now the southern boundary of the Site. At the southwestern corner of the landfill, the creek was rerouted to

flow north along the western boundary of the Site. Approximately 250 feet north of the northwestern corner of the Site, the creek channel turns west and the creek flows approximately two miles before discharging into Lake Marie. Lake Marie eventually discharges to the Fox River.

**Wetlands.** Based on aerial photographs and a 1960 USGS topographic map of the Site area, the eastern portion of the Site was a wetland area prior to landfill development. P.E. LaMoreaux & Associates, Inc. performed a detailed wetland assessment in 1993 and identified seasonal wetlands within only the low elevation portion of the Site, south of the "new landfill" area (see Figure 3). The wetlands are limited to the areas outside the delineated landfill boundaries. Sequoit Creek flows from Silver Lake by way of two stream channels which eventually join and proceed through the seasonal wetlands.

**Floodplain.** Floodplain maps developed before the operation of the "new landfill" showed that the existing landfill (the "old landfill") was outside the 100-year floodplain. Based on the established flood elevations of 765 to 767 feet MSL, the "new landfill" area is also above the floodplain elevation (FEMA, 1997). Additional information regarding surface hydrology at the Site can be found in the RI Report.

**Surface Soils.** The following surface soil types were present at the Site prior to site development, and may still be present in undeveloped areas.

- Houghton muck, wet
- Morley silt loam
- Zurich silt loam
- Peotone silty clay loam
- Peotone silty clay loam, wet
- Mundelein silt loam
- Miami silt loam

The Houghton muck and Peotone silty clay loam are classified by the USDA Soil Conservation Service (SCS) as hydric soils. The Zurich silt loam and Mundelein silt loam are non-hydric soils that may contain hydric inclusions. A description of each soil type is included in the RI Report.

**Site Geology.** The Site area is underlain by differentiated deposits of sand, gravel, and silty clay. Results of grain size analyses, Atterberg limits testing, TOC analyses, and permeability testing conducted on soil samples during the RI are presented in the RI Report.



The unconsolidated deposits encountered in borings drilled at the Site consist of a depositional sequence of till and outwash deposits associated with the surficial Cahokia alluvium (Holocene) and underlying Wadsworth and Haeger Till Members of the Wedron Formation. The unconsolidated deposits are divided into four distinct depositional units, in order of increasing depth and age:

- **Surface Soils** – Natural surface soils encountered during the RI included 1 to 1.5 feet of reddish to black topsoil formed as the weathered surface of the clay diamict encountered in soil borings. Five feet of peat and organic-rich clay and silts were found overlying the surficial sand in soil borings drilled in the wetland area.
- **Surficial Sand** – The surficial sand is present only along the southern portion of the Site and is not used for public or private water supply. It exhibits an elongated east-northeast to west trending geometry. The surficial sand generally consists of light brown to gray, fine to coarse grained sand, with varying amounts of gravel, silt, and clay. The surficial sand was not encountered in the northern portion of the landfill. A surficial sand isopach map is shown on Figure 17 of the RI Report.
- **Clay-Rich Diamict** – The clay-rich diamict is a laterally extensive deposit which contains various amounts of sand, gravel, and silt mixed in a matrix of clay, which contains discontinuous layers and lenses. The clay-rich diamict is present beneath the entire Site. Based on the soil borings drilled in the vicinity of the Site, the surficial sand is separated from the deep sand and gravel aquifer by the clay-rich diamict. RI data indicate that the clay-rich diamict is typically light to dark gray massive silty to lean clay, with trace to some sand and trace gravel.
- **Deep Sand and Gravel** – The deep sand and gravel is laterally extensive and is present beneath the entire Site. This unit is a part of the regional aquifer and is used regionally as a potable water source. The full thickness of the deep sand and gravel is not known, but the unit is at least 185 feet thick in the general vicinity of the Site. Based on the results of the sieve analysis of the samples collected from the deep sand and gravel from various borings, the upper portion of this unit consists of brown to gray fine to coarse sand, with trace to some gravel, trace to little silt, and trace clay. Lower portions of this unit are poorly sorted and contain greater percentages of gravel.

Geologic cross-sections for the Site are presented in Figures 11 through 16 of the RI Report.

**Site Hydrogeology.** Three major aquifers underlie the Site. The hydrostratigraphic units of concern include the surficial sand, the underlying clay-rich diamict aquitard and the deep sand and gravel.

Slug tests were performed on monitoring wells during the RI to estimate hydraulic conductivity. Resultant hydraulic conductivity estimates, and the conductivity test results obtained from the previous investigations, are presented in the RI Report. Descriptions of the three major geologic units in the vicinity of the Site follow:

- **Surficial Sand** – Water level elevations obtained from the water table wells and standpipes screened in the surficial sand indicate that the water table is near the surface and that the groundwater in the surficial sand is flowing into Sequoit Creek under a shallow hydraulic gradient. The rate of horizontal and vertical groundwater flow in the surficial sand is controlled by the hydraulic gradient and the hydraulic conductivity of the surficial sand. The results of the single well hydraulic conductivity slug tests performed in the surficial sand wells indicate horizontal hydraulic conductivity of the surficial sand ranges from  $2.10 \times 10^{-2}$  to  $3.60 \times 10^{-4}$  centimeters per second (cm/s). Based on the water level elevations obtained from well nests at the Site in June 1993, a very slight downward vertical hydraulic gradient of 0.002 foot per foot was observed from the water table surface to the base of the surficial sand.
- **Clay-Rich Diamict** – The clay-rich diamict acts as an aquitard, separating the surficial sand from the deep sand and gravel. Groundwater movement within the clay-rich diamict is greatly restricted, and primarily downward. The rate of groundwater movement within the diamict is controlled by the hydraulic conductivity of the diamict and the hydraulic gradient across the diamict. The results obtained from the single well hydraulic conductivity slug tests performed in wells screened in the clay diamict indicate horizontal hydraulic conductivity of  $7.9 \times 10^{-6}$  cm/s in one piezometer and  $8.0 \times 10^{-6}$  cm/s in another piezometer. During the RI, laboratory constant head permeability tests results indicated that the vertical and horizontal hydraulic conductivities of the clay-rich diamict are low, and as a result, poor hydraulic communication exists between the surficial sand and the deep sand and gravel. The properties of this soil layer were the basis for IEPA's approval of this site as a suitable location for a solid waste landfill.
- **Deep Sand and Gravel** – The deep sand and gravel aquifer is used for public water supply by the Village of Antioch, and for private well use at nearby residences located east (hydraulically upgradient) of the Site. This deep sand and gravel aquifer occurs beneath the entire Site, based on soil borings drilled during the previous site investigations and the RI. Based on the piezometric head elevation data collected in 1993 and 1994, the groundwater within the deep sand and gravel appears to be flowing from northeast to southwest under a low hydraulic gradient.

### **1.3.3 Site History**

**Ownership.** Permitted waste disposal activities began at the Site in 1963 and continued through 1984. The Site has been owned and/or operated by three distinct companies:

- Cunningham Cartage and Disposal Company (1963 - 1965)
- H.O.D. Disposal, Inc. (1965 - 1972)
- C.C.D. Disposal, Inc. (1972 - present, including merger with WMII).

Murrill Cunningham, owner, operator, and president of Cunningham Cartage and Disposal Company operated a 20-acre landfill (the "old landfill" area) at the Site from 1963 until August 1965. The property was then purchased by John Horak and Charles Dishinger, who operated the Site under the name H.O.D. Disposal, Inc. In December 1972, the 20-acre landfill was conveyed to C.C.D. Disposal, Inc. and C.C.D. Disposal, Inc. purchased the adjacent 60-acres of land to the east of the Site. WMII merged with H.O.D. Disposal, Inc. in December 1972 and C.C.D. Disposal, Inc. in June 1973, gaining ownership of the entire Site. A small portion of the Site is currently owned by the Village of Antioch. WMII operated the landfill from 1973 until 1984 when the Site stopped accepting waste. During the time WMII operated the landfill, portions of the 60-acre property (the "new landfill" area) were opened for landfilling.

**History of Regulatory Agency Response Actions.** In June 1981, WMII submitted to the U.S. EPA a Hazardous Waste Site Notification form, as required by Section 103(c) of CERCLA. The form indicated solvents, heavy metals, and cutting and hydraulic oils may have been disposed of at the Site, in addition to municipal waste.

The U.S. EPA conducted a Preliminary Assessment in 1983, a Site Inspection in 1984, and an Expanded Site Inspection between 1986 and 1989. During that period (1989), the Site was closed, and a landfill cover, leachate wells and LFG vents were installed in accordance with the applicable regulations in force at the time. The Site was placed on the National Priorities List (NPL) on February 21, 1990, based on an HRS score of 34.68 (out of 100), which was above U.S. EPA's eligibility threshold limit of 28.5 for Sites to be proposed for the NPL. The U.S. EPA identified a number of potentially responsible parties (PRPs); however, only WMII agreed to participate in the RI/FS. An Administrative Order on Consent (AOC) was signed between U.S. EPA and WMII in August, 1990.

In May 1990, WMII retained Montgomery Watson (formerly Warzyn) to support WMII's RI/FS effort by preparing the Work Plan for Preliminary Site Evaluation Report/Technical Scope (PSER/TS) and to subsequently perform the RI. The RI was conducted in 1993 and 1994. The final RI Report was approved by the U.S. EPA and IEPA on February 14, 1997. The draft Baseline RA was submitted by ICF Kaiser in 1994. WMII received comments on the Baseline RA from the IEPA in December 1996, and the U.S. EPA in February 1997. WMII addressed the comments to the Baseline RA which was finalized and approved on October 29, 1997.

**Previous Site Investigations.** Several investigations have been conducted at the Site and are listed below in approximate chronological order. Additional details, and the results of the investigations, are described in the RI Report.

- In 1965, prior to drilling and constructing Village Well 4, three test holes (1-65, 2-65 and 3-65) were drilled (to identify adequate thickness of water bearing units) in the Sequoit Acres Industrial Park area.
- A soil investigation was conducted by Testing Services Corporation (TSC) in 1973 to assess conditions for the expansion of the landfill and the construction of an on-site maintenance building.
- TSC installed six groundwater monitoring wells for WMII in May 1974.
- A hydrogeologic report for the proposed landfill expansion to the north was prepared in 1982.
- Five leachate samples were collected from leachate/gas wells (LP1, LP6, LP8, and LP11) and leachate collection manhole East (MHE) on May 12 and 13, 1993. The analytical results and field parameters may be found in Remedial Investigation Appendices 0-3 through 0-7 and Table 2-1, respectively.
- A Preliminary Assessment (PA) was completed on February 11, 1983 by the field investigation team (FIT) at the request of the U.S. EPA. The PA identified several data gaps including determination of waste quantity and information related to possible groundwater or surface water contamination.
- A Site Inspection was conducted on July 10, 1984 by the FIT. Groundwater samples were collected from on-Site monitoring wells. Analysis of groundwater samples, particularly from well G103, reportedly revealed the presence of elevated concentrations of zinc, lead, and cadmium. Analysis of surface water samples did not reveal elevated levels of analyzed parameters.
- Dames and Moore conducted a hydrogeologic assessment of the Site in 1985 at the request of WMII.
- In January 1986, IEPA collected groundwater samples from four residential wells located east of the Site. The samples were analyzed for nitrates, organic compounds and trace metals. The results of the chemical analysis indicated no trace metals and no organic compounds were detected.
- An Expanded Site Investigation (ESI) was conducted by the FIT (Ecology and Environment, 1989) during the period 1987 through 1989.
- Between 1989 and July 1990, P.E. LaMoreaux & Associates, Inc. (PELA), on behalf of WMII, conducted various site investigations.

- Video camera logging of Village Well 4 was conducted by PELA. Some areas of the well appeared to be badly pitted.
- Patrick Engineering, Inc. (Patrick) prepared an Environmental Audit of Sequoit Acres Industrial Park in 1989 on behalf of WMII. Patrick concluded that several potential sources of soil and/or groundwater contamination existed in the Sequoit Acres Industrial Park, including industry and landfilled areas containing both fill and refuse.
- Shallow borings were drilled at three locations in October 1989 by Patrick for Geoservices Inc. of Boynton Beach, Florida to collect samples of the clay diamict for laboratory permeability testing. Hydraulic conductivity values for the clay soils ranged from  $2.1 \times 10^{-7}$  cm/sec to  $9 \times 10^{-9}$  cm/sec. Results of the permeability testing of the clay diamict soils are summarized in Table 5 of the PSER/TS.
- Five temporary leachate piezometers were installed at the "old landfill" for WMII by Stratigraphics, Inc. on July 24 and 25, 1990. Leachate samples were collected for laboratory analysis from temporary leachate piezometers in July and August 1990. The Stratigraphics report indicated clay underlies refuse at each of the temporary leachate piezometer locations. Leachate samples were collected for laboratory analysis from temporary leachate piezometers TLP1 through TLP4 on July 27, 1990. Samples were collected from TLP2, TLP4, and TLP5 on August 10, 1990. Samples were analyzed for organics, metals and indicator parameters. Low levels of VOCs (primarily alkenes and aromatics) were detected in each of the leachate samples. Few detections of SVOCs were noted in the leachate samples, with naphthalene being the most commonly detected of the SVOCs. The RI presented specific leachate analytical data.
- A Hydropunch groundwater sample was collected near monitoring well US4S in May 1990. The sample was collected from a fine to medium sand at a depth of 20 to 21 feet below ground surface and was submitted for VOC analysis. VOCs detected in the groundwater sample included cis-1,2-DCE (110.3 ug/L), trans-1,2-DCE (1.4 ug/L), methylene chloride (2.7 ug/L) and vinyl chloride (188.4 ug/L).
- Groundwater quality samples were collected by WMII at ten on-site monitoring wells on July 1990. Samples were analyzed for organics, metals and groundwater quality indicator parameters. Analytical results indicates that VOCs were only detected in samples collected from wells US4S (cis-1,2-DCE @ 39.7 ug/L; trans-1,2-DCE @ 1.8 ug/L), US6D (TCE @ 0.7 ug/L) and R103 (cis-1,2-DCE @ 0.5 ug/L; TCE @ 4 ug/L).
- Leachate results from the 1996 and 1997 semi-annual compliance reports can be summarized by ranges as follows: barium from 736 to 837 ug/L, chromium from 12.3 to 20.5 ug/L, iron from 6,680 to 11,600 ug/L, lead from 5.0 to 7.1 ug/L, magnesium from 118,000 to 139,000 ug/L, zinc from 21.9 to 49.5 ug/L, 1,1-dichloroethane 6 ug/L, 1,2-dichloroethane from 6 to 13 ug/L, 1,2-dichloropropane

from 9 to 17 ug/L, benzene from 12 to 19 ug/L, ethylbenzene from 22 to 41 ug/L, methylene chloride from 8 to 26 ug/L, toluene from 140 to 210 ug/L, trichloroethene from 7 to 9 ug/L and vinyl chloride from 11 to 15 ug/L.

- The U.S. Geological Survey (USGS), in cooperation with the U.S. EPA, performed an evaluation of the aquifer pump test data collected during the ESI Report and presented the results in a report titled "Determination of Hydraulic Properties in the Vicinity of a Landfill Near Antioch, Illinois" (USGS, 1990).

#### **1.3.4 Local Demography and Land Use**

The Site is bordered on the south and west by Sequoit Creek. Silver Lake is located approximately 200 feet southeast of the Site. The Silver Lake residential subdivision is located east of the Site and agricultural land, scattered residential areas, and undeveloped land are located to the north. A large wetland area extends south of the Site from Sequoit Creek. A large industrial park area (Sequoit Acres Industrial Park), which was constructed on former landfill and fill areas, is located west of the Site and borders Sequoit Creek.

Sequoit Acres Industrial Park includes at least six companies designated as small quantity hazardous waste producers, five registered underground storage tanks ranging in size from 60 gallons to 200,000 gallons, and fill areas that were, at least in part, waste dumps (Cunningham Dump and Quaker Dump). Companies designated as small quantity hazardous waste producers include:

- Quaker Industries
- Chicago Ink and Research Company, Inc.
- Galdine Electronics, Inc.
- Major Industrial Truck, Inc.
- Nu-Way Speaker Products, Inc.
- Roll Foil Laminating, Inc.

Patrick has investigated the development and environmental history of the Sequoit Acres Industrial Park (Patrick, 1989).

**Water Supply and Groundwater Use.** The Village of Antioch obtains its water from six water supply wells screened in the deep sand and gravel. Under normal operating conditions, the Village wells are automatically activated in alternating cycles when the water pressure from aboveground water storage tanks drops below a designated level. The Village wells are located west and southwest of the Site. The closest Village well, VW4, was taken out of service and replaced with a new village well, VW7, in June, 1997. The location of VW7 is shown on Figure 6.

Privately owned wells in the vicinity of the Site (i.e., Silver Lake residential subdivision) are either screened in the same deep sand and gravel used by the Village of Antioch, or the deeper underlying dolomite. These private wells are located hydraulically upgradient from the Site. These wells are finished at depths ranging from approximately 85 to 250 feet.

Household wastewater from the Silver Lake subdivision (east of the Site) is discharged to septic systems.

#### **1.4 NATURE AND EXTENT OF CONTAMINATION**

The following media were sampled during the RI: groundwater (from Site and nearby monitoring wells, Village wells, and private wells), leachate, landfill gas, surface water, sediments, and surface soils. A monitoring well and piezometer location map is included as Figure 3. Leachate piezometer and gas probe locations are shown on Figure 4. Figure 5 shows surface water, sediment, and surface soil sampling locations. The Village of Antioch and private water supply well sampling locations are presented in Figures 6 and 7, respectively. Tables 1-1 through 1-7 present summaries of analytical results for sampling conducted during the RI. Table 1-8, a summary of historical monitoring well Volatile Organic Compound (VOC) data, has also been included. Based on this sampling and analysis, VOCs are potential contaminants of concern at the Site.

##### **1.4.1 Surficial Sand**

The groundwater samples collected from wells screened in the surficial sand immediately adjacent to the "old landfill" area in which VOCs were detected were found to only contain relatively low concentrations of alkenes and carbon disulfide. (Carbon disulfide was detected during the RI in the Round 1 and Round 2 samples collected from well G11S at concentrations of 0.8J ug/l and 18 ug/l, respectively. 1,2-Dichloroethene was detected during the RI in the Round 1 and Round 2 samples collected from well US4S at concentrations of 35 ug/l and 44 ug/l, respectively.)

VOCs were not detected in the surficial sand wells located on the west or south sides of Sequoit Creek during either of the two rounds of groundwater samples obtained as part of the RI. For further information on specific contaminant data, refer to Section 4.3.1.1 in the RI.

##### **1.4.2 Clay Diamict**

Trichloroethene (TCE) was detected in one groundwater monitoring well (US6I) which is located in the clay diamict at the southeast corner of the "old landfill" area. The TCE concentrations in groundwater samples collected from that monitoring well since 1987 exhibit a decreasing trend. For further information on specific contaminant data, refer to Section 4.3.1.2 in the RI.

##### **1.4.3 Deep Sand and Gravel**

VOCs were not detected in the on-site deep sand and gravel wells. Current data are not conclusive as to the source of the VOCs detected in two off-site deep sand and gravel wells. For further information on specific contaminant data, refer to Section 4.3.1.3 in the RI.

VOCs (vinyl chloride and 1,2-dichloroethene) were detected in groundwater samples from one deep sand and gravel monitoring well (US3D), which is located off-site in the

industrial park to the west. VOCs (vinyl chloride, acetone and 1,2-dichloroethene) were also detected in one water supply well, Village Well 4 (VW4), which was the closest Village well to the Site. It should be noted that Vinyl Chloride in VW4 was last detected on August 23, 1989, at 0.2 µg/L, and has not been detected in 24 samples collected from this well since. As mentioned previously, VW4 has been taken out of service, and replaced with VW7.

The detection and potential origin of the VOCs at VW4 (within the deep sand and gravel aquifer) were evaluated during the RI. The results of the investigations were not conclusive. VW4 was installed c. 1965 and was apparently constructed through the refuse material of the Cunningham Dump.

Although VOCs were detected in the on-site surficial sand wells, they were not present in the on-site deep sand and gravel wells, indicating that downward migration of VOCs from the surficial sand through the clay diamict does not appear to be occurring. The differences in the hydraulic heads from the surficial sand and the deep sand and gravel also indicate that the clay diamict is continuous and provides resistance to downward vertical flow (i.e., low vertical hydraulic conductivity).

#### **1.4.4 Sequoit Creek Surface Water Results**

VOCs (2-Hexanone and 4-methyl-2-pentanone) were detected in one surface water sample which was collected from Sequoit Creek during Round 1. This sample was collected adjacent to the northwest corner of the landfill. No other VOCs, SVOCs or Pesticides/PCBs were detected in any of the other Round 1 or Round 2 samples. For further information on specific contaminant data, refer to Section 4.5 in the RI.

The concentrations of inorganic constituents detected in the surface water samples are much lower than the concentrations detected in the leachate samples. Results presented in the RI indicate that Site leachate has not had a detectable effect on Sequoit Creek surface water quality.

#### **1.4.5 Sequoit Creek Sediment Results**

No VOCs or pesticides/PCBs were detected in the sediment samples collected from the creek. The SVOCs that were detected consisted of polynuclear aromatic hydrocarbons (PNAs), with the exception of bis(2-ethylhexyl) phthalate, which is a common laboratory contaminant. The PNAs could be due to other industrial sources, as they are common to urban industrial areas. For further information on specific contaminant data, refer to Section 4.6 in the RI.

#### **1.4.6 Surface Soils Results**

Surface soil samples during the Round 1 sampling activities were collected from areas exhibiting discolored soils, leachate seeps, stressed vegetation, or standing water. These locations were chosen as "worst case" samples in order to document the potential effects of the Site's LFG and leachate on the shallow surface soils of the Site.



The analytical results generally indicate that concentrations of VOCs (primarily aromatics and methylene chloride/acetone) and SVOCs (primarily phthalates and PNAs) are present, in areas with visible evidence of potential impact. No VOCs, and few SVOCs, were detected in a sample collected from an off-site location north of the "new landfill" in an area of standing water and apparent stressed vegetation. Similarly, fewer VOCs and SVOCs were detected off-site in a sample collected from a wetland area near the southeast corner of the "old landfill" and a sample collected from the wetland area east of the "new landfill." For further information on specific contaminant data, refer to Section 4.7 in the RI.

## **1.5 CONTAMINANT FATE AND TRANSPORT**

While a quantitative evaluation and modeling of fate and transport potential is beyond the scope of this FS, some general statements can be made based upon observed site conditions, known chemical properties, and calculated retardation factors presented in the RI. This section identifies potential migration pathways, briefly describes associated attenuation mechanisms, and describes the fate and transport of specific contaminants found in various media and in the immediate vicinity of the Site.

### **1.5.1 Primary Transport Pathways of Contaminants of Concern**

Migration pathways are defined as routes along which contaminants migrating out of, and away from, a contaminant source (e.g., landfill leachate, LFG) travel towards groundwater, surface soil, surface water, and sediments. The primary vehicle for mobilization of VOCs is partitioning of contaminants from LFG into the leachate and interstitial water in the waste. The primary transport mechanism from the source areas is via LFG, leachate, or groundwater migration.

LFG generation in the reducing environment of the landfill is largely the byproduct of anaerobic decomposition of the refuse. Gas pressure within the landfill builds and gas migrates away from the waste mass through the path of least resistance. Passive gas flares have been installed in the landfill to vent and burn off this gas but are not totally effective. Therefore, some LFG appears to be migrating horizontally and vertically through the surface soils in some locations.

Leachate is produced through the solution and suspension of chemicals mobilized by the interaction of the interstitial water with the waste mass and LFG. The water necessary for the formation of leachate may enter the landfill interior in the following ways: 1) stormwater infiltration through the cover, 2) groundwater seepage through the subsurface, and 3) moisture present within the waste at the time of placement within the landfill.

Leachate may migrate out of the landfill in the following ways:

- Release and transport by groundwater.
- Release directly to surface water and sediments.
- Release through the landfill cover and potential release to the surface soils, surface water and sediments.

### **1.5.2 Attenuating Effects**

Potential chemicals of concern in landfills, such as those at the Site, can be mobilized by the interstitial water passing through the waste and dissolving chemicals which forms leachate and by chemicals in LFG partitioning into the leachate. This leachate may then migrate from a landfill to affect potential receptors.

However, a landfill itself functions as a bioreactor, where the organic substrate (the organic fraction of the waste mass), in the presence of moisture, produces an anoxic (reducing) environment which degrades organic compounds and stabilizes the waste mass. This reaction produces LFG, which is primarily a combination of methane and carbon dioxide, with trace concentrations of VOCs.

The potential transport of the chemicals of concern to groundwater may be minimized by the low permeability clay underlying the waste, similar to the clay underlying the entire Site, and by the organic materials and peat, similar to that underlying areas of the southern portion of the "old landfill." Low permeability clay materials and peat and organic materials have a high capacity to adsorb the potential chemicals of concern, thereby helping to significantly reduce the concentrations of chemicals entering the groundwater. Further attenuation occurs by mixing, adsorption/desorption, biodegradation, oxidation and reduction reactions, precipitation, and volatilization as groundwater moves away from a landfill.

### **1.5.3 Fate and Migration of Site Contaminants in the Subsurface Landfill Gases.**

Once generated, LFG migrates from areas of high gas pressure to areas of low pressure (above the fluid levels in the landfill) and is flared (combusted) or emitted to the ambient air via the following release pathways:

- Leachate piezometer/gas wells
- Unlit gas flares
- Fissures in the landfill cover.

The ensuing dilution of the gas in the air is affected by wind speed, turbulence, temperature, height of the release point above the surrounding area, the roughness of the surrounding area, and by decomposition through direct photolysis.

Some LFG chemical constituents commonly partition into the soil (including the landfill cap) or vadose zone interstitial soil water. The infiltration of this vadose zone water presents a potential transport pathway for LFG chemical constituents to enter the leachate and eventually the surficial sand aquifer. This mechanism can contribute to leachate and/or groundwater contamination.

**Organic Compounds in Leachate.** Leachate samples collected from the Site contained a variety of chemical compound groupings, including chlorinated alkanes and alkenes, ketones, aromatics, phenols, phthalates, PNAs, and PCBs.

The biodegradation of refuse (waste) materials in a reducing environment produces various chemical degradation compounds in the leachate. The biodegradation process may consume much of the organic contaminant mass and produce ammonia, methane, CO<sub>2</sub>, and other anaerobic biodegradation and abiotic intermediate and end products. These compounds are detected in the landfill leachate and gas, and indicate that a high level of anaerobic biodegradation is occurring.

Storm water percolating vertically through the landfill cap into the waste mass and groundwater flowing horizontally into the waste mass provides the transport and mixing vehicle that promotes anaerobic biological and abiotic degradation of the chemical compounds. During this process, some of the compounds and degradation products remain or are introduced into the liquid leachate, while other compounds partition into the gas phase. The chlorinated alkenes and alkanes which were detected in the leachate tend to biodegrade more readily under the reducing conditions present in the landfill.

Leachate may migrate from the waste mass into the surrounding subsurface soils or groundwater, or may enter the ambient environment via surface seeps as described at the end of this section. As leachate moves from the waste mass, conditions become less anaerobic (i.e., less reducing), providing an environment more favorable to aerobic degraders. It is under these conditions that the phenols, ketones, aromatics, and to a lesser degree the PNAs and phthalates will be more readily biodegraded.

In addition to biodegradation, adsorption occurs in both the waste mass and in the subsurface environment as leachate moves through the system. Adsorption is a significant attenuation mechanism for the relatively less-soluble and less-degradable leachate constituents such as the PNAs, phthalates, and PCBs. Leachate from the landfill can mix with, and be transported by, groundwater wherein dilution and groundwater attenuation processes may also influence contaminant concentrations.

In addition to subsurface movement, a leachate seep was observed in an erosional cut in the cover near the center of the south slope of the "new landfill". The leachate flows from the landfill and down the erosional cut towards the base of the landfill where standing water was periodically observed during wet seasons.

**Inorganics in Leachate.** Relatively higher concentrations of metals were detected in the leachate than in the surrounding groundwater, soils, surface water or sediments. The concentrations of metals detected in the leachate are all below (except for barium) the IEPA-specified typical range of values for leachate from municipal solid waste landfills. Table 4-2 of the RI presents IEPA's list of general values for municipal solid waste landfills. Metals in leachate can migrate into the ambient environment along the same pathways described above. Metals concentrations in leachate tend to increase as metal complexes dissolve into leachate from the waste mass under highly reducing anaerobic biodegradation conditions present in the landfill. These conditions are not suitable for metals precipitation which would reduce the metals concentrations in the leachate. Concentrations of metals in leachate that migrates to the surface and subsurface environments is attenuated through dilution, adsorption, precipitation and

oxidation/reduction. Concentrations of metals in the leachate will drop rapidly when exposed to oxygen, as metal complexes form. For further information on specific contaminant data, refer to Section 4.1.4.1 and 4.1.4.4 in the RI.

**Organics in Groundwater – Surficial Sand/Clay Till.** VOCs were detected in groundwater samples from the on-site surficial sand monitoring wells. Shallow groundwater within the surficial sand flows toward, and discharges to, Sequoit Creek. Strong horizontal gradients are present in the surficial sand and result in rapid ground water flow (4 to 215 ft/yr). Groundwater elevation data also indicate the presence of a very slight downward vertical gradient within the surficial sand aquifer and the clay-rich diamict aquitard. However, the RI data indicate that the hydraulic conductivity of the surficial sand is more than two orders of magnitude greater than that of the clay-rich diamict. Therefore, dissolved constituents will readily migrate horizontally toward Sequoit Creek rather than vertically into the clay aquitard.

Based on the information presented, groundwater flow and contaminant migration in the vicinity of the southeast and southwest corners of the “old landfill” is toward Sequoit Creek, with the shallow groundwater discharging to the Creek. Refer to Figures 21 and 22 (Surficial Sand) and 26 and 27 (Deep Sand and Gravel) of the RI for groundwater flow directions. The surface water and sediment analytical results indicate that the contaminants detected in on-site shallow groundwater samples are not detected in the Creek.

Trichloroethene was detected at one Site well in the clay till aquitard. This compound will migrate slowly with groundwater flow in the clay till. Groundwater flow is slow, and predominantly downward, through the low permeability clay aquitard under the existing hydraulic gradient. The attenuation of organic and inorganic contaminants is high within the clay, primarily through adsorption. Further dilution and biodegradation can also occur, although biodegradation is probably limited within the clay till.

**Organics in Groundwater – Deep Sand and Gravel.** The contaminants of concern selected for the Baseline RA were only detected in the off-site deep sand and gravel aquifer at the three Village wells, VW3, VW4, and VW5, and at monitoring well US3D. The organic contaminants of concern detected in the first round samples collected from the Village wells included carbon disulfide, 2-methylphenol, and 4-chloroaniline. During the second round of sampling, detected contaminants of concern included acetone, chloroform, cis-1,2-dichloroethene, and 1,2-dichloroethane. The general lack of consistency in detections from these wells may indicate the lack of a definite source area for these contaminants in the Village wells. The organic contaminants of concern detected in monitoring well US3D included vinyl chloride and 1,2-dichloroethene in both sampling rounds.

The contaminants detected in the deep sand and gravel can be transported with groundwater flow in the deep sand and gravel at a flow velocity between 3 and 8 ft/yr. These contaminants are attenuated through dilution, biodegradation and adsorption.

**Inorganics in Groundwater.** Arsenic was detected in samples from municipal wells VW-3 and VW-5, but based on the background and downgradient data, arsenic is not an analyte associated with the Site. Beryllium was also detected in the off-site surficial sand aquifer. However, beryllium was identified as a compound of potential concern only because background data for beryllium was not available. Beryllium was only detected in only one of four groundwater samples from the off-site surficial sand aquifer. It is possible that this concentration of beryllium is naturally-occurring in the surficial sand aquifer. Beryllium was not detected in samples from the on-site monitoring wells screened in the surficial sand aquifer, and thus does not appear to be associated with the Site.

**Surface Water.** Surface water does not appear to have been affected by the landfill. Low concentrations of two ketone compounds were detected in one surface water sample. These compounds were not detected in the second round of surface water sampling. As previously discussed, these compounds would be significantly attenuated by absorption, dilution and volatilization in surface water.

Inorganic contaminants of concern in the surface water included antimony, barium, and lead. These metals in the surface water would also attenuate through dilution, adsorption to particulate matter and precipitation along the pathways discussed in Section 1.5.1.

**Sediments.** SVOCs were the only compounds detected in two of the sediment samples collected from Sequoit Creek along the perimeter of the "old landfill." The primary transport mechanism for the migration of these organic compounds from the landfill to the Sequoit Creek sediments could be migration and discharge of groundwater to Sequoit Creek. The detections of these compounds could also be due to sources other than the Site. SVOCs are attenuated by dilution and biodegradation and are adsorbed to soils and sediments. Once entrained in the soils and sediments, these organic compounds will either be consumed through biodegradation or will be released to surface water and groundwater and further attenuated by dilution.

As described in the Baseline RA, the metals detected in sediments are arsenic and thallium. These metals are attenuated through adsorption and precipitation as they migrate through the pathways discussed in Section 1.5.1. The metals can be released to the surface water under physical agitation or can be dissolved into surface water through the reduction of the metals in a reducing sediment environment. Once in the surface water, oxidation is likely to cause the metal complex to precipitate and be transported with surface water flow.

**Surface Soils.** The surface soil organic and inorganic impacts on the Site appear to be primarily related to localized LFG and leachate seeps through the landfill cap. As the leachate and LFG migrates through the cover material, many VOCs are volatilized into the air. Other less volatile and inorganic constituents are adsorbed to the surface soils. Precipitation may then transport these constituents to surface water and/or groundwater through overland run-off and infiltration.

Phthalates detected in the surface soils are strongly adsorbed to the organic materials in the soils, and thus will resist leaching into the groundwater. To a limited extent, biodegradation may also occur in surface soils. PNAs found in the surface soils are also strongly adsorbed to soils, have low water solubilities, and are therefore not expected to be mobilized by precipitation. Under aerobic conditions PNAs will undergo natural biodegradation. The inorganics determined to be contaminants of concern in the Baseline RA were selected due to the lack of regional background data. These metals are attenuated in the surface soils. Precipitation and oxidation also occur as the metal complexes are exposed to the atmosphere.

## **1.6 SUMMARY OF THE BASELINE RISK ASSESSMENT**

The Baseline RA was developed in accordance with the techniques described in the U.S. EPA's Baseline RA Guidance, and as subsequently modified by the U.S. EPA's "presumptive remedy for CERCLA Municipal Landfill Sites" September, 1993 (EPA 540-F-93-035). The presumptive remedy approach streamlines the process of identifying the need for, and nature and extent of, landfill site remediation. Through discussions with U.S. EPA Region V, the presumptive remedy guidance was interpreted to mean that the Baseline RA need not evaluate potential risks to a hypothetical future on-site resident. Rather, the need for on-site remediation was assessed in the Baseline RA by comparing the on-site groundwater concentrations to Safe Drinking Water Act Maximum Contaminant Levels (MCLs), non-zero MCL Goals (MCLGs), and the available Illinois drinking water standards. Consistent with a more traditional approach, the Baseline RA also addressed potential human health and environmental impacts associated with the presence, or possible migration, of site-related chemical contaminants from the landfill. ICF Kaiser Engineers, Inc. (ICFKE) and the Weinberg Consulting Group, Inc. (Weinberg Group) prepared the Baseline RA. The IEPA and U.S. EPA reviewed and commented on the Baseline RA, and U.S. EPA approved the final Baseline RA on October 29, 1997.

The Baseline RA was conducted to characterize the current or potential future threat to human health and the environment that may be posed by chemicals originating at, or migrating from, the Site. The Baseline RA was based on data and information obtained during the RI and during a separate site visit.

The first step in the risk assessment process was to select appropriate chemicals of potential concern, evaluate data from the RI, and include a consideration of naturally occurring background chemical concentrations in the soils and groundwater. The next step was to identify potential and complete pathways of concern to human health. The following pathways were selected for detailed evaluation:

- Incidental ingestion of on-site surface soil by trespassers on the Site.
- Dermal absorption of chemicals in on-site surface soil by trespassers on the Site.

- Dermal absorption of chemicals in Sequoit Creek surface water by trespassers on the Site.
- Incidental ingestion of Sequoit Creek sediment by trespassers on the Site.
- Dermal absorption of chemicals in Sequoit Creek sediment by trespassers on the Site.
- Groundwater ingestion from public water supply wells by nearby adult residents.
- Groundwater ingestion from private wells by nearby adult residents.
- Groundwater ingestion from off-site groundwater monitoring wells by nearby adult residents (surficial sand and the deep sand and gravel aquifers).
- Inhalation of volatile organic chemicals while showering with groundwater from public water supply wells by nearby adult residents.
- Inhalation of volatile organic chemicals while showering with groundwater from the off-site deep sand and gravel aquifer by nearby adult residents.
- Dermal absorption while showering with groundwater from public water supply wells by nearby adult residents.
- Dermal absorption while showering with groundwater from private wells by nearby adult residents.
- Dermal absorption while showering with off-site groundwater (surficial sand and the deep sand and gravel aquifers) by nearby adult residents.
- Inhalation of volatile organic chemicals emitted from the landfill surface by nearby residents.

Potential exposures within each identified pathway scenario were then calculated using reasonable maximum exposure (RME) protocols, as is the U.S. EPA-accepted method for a Baseline RA. This method produced a conservative estimate of risks at the Site.

Chemical concentrations at the potential points of exposure were calculated and combined with information on the magnitude, frequency, and duration of potential exposures. Mathematical models were used to estimate exposure point concentrations in indoor air while showering and in ambient air from LFG emissions. Once this step was completed, RME excess lifetime cancer risks and RME hazard indices were calculated for the predominant chemicals in each exposure pathway.

A summary of the Baseline RA results is shown in Table 1-9. Only one chemical in one pathway, ingestion of vinyl chloride from the off-site deep sand and gravel aquifer

groundwater, exceeded the established cancer risk guideline ( $1 \times 10^{-4}$ ) used to determine if remedial action generally is warranted. The excess lifetime cancer risks from inhalation and dermal absorption of vinyl chloride while showering with off-site deep sand and gravel collectively add a risk of  $9 \times 10^{-5}$  to the ingestion risk of  $8 \times 10^{-4}$ . Other chemicals that posed an excess lifetime cancer risk greater than  $1 \times 10^{-6}$  were:

- Beryllium – ingestion and dermal absorption while showering with off-site surficial sand and gravel aquifer groundwater
- Arsenic – ingestion of municipal well water
- Beryllium – dermal absorption from surface soil

RI data regarding the location, frequency, and magnitude of detection of vinyl chloride, beryllium, and arsenic did not conclusively establish the locational origin of the contaminants. In accordance with the Technical Work Plan for the Baseline RA, the concentrations of chemicals in on-site groundwater were compared to federal and State standards and guidelines. Thallium, manganese, and vinyl chloride exceeded established standards as described in the Baseline RA. However, thallium and vinyl chloride were only detected in one sample out of three and one sample out of twelve, respectively.

An ecological risk assessment was also conducted to evaluate potential impacts on nonhuman receptors associated with the Site. The evaluation showed that potential risks to plants, aquatic life, and terrestrial wildlife were minimal.

In summary, the Baseline RA evaluated risks to human health from potential and complete pathways. These pathways included various exposure scenarios from surface soil, surface water, sediment, groundwater from public and private wells, and groundwater from off-site wells. Only one exposure scenario, ingestion of vinyl chloride from the off-site deep sand and gravel aquifer groundwater, exceeded the  $10^{-4}$  risk range used by U.S. EPA to determine if remedial action generally is warranted. It should be noted that the only exposure scenario that exceeded the established risk guidelines (the ingestion of vinyl chloride from the off-site deep sand and gravel aquifer groundwater) is unlikely because use of groundwater from the Site vicinity has been eliminated by the Village of Antioch ordinance (Antioch Water Works and Sewage Ordinance Sections 50.008, 52.009, and 52.011) requiring properties within the Village limits to connect to the municipal water supply system and the fact that VW4 has been taken out of service.





## **2.0 DEVELOPMENT OF REMEDIAL ACTION ALTERNATIVES**

The primary objective of this phase of the FS is to develop appropriate remedial action alternatives that will be analyzed fully in the subsequent detailed evaluation phase of the FS (see Section 4). Appropriate remedial alternatives are developed by assembling combinations of technologies, and the media to which they would be applied, into alternatives that would address the identified Site conditions and risks. The NCP provides considerable latitude regarding the scope of this screening and development phase. As stated in the NCP §300.430(a)(1)(ii)(C): "Site-specific data needs, the evaluation of alternatives, and the documentation of the selected remedy should reflect the scope and complexity of the site problems being addressed." The NCP preamble discussion states that it is U.S. EPA's intent to balance the desire for definitive site characterization and alternatives analysis with a bias for initiating response actions as early as possible. The preamble emphasizes the principle of streamlining, which the U.S. EPA applies in managing the Superfund program as a whole, and in conducting individual remedial action projects. In accordance with the principle of streamlining, an alternatives screening step may be deemed unnecessary prior to detailed analysis. Of particular relevance for this FS is the fact that U.S. EPA has developed presumptive remedies for CERCLA municipal landfill sites. It is U.S. EPA's intent to use presumptive remedies to accelerate site-specific analysis of remedies by focusing feasibility study efforts. According to U.S. EPA guidance, use of the presumptive remedy approach eliminates the need for the initial step of identifying and screening a variety of alternatives during the FS. This FS will use presumptive remedy guidance to greatly simplify the technology identification and screening process.

To develop remedial action alternatives, remedial action objectives and applicable or relevant and appropriate requirements (ARARs) must be established. Remedial action objectives are requirements for the Site that provide adequate protection of human health and the environment. ARARs are standards, standards of control, and other substantive environmental protection requirements, criteria, or limitations promulgated under federal or state law that specifically address a hazardous substance, pollutant, contaminant, remedial action, or other circumstances.

### **2.1 REMEDIAL ACTION OBJECTIVES**

Remedial action objectives provide the foundation upon which remedial cleanup alternatives are developed. Remedial action objectives should reflect U.S. EPA's remedy selection expectations, as presented in NCP §300.430(a)(1)(iii). Where practicable, U.S. EPA expects to treat principal threats, employ engineering controls (e.g., containment) for low-level threats, use institutional controls to supplement engineering controls, and restore usable groundwaters to beneficial uses. Site-specific objectives usually relate to specific contaminated media (such as groundwater or soil), potential exposure routes, and to the identification of target remediation levels. Site-specific objectives are based on the

evaluation of risks to human health and the environment, identified in the Baseline RA, and are established in consideration of the ARARs.

### **2.1.1 NCP and CERCLA Goals**

The following two goals constitute the general objectives for remedial actions at all CERCLA sites.

1. The NCP states: "The appropriate extent of remedy shall be determined by the lead agency's selection of a cost-effective remedial alternative that effectively mitigates and minimizes threats to and provides adequate protection of public health and the environment" (40 CFR 300.68 (i)). For the H.O.D. Landfill Site, the lead agency is U.S. EPA.
2. The statutory scope of CERCLA was amended in 1986 by SARA to include the provision that the selected remedy must comply with or attain the level of any "standard, requirement, criteria, or limitation under any Federal environmental law or any promulgated standard, requirement, criteria, or limitation under a State environmental or facility siting law that is more stringent than any federal standard, requirement, criteria, or limitation" [Section 121(d)(2)(A)].

U.S. EPA has developed presumptive remedies for CERCLA municipal landfill sites. Presumptive remedies are preferred technologies for common types of sites, based on historical patterns of remedy selection and U.S. EPA's own evaluation of performance data. It is U.S. EPA's intent to use presumptive remedies to accelerate site-specific analysis of remedies by focusing feasibility study efforts. This presumptive remedy approach was used to streamline the selection of remedial alternatives for the H.O.D. Site. According to U.S. EPA guidance, the presumptive remedy for CERCLA municipal landfill sites is containment.

In addition, U.S. EPA guidance for municipal landfill sites explains that the decision to characterize and treat hot spots in a landfill should be based on whether the combination of the waste's physical and chemical characteristics and volume is such that the integrity of the containment system will be threatened if the waste is left in place. This decision is to be based on available site information. Based on historical records and the results of the RI and Baseline RA, no leachate hot spots were identified and therefore the characterization and treatment of hot spots is not supported at the H.O.D. Site for the following reasons:

- The estimated volume of in-place waste is approximately 1.5 million cubic yards.
- There is no evidence to suggest that hazardous wastes were disposed in localized areas within the landfill.
- Concentrations of contaminants of concern detected in on-site soils and groundwater did not exceed cancer risk guidelines used to determine if corrective action generally is warranted. However, off-site groundwater contaminant concentrations exceeded such guidelines.

Thus, well-defined hot spots are not apparent at the site and the integrity of the containment alternatives described in Section 3 will not be threatened if the waste is left in place.

### **2.1.2 General Site Response Action Objectives**

The Baseline RA was developed using the U.S. EPA's "Presumptive Remedy for CERCLA Municipal Landfill Sites," September 1993 (EPA 540-F-93-035) which identifies containment as the presumptive remedy. The State of Illinois 35 IAC 807 and 811 General Standards for Landfills were also used to establish the following general response action objectives:

- Preventing direct contact (dermal contact or ingestion) with impacted soil and landfill contents.
- Controlling infiltration and contaminant leaching to groundwater.
- Preventing inhalation and controlling fugitive vapors and dust.
- Controlling surface water runoff and erosion.
- Preventing migration of contaminants from source areas.
- Controlling and treating landfill gases (LFG).

Preventing direct contact with soil and waste, and controlling infiltration and leachate generation are typically addressed by capping the Site and by applying institutional controls. The control of leachate and LFG are typically addressed by installing and operating engineered leachate and gas collection systems. These three components have already been implemented with varying degrees of effectiveness at the Site during initial closure activities in 1989. The only risk greater than  $1 \times 10^{-4}$  presented in the Baseline RA was associated with the presence of vinyl chloride in the deep sand and gravel aquifer. It should again be noted that the source of this vinyl chloride may not be the H.O.D. Landfill. However, if the landfill is a contributor of vinyl chloride to the groundwater, the most effective way to control further release of this and other volatile organic compounds to the groundwater is to control the LFG and leachate within the waste mass. Many professional papers (Fenestra, 1992, Barber et al., 1990) and textbooks (Bagchi, 1994, Academic Press) have been published explaining the effect of dissolution of LFG contaminants into leachate and groundwater. Therefore, to reduce the potential for this phenomenon, various improvements on the existing cap, LFG control system and leachate collection system could be implemented in order to enhance their effectiveness.

The VOCs found in the surficial sand were not found to be migrating off-site, indicating that active groundwater controls in the off-site surficial sand aquifer is not needed. However, potential future release of VOCs to the on-site surficial sand would also be further controlled by enhancements to the existing LFG and leachate collection systems.

Control of surface water runoff and erosion are usually addressed by constructing and maintaining silt checks, sediment basins, and establishing vegetation. Prevention of fugitive vapors and dust is usually accomplished by watering construction areas for dust control during construction, and maintaining the vegetation and soil cover on the site.

## **2.2 APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS (ARARs)**

The 1986 SARA adopted and expanded a provision in the 1985 NCP which stated that remedial action must at least comply with ARARs. Amendments in SARA also require compliance with federal and state ARARs, such as state environmental or facility siting laws, whenever the state requirements are promulgated, more stringent than federal laws, and identified by the state in a timely manner.

Generally, laws and regulations adopted at the state level, as distinguished from the regional, county or local level, are considered as potential state ARARs. Local laws, in themselves, are not ARARs, unless they are both adopted and legally enforceable by the state (OSWER publication 9234.2-05/FS, December 1989).

### **2.2.1 Definitions of ARARs**

Applicable requirements are standards, standards of control, and other substantive environmental protection requirements, criteria, or limitations promulgated under federal or state law that specifically address a hazardous substance, pollutant, contaminant, remedial action, or other circumstance. For a requirement to be applicable, the remedial action or the circumstances at the Site must satisfy all of the jurisdictional prerequisites of that requirement. For example, the requirements governing construction in a floodplain would only be applicable if construction of a remedial alternative actually encroached into a floodplain.

Relevant and appropriate requirements are standards, standards of control, and other substantive environmental protection requirements, criteria, or limitations promulgated under federal or state law that, while not applicable to a CERCLA site, address problems or situations sufficiently similar to those encountered at the Site. In some circumstances, a requirement may be relevant to the particular site-specific situation but will not be appropriate because of differences in the purpose of the requirement, the duration of the regulated activity, or the physical size or characteristic of the situation it is intended to address. There is more discretion in the determination of relevant and appropriate requirements than in the determination of applicable requirements. Therefore, it is possible for only a part of a given requirement to be relevant and appropriate.

Additional factors to consider when evaluating whether or not a requirement is potentially relevant and appropriate are whether the requirement is substantive or administrative, and whether the action is an on-site or off-site activity. Substantive requirements are those that pertain directly to actions or conditions in the environment. Administrative requirements are those mechanisms that facilitate the implementation of the substantive requirements of a statute or regulation. In general, administrative requirements prescribe methods and procedures (such as fees, permitting, inspection, and reporting requirements) by which substantive requirements are made effective. On-site CERCLA response actions must comply with substantive requirements, but not with administrative requirements. For example, an on-site CERCLA response action must meet the intent of the law (substantive requirements), but need not conform with all applicable permitting or licensing rules (administrative requirements). This distinction applies only to on-site actions; off-site response actions are subject to the full requirements of applicable standards or regulations, including both substantive and administrative requirements.

In addition to the legally binding requirements established as ARARs, many federal, state and local programs have developed criteria, advisories, guidelines or proposed standards that may provide useful information or recommend procedures if ARARs are not available to address a particular situation. The use of these advisories, criteria or guidance to-be-considered (TBCs) that do not meet the definition of ARARs, may be evaluated along with ARARs to determine the necessary level of cleanup or develop Superfund remedies. TBCs are, by definition, generally neither promulgated nor enforceable so they do not have the same status under CERCLA as ARARs. Local laws also are not ARARs, but may be TBCs.

### **2.2.2 Classification of ARARs**

A description of the three distinct ARAR classifications is given below, while comparison of the remedial actions with each of the ARARs is presented in Section 4.

The U.S. EPA defines three types of ARARs:

- Chemical-specific
- Location-specific
- Action-specific

#### **2.2.2.1 Chemical-Specific ARARs**

Chemical-specific ARARs include those laws and requirements that regulate the release of materials having certain chemical or physical characteristics, or materials containing specified chemical compounds to the environment. These requirements generally establish health- or risk-based concentration limits or discharge limitations for specific hazardous substances.

#### **2.2.2.2 Location-Specific ARARs.**

Location-specific ARARs are those requirements that relate to the geographical or physical position of the Site, rather than to the nature of the contaminants or the proposed site remedial actions. These requirements may impose additional constraints on the remedial actions selected for the Site. Floodplain restrictions, wetland restrictions and protection of fish and wildlife are among location-specific potential ARARs for this site.

#### **2.2.2.3 Action-Specific ARARs.**

Action-specific ARARs are requirements that define acceptable treatment and disposal procedures for hazardous substances. These ARARs generally set performance, design, or other similar action-specific controls or restrictions on particular kinds of activities related to management of hazardous substances or pollutants. These requirements are triggered by the particular remedial activities that are selected to achieve remedial action objectives.

#### **2.2.3 ARARs for the HOD Site**

The potential ARARs for the Site are presented in Tables 2-1 through 2-3. These tables were developed jointly by U.S. EPA, and IEPA, in accordance with U.S. EPA guidance and Illinois State laws.

Chemical-specific potential ARARs for the H.O.D. Site have been identified for surface water, groundwater and air. Significant potential ARARs include Illinois water quality standards, leachate pretreatment standards, effluent guidelines, groundwater quality standards, and air quality standards.

Location-specific ARARs for wetlands have been identified as potentially relevant and appropriate for this Site because of the proximity of wetlands to the landfill areas. However, the identified wetland areas are outside of the landfill footprint, and potential construction activities presented in Section 3 would take place within the capped area only and will not encroach upon the wetland areas.

Similarly, floodplain ARARs have been included as potentially relevant and appropriate requirements. Floodplain maps developed before the development of the "new landfill" area show that the "old landfill" area was outside the 100-year floodplain. Based on flood elevations of 766 to 767 feet MSL, the "new landfill" area is also above the floodplain elevation. Construction activities conducted as part of the potential response actions evaluated for the Site are not expected to have detrimental impacts on the floodplain.

Because of the proximity of Sequoit Creek, the Fish and Wildlife Coordination Act is listed as a potential location-specific ARAR. Under the remedial action alternatives proposed, no control or structural modifications will be made to Sequoit Creek. In addition, no filling or dredging of the Creek is proposed in this evaluation.

Potential action-specific ARARs for the H.O.D. Site include specific requirements governing landfill closure; post-closure care; landfill gas collection and treatment; and leachate collection, treatment, and discharge.

The H.O.D. Landfill is an existing municipal solid waste landfill unit (MSWLF) as defined in 35 IAC §810.103, because it received waste before October 9, 1993. The H.O.D. Landfill received an operating permit under 35 IAC §807, and was closed under 35 IAC §807. Under 35 IAC §814.101(b)(3), H.O.D. Landfill is required to comply with the terms of its existing permit as established under 35 IAC §807, along with any relevant additional requirements specified in 35 IAC §814 Appendix A. Therefore, the requirements under 35 IAC §807 are applicable. 35 IAC §811 provides standards for new landfills which go beyond those provided in 35 IAC §807. Certain of these standards were identified by the State as relevant and appropriate for the H.O.D. Site. Because §811 was promulgated in part to set appropriate closure requirements for landfills, it covers problems or situations sufficiently similar to the circumstances of the release or remedial action contemplated. Because there is no technical bar to the effective implementation of these closure requirements at the H.O.D. Site, the §811 requirements are well-suited to the Site. See 40 CFR § 300.400(g)(2). Therefore, U.S. EPA and IEPA have identified these §811 requirements as relevant and appropriate.





)

)

### **3.0 REMEDIAL ACTION ALTERNATIVES**

This section identifies a variety of specific remedial action alternatives that could satisfy the remedial action objectives previously identified in Section 2. The technologies and process options described below include institutional controls, various engineered barriers, leachate and LFG collection and treatment, and groundwater monitoring upgrades (if necessary). This FS evaluates and incorporates presumptive remedies and ARAR-defined response actions to the maximum extent practicable in order to minimize detailed technology evaluation and screening, to accelerate the remedial process.

#### **3.1 ACTION ITEMS COMMON TO ALL REMEDIAL ACTION ALTERNATIVES**

The remedial action alternatives developed in this section are presented with the underlying assumption that regardless of the alternative(s) selected, the following site-related action items will be implemented or continue at the H.O.D. Site:

- Deed restrictions and institutional controls
- Site access restrictions
- Routine post-closure upkeep consisting of cap maintenance, stormwater control, and LFG and leachate collection and treatment
- Groundwater monitoring

Currently, Site access is restricted, and a landfill cap, LFG venting/flare system, and leachate collection system are in place at the Site. The LFG and leachate collection systems are operated in accordance with the IEPA permit requirements for the Site. A routine groundwater monitoring system is also in place at the Site.

Access restrictions to be evaluated for the Site include upgrading the existing fencing and signage, gates, and deed restrictions. Upgrading the existing fence will improve site security and restrict access to the Site by unauthorized individuals. A newly constructed chain link fence would be six-feet high with three strands of barbed wire at the top. Approximately 2,000 lineal feet of fencing would be needed to either replace or augment the existing fence and completely enclose the Site. Locking gates would be located at entry points. Signs would be posted every 300 feet along the fence at a height of approximately five feet. The signs would convey the following:

## **WARNING!**

### **H.O.D. LANDFILL AUTHORIZED PERSONNEL ONLY**

**THIS AREA MAY CONTAIN HAZARDOUS CHEMICALS IN THE  
SUBSURFACE SOILS AND GROUNDWATER.**

**CALL \_\_\_\_-\_\_\_\_-\_\_\_\_ FOR FURTHER INFORMATION**

Restrictive covenants on deeds to the Site would be maintained to prevent or limit site use and development. The covenants would notify a potential purchaser of the property of the past landfill activities and would assert that the land use must be restricted to ensure the continued integrity of the waste containment remedy.

The current groundwater monitoring program would continue to evaluate the effectiveness of the chosen remediation alternatives and document the concentrations of the chemical constituents in groundwater. The monitoring program should identify specific monitoring locations, frequencies and analytical parameters.

### **3.2 GENERAL RESPONSE ACTIONS**

The general response actions presented in this section describe broad types of action which could be conducted to satisfy the remedial action objectives. Response actions are selected on the basis of their applicability to site conditions and media of concern. An individual general response action may be capable of meeting all of the remedial objectives; however, combinations of response actions are typically more effective or economical. Potential general response actions for the H.O.D. Site were gathered from U.S. EPA guidance documents (including presumptive remedy guidance), literature review, and experience at other sites.

General response actions identified for the H.O.D. Site are:

- No Further Action
- Access Restrictions
- Capping
- Gas Collection/Treatment
- Leachate Collection/Treatment
- Groundwater Monitoring

In order to discuss the relevance of capping, LFG collection and treatment, and leachate collection as general response actions, the interrelationships between these three common measures should also be understood. Therefore, within each of the following discussions, the dependence of each of these measures on the other two will be explained. A general description of each of the above bulleted items is given below.

### **3.2.1 No Further Action**

This alternative provides a baseline for comparing other alternatives, and assumes that no additional remedial response actions would be implemented under CERCLA. The landfill has a continuous soil cover ranging in thickness from 49 inches to 87 inches. A passive LFG venting and combustion system is in place at the Site. In addition, a leachate collection and discharge system is in place, and is operated to remove approximately 6,000 to 8,000 gallons of leachate per week. The site is partially fenced to limit access. A routine groundwater monitoring program is regularly implemented at the Site.

### **3.2.2 Access Restrictions**

Access restrictions contribute to meeting all the remedial action objectives limiting human exposure to the Site, limiting how the Site can be used now and in the future, and educating potential site users and trespassers of the Site contents and their potential hazards. Access restrictions will include site fencing, signage, gates, and deed restrictions.

### **3.2.3 Capping**

The existing cover on the Site serves to control infiltration, contain the landfill contents and generally limit exposure to the waste mass. Upgrades to or repair of the existing cap on the landfill could address one or more of the general remedial action objectives, listed previously, to varying degrees. Repair of the existing cap would serve to reduce ponding and the associated infiltration of surface water, and contain leachate seeps and landfill gas (LFG).

The major effects of a continuous cap over the waste mass are threefold. In general, a cap:

1. Controls the release of LFG to the atmosphere, which causes buildup of LFG pressures. Once generated, LFG will migrate to areas of lower pressure with a concomitant increase in partitioning of LFG contaminants into the leachate and/or groundwater in direct subsurface contact with the LFG.
2. Controls the generation of leachate by limiting the infiltration of storm water into the waste mass.
3. Prevents direct contact with the waste mass, and effectively eliminates the potential for off-site transport of refuse or debris.

Therefore, by capping a landfill, LFG production will increase and leachate production will decrease. In this case, the chemical concentrations in both the LFG and the leachate may increase due to the reduced infiltration and LFG emissions.

As part of the containment measures, regardless of which capping option is selected, a small amount of waste located outside the property line on the north end of the "old landfill" area would be either be consolidated within the landfill waste mass or would remain in place if WMII acquires this portion of the adjacent property. If WMII acquires the property, the selected capping option would extend over this particular area.

As a common element within each capping option, surface water controls to direct stormwater runoff from the Site, and to prevent off-site surface water from running onto the Site, would be implemented. Specifically, Sequoit Creek would be protected through the implementation of erosion control measures (detailed in Section 3) and by the placement of temporary silt fencing between the creek bank and active construction areas. Surface water controls may include grading to manage the stormwater runoff, the use of soil erosion control measures such as revegetation, and the placement of straw bales in the site ditches.

### **3.2.4 Gas Collection/Treatment**

The existing passive LFG control system consists of 14 passive flares in the "new landfill" area. Refer to Figure 10 for the locations of these features. A passive LFG control system allows the LFG pressure within the waste mass to build-up, eventually causing the LFG to vent. An upgrade of the existing LFG collection and treatment system would be capable of meeting the general remedial action objectives by controlling the build-up and migration of landfill gas. These measures would prevent direct contact/inhalation threats, uncontrolled migration of the LFG, eliminate potential explosion hazards posed by the methane in the LFG, and significantly reduce the dissolution of chemicals (mainly VOCs) in the LFG into the leachate and/or groundwater. An active LFG system uses a mechanical device (usually a blower) to produce a vacuum within the collection devices (usually wells or perforated header pipes), thereby pulling LFG out of the waste mass. Performance of both active or passive systems can be increased by increasing the number of LFG venting or collection points.

Active collection and treatment of LFG serves to:

1. Reduce the LFG pressures that will naturally build under a landfill cap, reducing the potential for off-site migration of LFG, and potential for stressed vegetation on the cap.
2. Reduce the mass of the volatile constituents present in the landfill waste mass by maintaining a consistent flow of LFG out of the landfill. This in turn reduces the contaminant concentrations in the leachate, as fewer contaminants are partitioned into leachate. The removal of LFG can eliminate thousands of pounds of VOCs per year from the waste mass. It has been demonstrated that LFG controls may be significantly more effective in reducing volatile organic compound concentrations in groundwater (by several orders of magnitude) than groundwater removal/treatment systems (Bagchi, 1994, Cook et al, 1991). In addition, numerous studies have been done on LFG as a source of groundwater contamination near landfills (Challa et al, 1997, Heuckroth, et al, 1995, Janecek et al, 1995, Kerfoot, 1994). A recent study on more than 60 solid waste landfills indicated that LFG control significantly reduced contamination in nearby groundwater monitoring wells (Baker, 1997).
3. By reducing the contaminant concentrations in the leachate, the potential for adverse impacts to groundwater is reduced.

Methane concentrations measured at the Site during the RI range from 65 to 68 percent in the "new landfill" area and 72 percent in the "old landfill" area. VOCs found in the landfill gas include the following five groups: ketones, aromatics, alkenes, alkanes, and other VOCs. A summary of the concentrations of VOCs found in LFG at all of the sampling locations is provided in Table 1-2.

### **3.2.5 Leachate Collection/Treatment**

The volume of leachate within the Site is currently estimated to range from 69 to 96 million gallons. Currently, leachate is collected in pipes and directed to manholes (MHE and MHW) where approximately 35,000 gallons of leachate per month are extracted. Refer to Figure 10 for the locations of these features. Leachate collection and off-site disposal are currently conducted at the Site in order to maintain compliance with the existing IEPA permit for the Site. The current measures could be upgraded to meet the remedial action objectives of minimizing leachate build-up and eliminating potential seeps through the landfill side slopes. Leachate collection reduces potential migration of leachate to surface water and groundwater. It should be noted that upgrades to the leachate collection system at the Site would also likely induce an inward gradient and to some degree capture shallow groundwater in the surficial sand aquifer in the immediate vicinity of the Site.

Collection of leachate from the waste mass:

1. Maintains hydraulic control of the liquid levels within the waste mass, reducing the potential for off site migration.
2. Increases the production of LFG, attributable to anaerobic digestion, by reducing leachate levels, creating more favorable conditions within the waste mass for anaerobic digestion to occur.
3. Reduces the potential dissolution of LFG contaminants into the leachate by reducing the volume of leachate available within the waste mass.

### **3.2.6 Groundwater Monitoring**

A routine groundwater monitoring program is currently performed at the Site in accordance with the existing IEPA Site permit. This current groundwater monitoring and sampling program could be revised to more thoroughly address the effectiveness of the selected remedy with respect to identified groundwater impacts. The monitoring plan would entail sampling of select existing downgradient wells at the Site for the contaminants of concern. While groundwater monitoring does not directly address the remedial action objectives, it serves as a measuring tool to ensure that the other remedial actions implemented at the Site are meeting their respective remedial action objectives. If, at some time in the future, periodic groundwater monitoring results indicate an unacceptable change in the groundwater quality, a contingent groundwater response may be evaluated.

### 3.3 SUMMARY OF POTENTIAL ADDITIONAL REMEDIAL ACTION COMPONENTS

The following potential supplemental remedial action components have been developed and are summarized in Table 3-1:

- No Further Action
- Capping (see Figure D-1)
  - C1 – Landfill cap restoration and maintenance - As described in the Site Conditions (see Section 1.3), 49" to 87" of soil currently cover the waste mass. The soil is primarily compacted clay (compacted to over 90%, and in many cases >100%, of maximum Std. Proctor density as supported by TSC September 28, 1989 compaction testing report, attached as Appendix A) with a surficial vegetated topsoil layer. In this alternative, the cap would be restored and maintained at the grades that existed when the Site was closed in 1989. Existing cover soils in the low areas of the Site would be stripped and stockpiled for later use. Clay from the existing cover soils or from an off-site source would be compacted into the low areas and used to repair leachate seeps. The stockpiled cover soils, along with necessary supplementary soils from an off-site source, would then be regraded atop the compacted clay to promote drainage and eliminate surface water ponding. Twelve inches of soil (from the stockpiled soils or from an off-site source) would be placed atop the compacted clay and seeded to match existing vegetation.
  - C2 – Augmentation of the existing landfill cap - The existing cover soils would be stripped, and the existing clay would be reworked to form a uniform 35 IAC 807-compliant cap consisting of two feet of compacted clay with additional 24" of cover soil, (the stripped soil would be reused) the top six inches of which would consist of topsoil. The topsoil layer would be seeded to establish vegetation.
  - C3 – Reconfiguration/supplementation of existing landfill cap - The existing cover soils would be reworked and supplemented (if necessary) to form a 35 IAC 811-compliant cap consisting of three feet of compacted clay and three feet of cover soil, the top six inches of which would consist of topsoil. The topsoil layer would be seeded to establish vegetation.

In all three alternatives, the vegetation is assumed to be primarily native grasses that would minimize erosion and promote evapotranspiration.

- LFG Collection and Treatment
  - G1 – No further action - Continue to passively vent and destroy LFG with existing stick flares. These stick flare locations are shown on Figure 4.
  - G2 – Supplement the existing LFG system – The existing passive flare system in the new landfill area would be maintained, as necessary, and continue to be operated. LFG collection and treatment would also be supplemented through the addition of an active LFG control system in the old landfill section,

consisting of new vertical wells interconnected by header piping to a blower/flare station. A pilot/predesign study would be conducted to determine the necessary repairs in the new landfill area and the optimum locations for placement of vertical wells in the old landfill area.

- G3 – Active site upgrade of LFG system – The existing stick flares would be utilized as LFG extraction points (as necessary), additional wells in the old portion of the Site would be installed (as needed), and a header system would be installed to convey LFG to one centralized blower/flare station forming an entirely active treatment system. As in the case of G2, a series of pilot/predesign studies would be conducted to determine the viability of using existing extraction points and to identify new extraction points, if any, which may be needed. The results of these pilot/predesign studies may indicate that the fully active system proposed under G3 is not necessary, and that G2 is sufficient to address the LFG at the Site.
- Leachate Collection
  - LC1 – No further action, Continue to utilize the existing leachate extraction protocols and collection points.
  - LC2 – Toe-of-slope leachate collection - The toe-of-slope collection piping would be extended along the toe of both the old and new sections of the landfill and the existing extraction points (P1, P2A, P3A, and P8-P10) would be used. The entire system would be automated, at a minimum, with level controls on the wells, automatic pumps in the lift stations/manholes, an alarm system and control logic such as high level shut down.
  - LC3 – Upgrade/Supplementation of leachate system - The toe-of-slope collection piping would be extended along the toe of the landfill in the new section only; existing extraction points in the new section would also continue to be used. A dual extraction system consisting of 5 new wells interconnected with existing wells and header piping to a blower/flare station would be constructed in the old section of the landfill. A pilot/predesign study would be undertaken to determine the viability of using existing extraction points and to identify new extraction points, if any, which may be needed. It should be noted that this alternative would be considered in conjunction with the LFG alternative G2, because the required construction for each of these alternatives is similar (i.e., use existing systems with minor upgrades in the new landfill area, install new wells in the old landfill).
  - LC4 – Active Leachate Extraction – Existing gas and leachate wells (GWF1-GWF14 and LP1-LP14) in both the old and new sections of the landfill would be converted to dual extraction wells. The existing LFG wells would be used for additional extraction points. As in the case of LC3, a pilot/predesign study would be undertaken to determine the viability of using existing extraction points and to identify new extraction points, if any, which may be needed. The entire system would be automated. It should be noted that this alternative would be considered in conjunction with the LFG alternative G3, because the required construction for each of these alternatives is similar (i.e., install new



wells as necessary across the Site, install header piping and automate the entire system).

- Leachate Treatment/Disposal
  - LT1 – No further action - Continue to directly discharge to a licensed POTW. The current POTW standards, for discharge of leachate to the Fox River Water Reclamation District (FRWRD), are provided in Table 3-2. Note that the Site has, without exception, historically met these POTW discharge requirements.
  - LT2 – Pretreat leachate, discharge to POTW – Pretreatment of leachate via physical/chemical processes would be done before discharge to a POTW.
  - LT3 – Treat leachate, surface discharge – Full treatment of leachate to NPDES standards would be done prior to remote surface discharge to a surface water source of adequate assimilative capacity (not Sequoit Creek).
- Groundwater Monitoring
  - GW1 – No further action - The existing groundwater monitoring program would be continued.
  - GW2 – Monitored natural attenuation - The existing groundwater monitoring program would be upgraded to include additional monitoring points and analytes for natural attenuation monitoring near the southwest corner of the Site.

Costs for each of the above alternatives are presented at the end of the detailed descriptions found in the following sections. A cost summary table is included as Table 3-3. These cost estimates were prepared for each element of the various alternatives, using available sources of information such as Means® construction cost data, engineer's estimates, bid costs for similar work, quotes from vendors and contractors, and engineering judgment. However, the actual construction costs for any selected remedy will reflect the project specifications, the actual labor and material costs at the time of construction, the market conditions, the final project schedule, and other less quantifiable factors. Consequently, the cost estimates presented for each alternative must at this time be considered approximate, with a range of accuracy of +50% to -30%.

### **3.4 NO FURTHER ACTION**

The NCP requires the 'No Further Action' response alternative to be carried through detailed analysis. Under this option, no further remedial actions would be implemented at the Site under CERCLA. However, the routine operation and maintenance activities currently being performed at the Site under the existing IEPA permit, which include cap maintenance and operation and maintenance of the existing (passive) LFG and manual leachate collection systems, would continue under this alternative. The groundwater monitoring activities being performed at the Site would also continue under this alternative. The existing site security fence and deed restrictions would remain in place along with all existing Site control features, including the in-place landfill cover and the leachate and

LFG collection and control systems. The following estimated cost is associated with the no further action alternative:

- Capital Cost..... \$0
- Annual O&M ..... \$154,860
- Total Present Worth (30 yrs @ 7%)..... \$1,921,670

Note that the costs for decommissioning VW4 and installing VW7 have not been included in the above cost estimate. The decommissioning of VW4 and installation of VW7 have already been completed at a cost of \$652,800, and VW4 will eventually be abandoned for an estimated cost of \$39,400 (See Appendix D for details).

### **3.5 CAPPING**

#### **3.5.1 C1 – Landfill Cap Restoration and Maintenance**

This alternative involves using cover materials from the existing cap (or off-site clay, if necessary) to restore the cap to the approximate grades which existed when the site was closed in the late 1980s. Based on observations and performance to date, the "old landfill" has an excellent vegetative cover and is very uniform over the entire area. The "new landfill" area has some limited areas of erosion, differential settlement and resulting ponded water. Therefore, the cap repairs would be performed on the "new landfill" area, with limited potential repairs on the "old landfill" area. The cap repairs would be performed by supplementing the existing cover, thus adding thickness to the existing soil cover of 49 to 87 inches. Appendix A contains the 1989 TSC compaction testing report and subsequent 1991 TSC thickness testing report documenting final cover compaction and thickness at the Site. Alternative C1 would involve stripping and stockpiling existing cover soils in the low areas and other areas to be repaired on the Site. Clay soils from the existing cover or from an off-site source would be compacted into the low areas, and used to repair leachate seeps. The stockpiled cover soils, along with necessary supplementary soils from an off-site source, would then be regraded atop the compacted clay to promote drainage and eliminate surface water ponding. After regrading is completed to promote drainage, a 12 inch thick soil layer would be placed on the repaired areas and seeded to establish vegetation. The resulting dual layer cap would meet or exceed the final cover specifications embodied in 35 IAC 807 (which call for "a compacted layer of not less than two feet of suitable material").

Construction activities would include the removal of vegetation, stockpiling of topsoil to be reused as vegetation layer soils, consolidation of the off-property waste at the northern edge of the "old landfill" onto Site property, regrading, placing and compacting the clay soils, placing the vegetation layer soils (uncompacted), and re-establishing the vegetation. The existing landfill access roads are adequate; therefore, the construction of additional access roads is not included under this capping alternative. Construction activities would be planned to avoid encroaching upon or impacting the adjacent wetlands or floodplain.

The regrading of the Site would be performed to improve areas of the landfill that have been affected by erosion and/or settlement, to create and maintain a continuously sloped surface sufficient to maintain positive drainage over and off the Site. The soil in the area of leachate seeps would be overexcavated and consolidated in the low areas. The resulting excavation would be backfilled and compacted with clay soils, effectively sealing the cover. The existing cover soils range in thickness from approximately four to seven feet which should provide sufficient cut and fill material balance for these regrading activities. Off-site soils would be used, only if necessary. The Site would be graded to a minimum 2 percent slope and the side slopes would be no steeper than 4H:1V. The exception to this would be in the "old landfill" area next to Sequoit Creek, where some of the side slopes exceed 4H:1V. However, these slopes have been in place for at least 10 years, and will not be significantly affected by regrading in alternative C1. There are no signs of incipient slope failure, and the vegetation in these areas adds to the stability of the slopes. In the "new landfill" area, the existing side slopes range from 4H:1V to 6H:1, and therefore should not hinder the regrading effort.

Appropriate erosion control measures, to protect nearby Sequoit Creek and the adjacent wetlands, would be implemented prior to construction activities. These measures would possibly include construction of berms/silt fences, rip-rap and straw bale dikes, and use of temporary cover material.

After repairs to the soil cap are made, maintenance of the cap would include mowing at a minimum of twice per year and perimeter ditch inspection and maintenance on a quarterly basis. Maintenance of the ditches would include removal of silt and debris. Quarterly inspections would include walking the Site and visually noting signs of erosion, settlement, or other damage. Noticeable, significant cover damage would be repaired. Although the majority of settlement on the Site has already occurred, additional differential settlement could occur as a result of continued or upgraded LFG and/or leachate extraction. However, any such settlement would be repaired by stripping soils, placing and compacting clay in the settled areas, and regrading the stockpiled soils as part of routine maintenance.

Infiltration would be reduced by over two inches per year (from 3.9 inches) by these cap improvements. Approximately 1.6 inches/year of infiltration would be expected following the implementation of this cap alternative, as shown on the HELP Model Version 3 output included in Appendix C.

Construction would be expected to take approximately 6 weeks and may be completed in one construction season (May-October) with the following estimated cost:

- Capital Cost..... \$1,370,000
- Annual O&M ..... \$72,000
- Total Present Worth (30 yrs @ 7%)..... \$2,270,000

### **3.5.2 C2 – Augmentation of the Existing Landfill Cap**

This alternative involves using clay and cover materials from the existing cap to rework the cap over both the old and new landfill areas. The reworked cap would be constructed by stripping the existing soil cover, stockpiling the soils for later use, placing a two-foot compacted clay layer atop the entire landfill using on-site and off-site clay sources, as necessary, and replacing the stockpiled soil in a two-foot uncompacted rooting zone/cover layer to support vegetation. The resulting dual layer cap would meet or exceed the final cover specifications embodied in 35 IAC 807. The additional two feet of material would help to facilitate the post-closure goal of minimizing future cap maintenance by providing an additional protective layer conducive to vegetative rooting. Figure 9 presents a cross-section and conceptual details of this proposed cover configuration.

Construction activities would include the removal of vegetation, stockpiling of soils to be used as vegetation layer soils, consolidation of the off-Property waste at the northern edge of the "old landfill" onto Site property, regrading, placing and compacting the clay soils, placing the vegetation layer soils (uncompacted), and re-establishing the vegetation. The existing landfill access roads are adequate; therefore, the construction of additional access roads is not included under this capping alternative. Construction activities would be planned at the landfill to avoid encroaching upon or impacting the adjacent wetlands or floodplain.

The regrading of the Site will be performed to improve areas of the landfill that have been affected by erosion and/or settlement, to create and maintain a continuously sloped surface sufficient to maintain positive drainage over and off the Site. Recomposition of the cover would reduce infiltration of surface water by establishing a less permeable barrier layer. All work would be expected to be performed using existing on-site soils of supplemental off-site borrow soils. The Site would be graded to a minimum 2 percent slope and the side slopes would be no steeper than 4H:1V. For alternative C2, the side slopes in the "old landfill" area next to Sequoit Creek, where some of the side slopes exceed 4H:1V, would require some amount of regrading to ensure slope stability following placement of the additional cover soils in these areas. The tops of the slopes would likely be pulled back, and the compacted clay and cover soils would be regraded on the reduced slopes. A detailed analysis of the slope regrading and reconfigurations would be part of the Remedial Design for the Site, should alternative C2 be selected. In the "new landfill" area, the existing side slopes range from 4H:1V to 6H:1, and therefore should not hinder the regrading effort.

Appropriate erosion control measures, to protect nearby Sequoit Creek and the adjacent wetlands, would be implemented prior to reworking the cap. These measures may include construction of berms/silt fences, rip-rap and straw bale dikes, and use of temporary cover material.

After the reworking of the soil cap, maintenance of the cap would continue to be required and would include mowing at a minimum of twice per year and perimeter ditch inspection and maintenance on a quarterly basis. Maintenance of the ditches would include removal

of silt and debris. Quarterly inspections would include walking the Site and visually noting signs of erosion, settlement, or other damage. Any damage would be repaired. Although the majority of settlement on the Site has already occurred, additional differential settlement could occur as a result of additional weight from reworking the existing landfill cover. However, no additional thickness of cover soils is planned to be placed and therefore settlement would not be expected to be significant for this option.

Approximately 2.0 inches/year of infiltration would be expected following the implementation of this cap alternative, as shown on the HELP Model Version 3 output included in Appendix C. It should be noted that this infiltration value is greater than that of C1 because of the greater thickness of soil atop the compacted clay, allowing a greater volume of pore water to collect atop, and eventually infiltrate through, the compacted clay.

Construction would be expected to take approximately 20 weeks and may be completed in one construction season (May-October) with the following estimated cost:

- Capital Cost..... \$4,861,000
- Annual O&M ..... \$72,000
- Total Present Worth (30 yrs @ 7%)..... \$5,761,000

### **3.5.3 C3 – Reconfiguration/Supplementation of the Existing Landfill Cap**

This alternative includes using the soil materials from the existing cap as a “final protective layer” and using either existing on-site clay, supplemented, as needed, with off-site clay, or entirely new off-site clay as a “low permeability layer.” A cap that uniformly consists of a three-foot compacted clay layer and a three-foot uncompacted rooting zone/cover soil layer and vegetative cover would be constructed. The resulting cap would comply with the final cover specifications of 35 IAC 811, which requires a low permeability layer with a minimum allowable thickness of three feet, overlain by a final protective layer, sufficient to protect the low permeability layer from freezing and minimize root penetration, not less than three feet thick. Figure 9 presents the conceptual details of this proposed cover alternative. It is worth noting that the 35 IAC 811 requirement for capping is not applicable for the Site, but this alternative was evaluated for reference purposes.

Construction activities would include removal of vegetation, stockpiling the cover soils for re-use as needed, consolidation of the off-Property waste at the northern edge of the “old landfill” onto Site property, re-grading the Site using existing soils to a uniform graded surface, excavating and hauling supplemental off-site clay to the site, placing and compacting three feet of clay as the barrier layer, placing the rooting zone soils and topsoil layer, and re-establishing vegetation. A borrow-source investigation would be conducted to confirm the quality of off-site clay before it is excavated and used in the cap. It is important to note that the cap could be supplemented with clay from the previously used clay source (north of the “new landfill” area) if the clay is available in sufficient quantity and is of acceptable quality (to be determined by borrow-source testing). Existing landfill access roads are adequate; therefore, construction of additional access roads is not included under this capping alternative. Construction activities could be performed so as not to encroach upon, or impact, the adjacent wetlands or floodplain.

Regrading of the Site, using existing cover soils, would be performed to address the erosional rills, gullies, and settlement depressions that affect approximately 20 percent of the Site area. This would create a continuously sloped surface sufficient to maintain positive drainage over and off the Site and would also reduce infiltration and the formation of leachate. Recomposition of the cover would reduce the infiltrating volume of surface water by establishing a less permeable barrier layer. The Site would be graded to a minimum 2 percent slope and to a maximum 4H:1V slope on side slopes, except at the property boundary where Sequoit Creek abuts the Site. The 4H:1V design criterion is intended as a generalized guidance for the cap and may have to be evaluated at the very edge of the property boundary in these areas. Although significant grading may be necessary to place the additional thickness of cover soils in the steep areas, these slopes appear to be in relatively good shape, and a detailed analysis would be conducted to determine the proper slope grades and configurations, if these areas would necessarily be regraded to install the cap upgrade.

Appropriate erosion control measures, to protect nearby Sequoit Creek and the adjacent wetlands, would be implemented prior to reworking the cap. These measures may include the construction of berms/silt fences, the placement of rip-rap, and straw bale dikes, or the use of temporary cover material.

After the reworking of the landfill cap, maintenance would continue to be performed and would include mowing at a minimum of twice per year and site inspection on a quarterly basis. Quarterly inspections would consist of walking the Site and visually noting evidence of erosion, settlement, clogged swales, and/or other damage. Repair would be performed as needed. Maintenance of the ditches would include removal of silt and/or debris that may impair surface water flow. Additional differential settlement could occur after the reconstruction of the landfill cover as a result of the weight addition provided by the new cover soils; however, additional settlement would be addressed as part of the routine Site maintenance.

Approximately 2.1 inches/year of infiltration would be expected following the implementation of this capping alternative, as shown on HELP Model Version 3 output included in Appendix C. It should be noted that infiltration is greater through the C3 alternative than that of the C2 alternative because the thicker soil layer is able to retain more moisture, thus allowing a greater volume of pore water to infiltrate through the clay to the waste mass.

Construction would be expected to take approximately 22 to 27 weeks and may need to extend over the course of two construction seasons with the following estimated cost:

- Capital Cost..... Up to \$8,783,500
- Annual O&M ..... \$72,000
- Total Present Worth (30 yrs @ 7%)..... Up to \$9,683,500

## **3.6 LANDFILL GAS COLLECTION AND TREATMENT ALTERNATIVES**

### **3.6.1 G1 – No Further Action, Utilize the Existing Gas Collection System**

This alternative involves the continued utilization of the existing passive gas vent system at the Site (shown on Figure 4). Repairs to the existing gas flares may be required in order to maintain the gas collection efficiency of the system. The following estimated costs are associated with utilizing the existing gas collection system:

- Capital Cost..... \$231,000
- Annual O&M ..... \$35,000
- Total Present Worth (30 yrs @ 7%)..... \$665,400

### **3.6.2 G2 – Supplement the Existing LFG System**

The existing passive flare system in the new landfill area, consisting of flares GWF1-GWF14, would be repaired, as necessary, and continue to be operated. LFG collection and treatment would also be supplemented through the addition of an active system in the old landfill section, consisting of approximately five new vertical extraction wells (GE1-GE5), and utilization of the nine existing extraction points (LP1-LP4, and LP10-LP14). The extraction points would be interconnected by header piping to a blower/flare station. A pilot/pre-design study would be undertaken to determine the necessary repairs to the existing passive flares in the “new landfill”, viability of using the nine existing wells in the “old landfill” and the optimum locations for placement of new wells in the “old landfill”. Figure 11 shows the system layout for this alternative.

The installation of the new system in the “old landfill” area would require trenching in areas of the Site where header pipe placement is needed (or this work would need to be coordinated with the “new landfill” cap re-construction, if performed), the placement of header piping and installation of the new wells, backfilling, the reworking of the cap, and construction of the blower and flare station.

The existing gas collection system consists only of passive vent points. These existing gas vent points will be raised or lowered, as necessary, concurrently with the cap repair or upgrade. Care will be taken when grading around these vent points, and grading will likely be done by hand in the immediate vicinity of the wells or vents, so that damage will be avoided or minimized.

After installation of the new system, operation, inspection, and maintenance would be required as described for alternative G3. The existing system in the “new landfill” area would also require inspection and maintenance. Construction activities would have to be staged so that they would not encroach upon or impact the adjacent wetlands or floodplain.

Construction of this gas collection/treatment alternative can be completed in one construction season and can occur concurrently with the cap restoration with the following estimated costs:

- Capital Cost..... \$701,100
- Annual O&M ..... \$35,000
- Total Present Worth (30 yrs @ 7%)..... \$1,135,500

### 3.6.3 G3 – Active Site Upgrade of LFG System

Figure 12 illustrates the system layout for this alternative. Stick flares (GWF1-GWF14) in the “new landfill” area would be converted to extraction wells (as necessary). Existing vertical extraction wells in “old landfill” would be used, and additional wells in the “old landfill” would be installed (as needed). A header system would be installed that would interconnect all of the wells, including LP1-LP14, located throughout the landfill, to convey LFG to one centralized blower/flare station, forming an entirely active extraction and treatment system. As in the case of G2, a series of pilot/predesign studies would be conducted to determine the viability of using existing extraction points and to identify new extraction points, if any, which may be needed. The results of these pilot/predesign studies may indicate that the fully active system proposed under G3 is not necessary, and that G2 is sufficient to address the LFG at the Site.

The implementation of this alternative would require trenching in areas of the Site for pipe placement (or if cap construction occurs, placement of piping would be coordinated with that work), placement of pipe and new wells, placement of backfill around these new features, localized cap reconstruction and construction of the blower and flare station. Construction activities would be performed so they do not encroach upon or impact the adjacent wetlands or floodplain.

This LFG system upgrade would allow LFG to be actively extracted from the waste mass increasing the radius of influence (ROI) of each well to between 100 and 150 feet per well which is typical for active municipal LFG extraction wells. The existing 14 wells (GWF1-GWF14) are spaced approximately 200 feet apart, allowing for effective use of a 100 to 150 foot ROI. Approximately five new wells (GE1-GE5) would be constructed in the “old landfill” area and one new well (GE6) would be proposed for installation in the “new landfill” area to provide complete coverage. These new wells would have an approximate 35-foot depth and would be spaced approximately 200 feet apart. Approximately 12,000 feet of piping would connect all of the LFG extraction wells at the Site and a blower and flare station would be constructed.

This active gas system, after installation, would require continual operation and regular maintenance. Inspections would be performed monthly to assure proper operation of warning lights, telemetry systems, and building vents. Measurements of valve settings, pressures and blower settings would be recorded. Routine maintenance and LFG monitoring would be performed as well.

This active LFG extraction/collection system could be constructed as part of a dual extraction system for leachate and gas. An additional feature of this option would be leachate extraction, therefore the leachate collection portion of the dual extraction system is presented as leachate collection alternative LC4.



Construction of this gas collection/treatment alternative can be completed in one construction season and can occur concurrently with the cap restoration with the following estimated costs:

- Capital Cost..... \$924,000
- Annual O&M ..... \$35,000
- Total Present Worth (30 yrs @ 7%)..... \$1,358,400

### **3.7 LEACHATE COLLECTION ALTERNATIVES**

#### **3.7.1 LC1 – No Further Action, Continue To Utilize Existing System**

This alternative would utilize the existing toe-of-slope collection pipes and leachate extraction manholes. Collection of leachate would continue as it has, with approximately 1250 gpd removed from the landfill.

The following estimated costs are associated with this leachate collection alternative:

- Capital Cost..... \$0
- Annual O&M ..... \$4,000
- Total Present Worth (30 yrs @ 7%)..... \$49,700

#### **3.7.2 LC2 – Toe-of-Slope Leachate Collection**

Figure 13 illustrates the leachate collection system for alternative LC2. This combination passive/active leachate collection alternative involves extending the existing leachate collection piping along the perimeter of the waste mass on both sides of the separation barrier between the “old and “new” landfill areas, and using the leachate extraction wells (P1, P2A, P3A, and P8-P10) in the “new landfill” area. In the “new landfill” area, piping would be constructed along the north and south perimeters and would tie into the pipe which runs along the west side of the “new landfill” area into the east manhole (MHE). In the “old landfill” area, piping would be constructed along the north, south, and west perimeters that would tie into the pipe which runs along the east side into the west manhole (MHW). Approximately 4,200 feet of total piping would be placed.

Construction of this alternative includes removal of the cap in areas of pipe placement (or if cap construction occurs, placement of piping would be coordinated with that work), placement of backfill, relocation of excavated waste, and replacement of the cap. Construction activities would be staged so that they do not encroach upon or impact the adjacent wetlands and floodplain.

This alternative would increase leachate collection efficiency, reduce leachate levels near the toe of slope to eliminate seeps, and induce an inward gradient at the perimeter of the landfill, potentially capturing impacted shallow groundwater in the surficial sand aquifer in the vicinity of the Site. Extraction of leachate would continue via the leachate extraction wells in the “new landfill” and from MHE and MHW. In addition, the extraction points

installed in 1993 (LP1-LP14) could be used. These 14 wells were constructed for leachate/gas extraction, if needed.

After construction of the new piping, routine operation and maintenance activities would need to be performed. Inspections would be performed to assure proper operation of pumps, switches, and alarms and equipment maintenance would be done, as needed. Monitoring of leachate volumes and composition would also be performed.

Construction of this leachate collection alternative can be completed in one construction season and can occur concurrently with the cap restoration with the following estimated costs:

- Capital Cost..... \$232,300
- Annual O&M ..... \$60,000
- Total Present Worth (30 yrs @ 7%)..... \$976,900

### **3.7.3 LC3 – Upgrade/Supplementation of Leachate System**

The layout for this alternative is shown on Figure 11. The toe-of-slope collection piping would be extended along the north and south perimeter of the “new landfill” only; existing extraction points in the “new landfill” would also continue to be used. A dual extraction system consisting of five new wells (GE1-GE5) interconnected with existing wells (LP1-LP4 and LP10-LP14) and header piped to a blower/flare station would be constructed in the old section of the landfill. A pilot/predesign study would be conducted to determine the viability of using existing extraction points and to identify new extraction points, if any, which may be needed. It should be noted that this alternative would be considered in conjunction with the LFG alternative G2, because the required construction for each of these alternatives is similar (i.e., use existing systems with minor upgrades in the “new landfill”, install new wells in the “old landfill”).

The work includes removal of the cap in areas of pipe placement (coordination of pipe placement and well installation would also have to be coordinated with the reconstruction of the cap), installation of additional leachate/gas extraction wells and header piping, backfilling, and relocating of excavated waste, and reconstruction of the cap. Construction activities would be performed so that they would not encroach upon or impact the adjacent wetlands or floodplain.

The “new landfill” area has six existing leachate extraction wells from which leachate can be pumped and discharged into a leachate holding tank. The collection pipe along the perimeter would act as a control measure to eliminate side slope seeps. This alternative would also induce an inward gradient at the perimeter of the Site, and shallow groundwater in the surficial sand aquifer in the vicinity of the Site.

After the systems are constructed, inspection, operation, and maintenance activities would need to be performed. For the “old landfill” area, inspections would be performed monthly for the gas and leachate systems to assure proper operation of warning lights, telemetry systems, building vents, pumps, and controls. The monitoring of valve settings, pressures, blower settings, and leachate volumes and composition would also need to be done. For

the "new landfill" area, inspections would need to be performed monthly for the piping and pumps along with monthly monitoring of leachate volumes and leachate composition.

Construction of this leachate collection alternative can be completed in one construction season and can occur concurrently with the cap restoration with the following estimated costs:

- Capital Cost..... \$367,800
- Annual O&M ..... \$72,000
- Total Present Worth (30 yrs @ 7%)..... \$1,261,300

#### **3.7.4 LC4 – Active Leachate Extraction**

The system layout for this alternative is shown in Figure 14. It should be noted that this alternative would be considered in conjunction with the LFG alternative G3, because the required construction for each of these alternatives is similar (i.e., install new wells as necessary across the Site, install header piping and automate the entire system).

Existing gas and leachate wells (GWF1-GWF14 and LP1-LP14) located in both the old and new sections of the landfill would be converted to dual extraction wells. New dual extraction wells (GE1-GE6) would be constructed (as needed). A header system would be constructed for the conveyance of gas and leachate. Approximately 28 wells would require conversion into dual extraction wells and approximately 12,000 feet of header pipe installation would be required for leachate extraction. In addition to the leachate header piping, a leachate storage tank would be required (there is a tank currently on-site).

As in the case of LC3, a pilot/predesign study would be conducted to determine the viability of using existing extraction points and to identify new extraction points, if any, which may be needed. The entire system would be automated, and the final design would be based on the results of the pilot/predesign studies.

Construction of this alternative includes converting the existing gas wells into dual extraction wells, removal of the cap in areas of leachate header pipe placement (or if cap construction occurs, placement of header piping in coordination with that work), placement of pipe, backfilling and relocating excavated waste, reconstructing the cap, and installation of a leachate storage tank. Construction activities would be staged so they would not encroach upon or impact the adjacent wetlands or floodplain.

This alternative would increase leachate collection efficiency, reduce leachate levels throughout the landfill to eliminate seeps, and would also induce an inward gradient to control and collect shallow groundwater in the surficial sand aquifer in the vicinity of the Site.

After construction of this system, inspections would need to be performed on a monthly basis to assure proper operation of pumps, switches, controls, warning lights, telemetry systems, and building vents. Maintenance, adjustments, and repairs to the system would be made as necessary. Monitoring of leachate volumes and leachate composition would be

performed in addition to the gas system monitoring that would be required (described in alternative G2).

Construction of this leachate collection alternative can be completed in one construction season and can occur concurrently with the cap restoration with the following estimated costs:

- Capital Cost..... \$439,000
- Annual O&M ..... \$60,000
- Total Present Worth (30 yrs @ 7%)..... \$1,183,600

### **3.8 LEACHATE TREATMENT ALTERNATIVES**

#### **3.8.1 LT1 – No Further Action, Continue To Discharge To A Licensed POTW**

Under this alternative, leachate would continue to be discharged to a licensed POTW. The leachate would be pumped directly from the collection system and transported or discharged to a POTW for treatment under an industrial discharge permit for the Site.

The following estimated costs are associated with this leachate collection alternative:

- Capital Cost..... \$0
- Annual O&M ..... \$66,800
- Total Present Worth (30 yrs @ 7%)..... \$829,000

#### **3.8.2 LT2 – Pretreatment of Leachate, Discharge to POTW**

Under this alternative, leachate would be pre-treated prior to discharge to a local POTW. Pretreatment may include chemical precipitation for metals removal and aeration to lower BOD concentrations. Table 3-4 indicates potential treatment processes for the removal of various compounds. The use of some combination of these pretreatment processes or discharge without treatment may be possible based on the requirements of the POTW. Discharge requirements for the FRWRD where the leachate is currently discharged, are listed in Table 3-2. It should be noted that the leachate may or may not continue to be discharged to this particular POTW.

An on-site pretreatment facility would require the construction of a treatment building; installation of tanks, piping, gauges, valves, fittings, pumps, electrical controls, and meters; and connection of utility service to the building. Construction activities would not encroach upon or impact the adjacent wetlands or floodplain.

This alternative would eliminate the hazards associated with overland transport of leachate to an off-site POTW, and would accommodate the increased volume of leachate associated with increasing leachate collection efficiency at the Site. The leachate collection alternatives presented previously are intended to bring about the reduction of leachate levels throughout the landfill.

Currently, approximately one gallon per minute (gpm) of leachate is pumped and transported to a POTW (1,500 gpd). The quantity of leachate removed would initially increase if an enhanced leachate collection system is installed at the site. For this alternative an initial increase in the extraction rate has been assumed. An agreement/permit with/from the local POTW would be required. The permit would specify the leachate constituent concentrations and acceptable leachate quantities that could be effectively handled by the POTW. A pretreatment facility would be designed and constructed to attain the pretreatment level required by the POTW, if necessary. Monitoring would be performed at the frequency specified by the POTW to ensure compliance with the POTW's requirements.

After construction of this system, inspections would be performed on a monthly basis to ensure proper operation of pumps, switches, controls, warning lights, telemetry systems, and building vents. Maintenance, adjustments, and repairs to the system would be made as necessary.

Construction of this leachate treatment alternative can be completed in one construction season and can occur concurrently with the cap restoration with the following estimated costs:

- Capital Cost..... \$476,000
- Annual O&M ..... \$747,000
- Total Present Worth (30 yrs @ 7%)..... \$9,750,000

### **3.8.3 LT3 – Treatment of Leachate, Surface Discharge**

This alternative involves treatment of leachate to meet surface water discharge standards. A combination of multiple treatment technologies would likely be required to provide the necessary level of treatment to reduce all of the leachate constituents to required levels. Table 3-4 indicates potential treatment technologies for compounds typically found in landfill leachate.

An on-site treatment facility would require the construction of a treatment building; installation of tanks, piping, gauges, valves, fittings, pumps, electrical controls, and meters; and connection of utility service to the building. Construction activities would not encroach upon or impact the adjacent wetlands or floodplain. Operation and maintenance of the facility would require the services of a certified treatment plant operator for a minimum of 20 hours/week to operate, maintain and perform the required monitoring of the treatment systems.

A surface water discharge (NPDES) permit would be required for this alternative. Leachate would be extracted at a rate sufficient to control the off-site migration of leachate, treated, and discharged to a surface water location of adequate assimilative capacity. Since adjacent Sequoit Creek is not suitable for discharge due to its low assimilative capacity, another more remote surface discharge location would have to be identified for this alternative to be considered feasible. To demonstrate compliance with the NPDES permit

requirements, monitoring at a frequency to be specified in the permit would need to be performed.

The treatment system would require continuous operation and ongoing routine maintenance. After construction of the system, inspections would, at a minimum, be performed on a monthly basis to assure proper operation of pumps, switches, controls, warning lights, telemetry systems, and building vents. Maintenance, adjustments, and repairs to the system would be made as necessary.

Construction of this leachate treatment alternative would require a significant effort due to the pipeline construction to an adequate outfall location. Therefore, this alternative would likely extend over two construction seasons. The following costs are estimated for LT3:

- Capital Cost..... \$1,843,000
- Annual O&M ..... \$595,000
- Total Present Worth (30 yrs @ 7%)..... \$9,227,000

### **3.9 GROUNDWATER ALTERNATIVES**

#### **3.9.1 GW1 - No Further Action - Continue Groundwater Monitoring**

The existing groundwater monitoring program would be continued under the no further action alternative. As stated in the current IEPA Site permit, additional monitoring points would be established during the CERCLA RD process, and a formal monitoring program would be presented to the Agencies at that time. The groundwater monitoring frequency will be quarterly, in accordance with 35 IAC 811.319(a).

The following estimated costs are associated with the No Further Action groundwater monitoring alternative:

- Replacement of VW4 with VW7 ..... \$694,000
- Annual Cost..... \$63,000
- Total Present Worth (30 yrs @ 7%)..... \$1,475,800

To mitigate potential adverse environmental impact posed by groundwater contamination identified in the RI, the nearest public well, VW4, located in the industrial park, was replaced with a new well (VW7) which is located more than one mile from the site

#### **3.9.2 GW2 - Monitored Natural Attenuation**

Under this alternative, in addition to the continuation of the groundwater monitoring program, a groundwater monitoring plan would be implemented to assess the effectiveness of natural attenuation in reducing the contaminant impacts to groundwater. The groundwater monitoring program would monitor the quality of groundwater from both the surficial sand and the deep sand and gravel aquifers. Preliminary modeling indicates that compounds in the vicinity of US3D should attenuate over a relatively short distance. To

verify that attenuation is, in fact, occurring, a pre-design investigation consisting of one or possibly two monitoring wells will be performed. The wells will be located approximately 300 feet downgradient of US3D and will be screened in the deep sand and gravel aquifer at a depth of approximately 85 feet below ground surface. A groundwater management zone (GMZ) cannot be established (in accordance with 35 IAC 620.250) because a contaminant plume requiring corrective action does not exist. In the event that a contaminant plume is discovered as part of the pre-design investigation, the need for establishing a GMZ would then be reevaluated. Wells to be monitored would be selected based on the RI analytical results and their location relative to known groundwater flow directions (generally west, along Sequoit Creek, in the surficial sand aquifer, and southwest in the deep sand aquifer). Wells located along the south and southwest perimeter of the site would be likely candidates for inclusion in the groundwater monitoring plan, including:

G11S	US3S	G14D	W3D
G11D	US3D	R103	W4S
G14S	US4D	G102	W5S

The upgradient monitoring wells (G14S, G14D, G11S, and G11D) and the selected downgradient monitoring wells include wells which are screened in the surficial sand aquifer and wells which are screened in the deep sand aquifer at the Site. Monitoring wells US3D, US4D, and W3D form a linear downgradient monitoring network which is screened in the deep aquifer. Periodic sampling from this network of wells would be performed to gauge the effectiveness of remedial measures and document groundwater conditions in the vicinity of the site. As groundwater contaminant conditions continue to be evaluated during the 30-year O&M period, monitoring wells and/or private wells may be added to the groundwater monitoring well network. (See Figure 15 for the location of the monitoring wells.)

The selected monitoring wells would be sampled on a quarterly basis for 30 years, in accordance with 35 IAC 811.319(a)(1)(A), and groundwater samples would be analyzed for the current list of analytes, including boron, chloride, iron, ammonia nitrogen, total dissolved solids, and zinc. VOCs would be monitored on a yearly basis in accordance with 35 IAC 811.319(a)(3)(C). However, for the first five years of monitoring, VOC groundwater monitoring frequencies will be quarterly. After the first three years of monitoring, USEPA may approve a monitoring frequency of semi-annually for the final two years of the five-year-period, based on a review of three years of VOC groundwater monitoring data. After the first five years of monitoring are complete, USEPA will consider a yearly VOC monitoring frequency, based on data reviewed. In addition, natural attenuation parameters would be monitored in select groundwater monitoring wells, specifically near the southwest corner of the Site. These parameters would include: total organic carbon, biological oxygen demand, nitrate nitrogen, nitrite nitrogen, total kjeldahl nitrogen, orthophosphate, sulfate, conductivity, alkalinity, dissolved oxygen, pH, temperature, and redox potential. Additional natural attenuation parameters may be considered, and will be proposed in the monitoring plan to be developed during the RD phase. The monitoring program would be capable of recording changes in groundwater contaminant concentrations over time. After a baseline analytical database was established,

it is anticipated that some reduction in analytes or monitoring points would be appropriate, and the Agencies would be petitioned for such a reduction in accordance with 35 IAC 811.319.

Installation of the two wells for the pre-design investigation can be completed in one construction season and can occur concurrently with the cap restoration. The well installation costs are included with the following estimated costs associated with monitored natural attenuation:

- Replacement of VW4 with VW7 ..... \$725,300
- Annual Cost..... \$69,700
- Total Present Worth (30 yrs @ 7%)..... \$1,590,300





## 4.0 EVALUATION OF REMEDIAL ACTION ALTERNATIVES

This section evaluates each remedial alternative presented in Section 3 with respect to seven of the nine criteria defined in the NCP in section 300.430(e)(9)(iii). Evaluation of each alternative's ability to satisfy the other two criteria, state/support agency acceptance and public acceptance, cannot be completed until public comment on the Proposed Remedial Action Plan has been received and evaluated. The purpose of this detailed evaluation is to determine how well each of the alternatives satisfies the remedial action objectives defined in Section 3 and the evaluation criteria mandated by CERCLA, and ultimately, to provide the information needed by the Agencies to make the appropriate risk management decisions.

### 4.1 CERCLA REQUIREMENTS

The statutory considerations embodied within Section 121 of CERCLA were assembled in NCP §300.430(e)(9) into the seven criteria that are to be used in the detailed evaluation of any remedial alternative. These seven criteria are:

- **Overall Protection of Human Health and the Environment** which addresses the degree to which a remedy provides adequate human health protection by virtue of how risks posed by each pathway are eliminated, reduced, or controlled through treatment, engineering controls, or institutional controls.
- **Compliance with ARARs** addresses the degree to which a remedial alternative satisfies all of the applicable or relevant and appropriate requirements of other federal and State environmental statutes and/or provides the grounds for invoking a waiver of specific ARARs.
- **Long-Term Effectiveness and Permanence** refers to the ability of a remedy to maintain reliable protection of human health and the environment over time, once cleanup goals have been met.
- **Reduction of Toxicity, Mobility, or Volume Through Treatment** is the anticipated performance of the treatment technologies which a remedy may employ.
- **Short-Term Effectiveness** addresses the time needed to achieve an adequate level of protection. It also evaluates any adverse impacts on human health and the environment that may be posed during the construction and implementation period, until such time as the cleanup goals are achieved. Short-term effectiveness can be important in cases where one remedy can be implemented in a considerably shorter period than another remedy. In such a case, the former may be preferable, even if it provides a lesser degree of protection, since a significant level of protection is provided more rapidly.

- **Implementability** is the technical and administrative feasibility of a remedy, including the availability of the materials and services needed to complete a particular alternative.
- **Cost** includes estimated capital and long-term operation and maintenance costs, and also includes net present worth calculations.

In addition to these seven criteria, Section 121 of CERCLA provides for state involvement in remedy selection, and sections 113 and 117 provide for public participation during remedy selection. Under CERCLA, these two additional criteria (state involvement and public participation) are applied to the remedy selection process following receipt of Agency comments on the FS (for support agency acceptance) and after the public comment period following publication of the Proposed Remedial Action Plan.

The NCP §300.430(f)(1)(i) further divides these nine criteria into the following three categories:

- **Threshold criteria** which cover the overall protection of human health and the environment, and compliance with ARARs, are requirements that each alternative must meet.
- **Balancing criteria**, which cover the anticipated costs, the degree to which each remedial alternative reduces toxicity, mobility and volume through treatment, the short-term effectiveness, long-term effectiveness and permanence, and the ability to implement each alternative.
- **Modifying criteria**, which cover state/support agency acceptance and public acceptance.

Each of the alternatives described in Section 3 is evaluated in terms of the threshold and balancing criteria in this section. Each evaluation is organized by capping, gas extraction, leachate collection and leachate treatment alternatives.

## 4.2 NO FURTHER ACTION EVALUATION

As summarized in Section 1, the Site has an existing final cover (35 IAC 807 cover) over the old and new landfills, a leachate collection system, a landfill gas collection system and a groundwater monitoring program. These systems are in place and have been operational for the last nine years, since the Site closure was completed in 1989. Subsequent studies conducted at the Site include a comprehensive RI Report and a Baseline RA. The results from the Baseline RA indicate that there are risks of approximately  $9 \times 10^{-4}$  in the off-site deep sand and gravel aquifer.

The Baseline RA considered the results from the RI Report to determine if the Site posed risks which may exceed the  $1 \times 10^{-6}$  RME cancer risk threshold or a hazard index greater than 1. The Baseline RA indicates that manganese was the only constituent that exceeded the RME hazard index of one. However, the Baseline RA de-emphasized the importance of the manganese risk, based on several factors. For carcinogenic risk, beryllium, arsenic, and vinyl chloride exceeded the RME excess lifetime cancer risk of  $1 \times 10^{-6}$ . The Baseline RA concluded that beryllium and arsenic are probably not Site-related.

Most significantly, the only cumulative pathway risk which exceeded an RME lifetime cancer risk of  $1 \times 10^{-4}$  was the hypothetical future use of the off-site deep sand and gravel aquifer. The cumulative risk for this potential future pathway was calculated to be  $9 \times 10^{-4}$  due to the presence of vinyl chloride. The Baseline RA considered the sample analytical results from off-site wells US03D and W03D to establish the risk associated with the vinyl chloride in the off-site deep sand and gravel aquifer. US03D was sampled twice during the RI and vinyl chloride was detected in the well at 28 and 35  $\mu\text{g/L}$ . Samples collected from W03D (also downgradient of the site and side-gradient to US03D) did not exhibit detectable concentrations of vinyl chloride. Therefore, although two samples from US03D indicated vinyl chloride was present in the deep sand and gravel aquifer, data from W03D indicate that the areal extent of the vinyl chloride impact may be limited. These two wells are approximately 600 feet apart. Well US03D is located downgradient of the landfill, in the Sequoit Acres Industrial Park. W03D is also located downgradient of the landfill, but is upgradient of the Sequoit Acres Industrial Park.

The Baseline RA utilized only two rounds of analytical data to establish this risk. The uncertainty regarding the presence of vinyl chloride in the deep sand and gravel aquifer is highlighted by the analytical data obtained over the course of the routine sampling of Village of Antioch well VW4, which was located approximately 80 feet west of US03D. Vinyl chloride, of unknown origin, had been detected sporadically in samples from this well over several rounds of sampling between 1984 and 1989. In the 24 subsequent monitoring rounds spanning the period from 1989 through 1994, vinyl chloride was not detected. The last detection of vinyl chloride in Village well VW4 was in a sample collected on August 23, 1989. The results also indicate a decreasing trend in the vinyl chloride concentrations in VW4 over time (Table 4-1), with no measurable impacts over a period of five years. In spite of the fact that VW4 was pumping up to 650 gpm and is only 80 feet from US03D, which according to the gradient data in the RI, is within the radius of influence of VW4, the vinyl chloride contamination at US03D did not decrease the time, while the vinyl chloride contamination at VW4 did. These facts argue that the vinyl chloride may have been an artifact of an incidental, non-recurring release, and do not indicate gradually deteriorating groundwater conditions that may be attributable to ongoing releases from landfilled wastes. Again, one must note that wells US03D and VW4 are located in an industrial park with documented filling activities as well as industrial and hazardous waste handling and storage operations.

Arsenic was detected in samples collected from municipal wells VW-3 and VW-5 (2.1B  $\mu\text{g/L}$  and 4.5B  $\mu\text{g/L}$ , respectively), but based on background and downgradient data, arsenic is not a compound associated with the Site. The arsenic concentrations detected in these

wells during the RI were well below the legally-enforceable MCL of 50 µg/L for arsenic. Furthermore, VW-5 is located much further downgradient of the Site than VW-3, yet exhibits the higher of the two concentrations of this contaminant. In summary, the risk associated with the arsenic detected in the municipal wells is within the range of acceptability (i.e.,  $9 \times 10^{-5}$ ), and the spatial distribution of the arsenic detections does not support the conclusion that the arsenic represents a Site-related release.

Beryllium, according to the Baseline RA, poses a cumulative RME excess lifetime cancer risk of  $7 \times 10^{-5}$  within the off-site surficial sand aquifer. However, beryllium was only identified as a compound of potential concern because RI background data for beryllium were not available. Beryllium was detected (at 0.95 µg/L) in only one out of four groundwater samples collected from the off-site surficial sand aquifer. It was also detected in only one out of 34 regional background samples at a concentration of 1 µg/L. Based on these facts, it is possible that these beryllium concentrations are naturally occurring within the surficial sand aquifer. Significantly, beryllium was not detected in samples obtained from the surficial sand aquifer on-site monitoring wells, and it can therefore be concluded that these detections are probably not associated with the H.O.D. Landfill. Furthermore, the surficial sand aquifer is of limited extent and is not used for drinking purposes. The installation of wells into the surficial sand for the purpose of obtaining drinking water is prohibited near the Site by 35 IAC which establishes setback requirements for drinking water wells placed near landfills.

The manganese concentration in the off-site surficial sand groundwater used to calculate long-term risks was the single maximum detected value in one well. The manganese concentrations detected in the other off-site surficial sand monitoring wells were all at least ten times lower than the maximum. All of the detected manganese concentrations in off-site surficial sand groundwater wells were less than the levels at which minor neurological effects (based on neurologic exam scores) have been observed in individuals chronically exposed to manganese in drinking water (Kondakis et al. 1989). Also, there is no actual current use of water from the off-site surficial sand monitoring wells.

Future private residential use of the deep sand and gravel aquifer is unlikely, given that the Village of Antioch has enacted an ordinance that requires properties within the Village limits to be connected to the public water supply. In addition, 35 IAC 811 also prohibits the installation of drinking water wells in the immediate vicinity of a known landfill.

The No Further Action alternative assumes that the Site does not warrant remedial action under CERCLA. The Site has been closed under the State of Illinois Permit Program for solid waste landfills. Since the Site stopped accepting waste before October 9, 1993 and was originally closed under 35 IAC 807 requirements, it is exempt from the requirements of 35 IAC 814, except for 814.101(b)(3) (additional requirements for municipal, solid waste landfills operating under 35 IAC 807 permits). Therefore, 35 IAC 807 is applicable. However, the following post-closure care requirements are relevant and appropriate to the H.O.D. Landfill site: 35 IAC 811.111(c), 811.308(a)(c)(d)(e)(f)(g)(h), 811.310, 811.318, and 811.319(a).

Therefore, because under a no further action alternative the Site would revert back to the State Permit Program under 35 IAC 807, a brief description of the proposed actions under the State of Illinois Permit Program are presented below.

#### **4.3 PROPOSED ACTIONS UNDER THE ILLINOIS PERMIT PROGRAM**

Under the State of Illinois Permit Program, several actions would take place to bring Site conditions into compliance with the existing Illinois Operating Permit #1975-22-OP for H.O.D. Landfill.

To comply with the 35 IAC 807 regulations, the following will be done:

- The cap will be repaired with sufficient compacted clay and an appropriate vegetative layer such that it meets or exceeds the requirements of the existing 35 IAC 807 Permit.
- Leachate collection will continue, and will be automated as necessary to maintain the leachate levels and eliminate leachate seeps.
- Leachate will continue to be treated at a licensed POTW.
- The existing LFG system will be upgraded, potentially activating all or part of the existing system.
- Groundwater and surface water will continue to be monitored, with the possible expansion of the current system to include more wells or analytes.
- Village well VW4 will be taken out of service (already completed) and permanently sealed.

As discussed in Section 2, understanding the interrelationships between capping, LFG collection and treatment, and leachate collection and treatment is paramount in selecting an appropriate site remedy. Based on the conclusion of the Baseline RA, the driving risk at the Site is vinyl chloride in the deep groundwater. Therefore, if volatile compounds, including PCE, TCE, 1,2-DCE (all chemical precursors of vinyl chloride) and vinyl chloride can be reduced in the waste mass, the potential for dissolution into the groundwater can be significantly reduced. The most efficient way to reduce these compounds in the waste mass is by effectively collecting LFG and leachate at the Site. Minimization of infiltration is not an appropriate goal at this Site because of the identified Site characteristics: areas of the landfill were designed as "zone of saturation" (waste below the water table) fill areas. Therefore, leachate extraction and control will always be a component of the long-term O&M of the Site. Thus, minimization of infiltration will only be a small factor in the overall leachate maintenance program. In addition, an adequate landfill cap (repairing the existing cap to eliminate low areas, ponded water, and leachate or LFG seeps) will help to limit infiltration, and thus the production of leachate. However, it is recognized that with improved LFG and leachate collection, the importance

and benefits of a completely reconstructed cap are significantly decreased. Therefore, by implementing the above-listed actions at the Site, LFG and leachate controls will be enhanced significantly, thereby reducing concentrations of VOCs in the waste mass. Each of the above bulleted items proposed under the State Permit Program is described below.

### **Cap Repair**

The "old landfill" area is covered with a continuous cap that is generally in excellent condition. No low spots, bare vegetation, leachate or LFG seeps have been noted in the "old landfill" area. Therefore, cap repair will focus on the "new landfill" area. The "new landfill" area will be repaired to re-establish the approximate Site grades that existed at the time of Site closure in 1989. This grading will control infiltration, and promote positive drainage. Areas where leachate seeps have been noted will be overexcavated and backfilled with compacted clay, effectively sealing the landfill cover. To minimize erosion, the cap will have a vegetative cover and a continuous sloped surface consisting of a 2% minimum slope that will promote positive and continuous drainage. The side slopes in the "new landfill" portion of the Site will be regraded such that they are 33% maximum and will be repaired, as needed. The cap will allow for a maximum average annual infiltration rate of no greater than 2.48 inches per year (based on the HELP model for the 35 IAC 807 compliant cap) and will be repaired in a fashion that will facilitate the post-closure care goal of minimizing further cap maintenance. By controlling infiltration, potential for leachate seeps will be reduced.

### **Leachate Collection and Treatment**

The leachate collection system will also be automated in order to maintain leachate levels at the "leachate maintenance level," defined in the existing operational permit to be two feet below the water level elevation contemporaneously measured in well G11D. Existing materials (wells and header piping) will be used to the fullest extent possible to minimize costs and time required to implement this remedial action. If conditions warrant (i.e. elevated leachate levels and recoverable quantities), the installation of leachate pumps will be considered in the RD stage for all or some of the existing monitoring wells and extraction points within the waste mass. Leachate extraction at specific points on the Site will also be evaluated to address leachate seeps.

Leachate removal will be increased from the current maximum rate of approximately 1 gallon per minute to a rate necessary to maintain the leachate maintenance level. An estimated steady-state rate of 5.25 gallons per minute is anticipated after an initial start-up period when leachate extraction volumes may be higher. To accommodate the increased leachate volume, two options will be evaluated: (1) pretreatment and discharge to a POTW, and (2) direct discharge to a POTW.

### **Landfill Gas Collection and Treatment**

If an active LFG System is to be implemented, as is likely, the extent of the system will be defined during the Remedial Design Phase. The individual wells would likely be connected with a header pipe to a single flare point and automated in order to monitor/quantify the mass of VOCs removed from the Site. A well radius of influence (ROI) of 100-150 feet is

sufficient for LFG Systems at municipal solid waste landfills. Existing materials (wells) will be used to the fullest extent possible to minimize costs and expedite the implementation of this remedial action.

### **Monitoring**

The current groundwater and surface water monitoring system in place at the Site will continue to be used to ensure the landfill is not detrimentally affecting the surrounding groundwater and surface water. It is probable that additional monitoring points will be established, and additional analytes will be monitored on a routine basis.

### **Elimination of Village Well VW4**

As described in Section 1, VW4 has been taken out of service and replaced with VW7, which is further away from the Site (Figure 6). The Village of Antioch has no further plans to install more wells in the vicinity of the Site, and is not able to use the water from VW4 for drinking water supply. VW4 will be permanently sealed, contingent on the approval of the Village of Antioch.

### **Institutional Controls**

Institutional controls such as deed restrictions, site fencing, access restrictions, and warning signs will be used to implement institutional controls at the Site. In addition, the Village of Antioch Water Works and Sewage Ordinance Sections 50.008, 52.009, and 52.011, requiring properties to connect to the public water supply will serve to virtually eliminate the potential use of the aquifers near the Site.

## **4.4 EVALUATION OF ALTERNATIVES**

The remedial actions described above were developed after consideration of several discrete remedial options. In order to select appropriate specific remedial actions at the Site, several alternatives for capping, landfill gas collection and treatment, and leachate collection and treatment, were evaluated, and are presented herein, to facilitate review and evaluation of the post-closure care requirements. This alternatives evaluation compares potential post-closure care alternatives against seven of the nine criteria defined in the NCP in section 300.430(e)(9)(iii).

### **4.4.1 Capping Alternatives Evaluation**

The capping alternatives consist of: C1 - Repairing the "new landfill" area cap to comply with the existing closure/post-closure plan; C2 - Reworking the existing cover to form an 807-compliant cap; C3 - Supplementing the existing cover to form an 811-compliant cap.

#### **4.4.1.1 Overall Protection of Human Health and Environment.**

The Baseline RA demonstrated that the only risk to human health and the environment greater than  $1 \times 10^{-4}$  potentially associated with the Site is that posed by the ingestion of vinyl chloride-contaminated water from the off-site deep sand and gravel aquifer. Repairs to the cap would not further reduce the specific risk posed by vinyl chloride since a repaired cap would not directly mitigate the possibility of ingestion of vinyl chloride from



the off-Site deep aquifer. The goal of the existing cap has been to provide adequate protection to human health and the environment by preventing dermal contact with landfill contents, reducing contaminant leaching to groundwater, controlling surface water runoff and erosion, and reducing the potential for direct inhalation of LFG by providing increased containment for LFG. It is important to note that the goal of the cap is not to minimize or eliminate infiltration. Therefore, addition of an extremely thick (4 feet or greater above the clay) cap or a drainage layer above the clay, although considered, is not recommended for this Site.

In order to ensure that the adequate level of protection of human health and the environment provided by the cap is maintained, the existing cover on the "new landfill" area would require repairs which would involve regrading the low areas on Site, and recompact cover soils to repair leachate seeps and to produce a continuous cap in accordance with the description in Section 3.4.1. In this manner, the "new landfill" area would be brought up to existing permit standards. The cap repairs would reduce storm water infiltration to approximately 1.6 inches/year, thereby reducing leachate production. Control of leachate production over time would help contain Site contamination and control the potential for contaminant migration from the Site. This is a response action objective in the "Presumptive Remedy for CERCLA Municipal Landfill Sites" guidance.

Alternatives C2 and C3 - As previously mentioned, the Baseline RA demonstrated that the only risk to human health and the environment greater than  $1 \times 10^{-4}$  potentially associated with the Site is that posed by the ingestion of vinyl chloride-contaminated water from the off-site deep sand and gravel aquifer. The cap improvements prescribed under Alternatives C2 and C3 would not further reduce the specific risk posed by vinyl chloride because improvements would not eliminate this ingestion pathway consideration. It is also important to note that augmenting the existing cap structure could exacerbate environmental threats posed by LFG, as discussed in Section 2.3.3. A much "tighter" cap could increase the rate of partitioning of LFG constituents into leachate and groundwater, thus elevating the potential level of risk associated with the Site. As a result, Alternatives C2 and C3 would elevate risk levels above those associated with Alternative C1. Alternative C3 would be the "worst case" alternative for this reason; also, Alternative C3 could introduce further risks because it would involve the manipulation of cover materials on a much larger scale than the other two alternatives. Benefits provided by Alternatives C2 and C3 would include preventing direct contact with landfill contents, reducing contaminant leaching to groundwater, controlling surface water runoff; however, all of these benefits could be achieved with far less risk by making simple repairs to the cap, as described under Alternative C1. Reworking the existing cover for both Alternative C2 and C3 would involve regrading of the site prior to recompaction of the barrier layer of the cap and placement of the cover soils. Both alternatives would reduce rainfall infiltration through the cap slightly less than Alternative C1 (an estimated maximum of approximately 2.0 inches/year and 2.1 inches/year for Alternatives C2 and C3, respectively), as modeled by the HELP model Version 3 (see Appendix C) and ultimately would reduce leachate head levels within the waste mass. The infiltration values for these cap alternatives are higher than that of the C1 alternative because the added thickness of soil on top of the compacted clay resulted in a higher volume of pore space water available to infiltrate through the clay.

It is important to note that since a portion of the Site was constructed with the base of the landfill below the water table (a "zone of saturation" Site), reduction of infiltration alone will not prevent leachate generation. Therefore, a balance between the capping alternative and the leachate collection alternative must be considered when selecting the Site remedial components. Capping alternatives C2 and C3 do not reduce infiltration more than C1, and because of the zone of saturation, leachate generation and collection will be required regardless of what cap alternative is selected. Therefore the additional disturbance necessary to construct C2 and C3 cap alternatives and the increased infiltration through these caps make these alternatives less protective of human health and the environment.

#### **4.4.1.2 Compliance with ARARs.**

ARARs that apply to capping alternatives involve protection of the floodplain, wetlands, and surface waters, and compliance with 35 IAC 807 capping and 811.111(c) post-closure care requirements. Capping alternatives C1, C2, and C3 all comply with the applicable State 35 IAC 807 requirements by providing cover design and performance to include, at a minimum, a two-foot thick low-permeability layer of compacted soil overlain by adequate cover soils to minimize erosion and maintenance requirements. Alternatives C1 and C2 also comply with the relevant and appropriate 35 IAC 811.111(c) post-closure requirements, since they include the 30-year operation and maintenance described in the 811.111(c) ARAR. Alternative C3, by definition, complies with the 811.111(c) post-closure requirements. All of the alternatives would involve erosion control and staged construction activities such that the adjacent wetlands and floodplain would be protected.

#### **4.4.1.3 Long-Term Effectiveness and Permanence.**

Alternatives C1, C2, and C3 address long-term protection by controlling stormwater infiltration into the landfill, thus decreasing the potential for contaminant transport into the leachate and groundwater. These alternatives, which combine both access restrictions and improved covers, would prevent direct contact with landfill contents. They would also minimize future erosion and control surface water runoff by implementation of the maintenance plan described for each alternative. The soil cover of each of the alternatives can last indefinitely if correctly maintained.

#### **4.4.1.4 Reduction of Toxicity, Mobility or Volume Through Treatment.**

Capping alternatives do not involve treatment and therefore cannot be evaluated against this criterion.

#### **4.4.1.5 Short-Term Effectiveness.**

The potential short-term impacts on the community, environment, and construction workers during site construction activities were evaluated. These potential impacts include noise, dust, erosion, dermal contact with waste, and increased truck traffic.

Alternative C1 would have relatively low short-term construction impacts. These impacts may include additional noise and dust generation due to soil relocation/placement during cap regrading and waste consolidation. Since this alternative would primarily involve

regrading and recompacting areas of the upper layer of the existing cap, dermal contact with the waste mass should not be a concern. Potential dermal contact with the waste mass would be minimized through the use of personal monitoring and protective equipment (if necessary). Equipment decontamination would be implemented, thus further reducing the potential concern for dermal contact. Construction activities would be performed in accordance with agency-approved site health and safety plans. Noise levels increase during construction; however, noise can be minimized by maintaining noise control devices on construction equipment. Wearing hearing protection can also reduce the effects of heavy machinery noise on site workers. Fugitive dust emissions would occur during construction; however, measures can be taken to minimize the amount of dust generated by the watering of construction areas and roads, and the potential use of dust masks by site workers. Additionally, erosion control measures and protection of Sequoit Creek from sedimentation would be conducted during construction and thereafter, as needed. This alternative would take approximately six weeks to construct based on moving approximately 6,000 cy of material per day, five days per week (Appendix B).

Alternative C2 would also have relatively low short-term construction impacts. These impacts may include potential dermal contact with waste, and additional noise and dust generation due to soil relocation/placement and waste consolidation during cap construction. Construction activities would be performed in accordance with agency-approved site health and safety plans, which would include personal monitoring, protective equipment (if required), and equipment decontamination recommendations and therefore would reduce the potential concern for dermal contact. Noise levels increase during construction; however, noise can be minimized by maintaining noise control devices on construction equipment. Wearing hearing protection can also reduce the effects of heavy machinery noise on site workers. Fugitive dust emissions would occur during construction; however, measures can be taken to minimize the amount of dust generated by the watering the construction area and roads, and the potential use of dust masks by site workers. Additionally, erosion control measures and protection of Sequoit Creek from sedimentation would be conducted during construction and thereafter, as needed. This alternative would take approximately 21 weeks to construct based on moving approximately 6,000 cy of material per day, five days per week (Appendix B).

Alternative C3 would have some short-term construction impacts, including increased dust, noise, and the potential for dermal contact with waste. As stated above for Alternative C2, measures can be taken to minimize all of these construction impacts. This alternative may also involve importing supplemental clay to complete the compacted clay cap. Therefore, an increase in truck traffic, noise, and dust generation could be expected during the construction period, which could affect nearby community roads. Construction is expected to take 26 to 32 weeks and would likely extend over the course of two construction seasons. If a clay borrow site is needed, it would also experience short-term construction impacts requiring dust control, noise control, erosion control, and surface water management. These impacts would be addressed using the same measures outlined above to minimize impacts at the H.O.D. Site.

#### **4.4.1.6 Implementability.**

Alternatives C1 and C2 would require the coordinated work of an earthwork contractor with a landscape subcontractor. Alternative C1 could be implemented with a minimum of earthwork activity, limiting the activity to the low areas of the Site only. Alternative C2 would require more disturbance of surface soils, and therefore more earthwork and compactive effort. Under either alternative, off-site materials are not expected to be required to complete the cap construction. Earthwork contractors with landfill capping experience are readily available in the area of the Site. An agreement with the adjacent property owner would be necessary for access to consolidate the off-Property waste at the northern edge of the "old landfill" onto WMII property. Both C1 and C2 could be implemented in one year.

Alternative C3 would involve the coordinated work of an earthwork contractor with a landscape subcontractor. A clay source would likely be required which can provide clay meeting the quantity needs and quality specifications established for the Site. Approximately 103,000 cy of quality clay meeting the maximum permeability of  $1 \times 10^{-7}$  cm/s would be required to construct a three-foot thick barrier layer. Prior to transporting off-site clay, weight restrictions and other local road requirements would need to be evaluated. An agreement with the adjacent property owner would be required for access to consolidate the off-Property waste at the northern edge of the "old landfill" onto Site property. C3 may require two construction seasons to implement the entire capping remedy.

#### **4.4.1.7 Costs.**

Table 3-3 indicates costs for the capping alternatives. Costs include present worth of capital and Operation and Maintenance (O&M) costs. The detailed cost estimates are contained in Appendix D. Alternative C1 is estimated to cost approximately \$2.7 million dollars, and reduce infiltration by approximately 2.3 inches per year (to approximately 1.6 inches per year). Alternative C2 will cost approximately \$6 million dollars, and only reduce infiltration by 2.5 inches per year (to 2.0 inches per year). In other words, if C2 was implemented, the additional \$3.4 million would not result in less infiltration but would actually allow more infiltration due to additional pore space water. C3 will potentially cost from \$8.0 to \$11.3 million dollars, depending on the use of existing clay, and will actually be less effective than C2, reducing infiltration to 2.1 inches per year. Therefore, C1 is the most cost effective capping solution, by having the greatest impact on infiltration control for the least cost.

#### **4.4.2 Gas Collection and Treatment Alternatives Evaluation**

The gas collection/treatment alternatives consist of: G1 - Utilizing the existing passive gas vent system ("new landfill"); G2 - Upgrade and/or supplement the existing LFG collection system ("new landfill" (passive); "old landfill" (active)); and G3 - Install and activate the entire LFG system ("new" and "old landfill").

#### **4.4.2.1 Overall Protection of Human Health and Environment.**

The risks posed by LFG from the Site are attributable to the potential for direct inhalation of LFG and partitioning of LFG constituents, including vinyl chloride, to groundwater. However, it should be noted that the RME excess lifetime cancer risk attributable to inhalation of VOCs from the ambient air at the Site falls well below the  $1 \times 10^{-6}$  threshold (the calculated risk is  $4 \times 10^{-9}$ ), and therefore is considered acceptable.

Alternative G1 proposes utilizing the existing passive gas vent system for the entire landfill. This system has been demonstrated over time to be somewhat effective in venting and flaring LFG, but is not totally effective due to flare blow-out, and corrosion of the vent / flare stacks. If the system is used as originally intended (venting and flaring the LFG on a consistent basis) and is properly maintained, the existing passive system meets the remedial action objectives, and reduces risk to human health and the environment by preventing inhalation of vapors and controlling migration of LFG.

Alternative G2 provides for active extraction of LFG in the "old landfill" area only. The "new landfill" area would continue to use the existing system, following necessary repair of the existing wells and stick flares. If the existing system in the "new landfill" area were used as originally intended and maintained, coverage and efficiency in the "new landfill" area would be provided, along with increased protection from LFG migration or inhalation of vapors. Operation of the existing system in the "new landfill" and a new active system in the "old landfill" area would reduce risk to human health and the environment. This alternative could also be implemented with leachate collection alternative LC3, installation of an active leachate collection system in the "old landfill."

Alternative G3 proposes an active gas extraction system with a treatment flare for the entire landfill. This alternative assumes each installed well has a radius of influence of between 100 and 150 feet, and therefore provides adequate site coverage. LFG would be collected by the wells and piping and would be discharged to a flare system for destruction. This alternative meets the remedial action objectives and reduces risk to human health and the environment by preventing inhalation of vapors and controlling migration of LFG. This alternative would provide the added benefit of further reducing the concentrations of volatile organic contaminants in the leachate by removing them before they partition into the liquid phase. This alternative could also be implemented with leachate collection alternative LC4, installation of a dual extraction system.

#### **4.4.2.2 Compliance with ARARs.**

The State of Illinois, under 35 IAC 811.311, establishes minimum requirements for gas venting and collection systems to ensure the protection of human health. The State has promulgated specific air emission standards for LFG venting and gas collection systems. State of Illinois regulations (35 IAC Part 218) require that VOC emissions from the Site must not exceed 25 tons/year, because the Site is located in an ozone non-attainment area. Other pertinent State of Illinois air emission standards regulate particulate matter, sulfur, organics, carbon monoxide, nitrogen oxides and hydrogen sulfide (35 IAC Parts 212 - 217). There are also general provisions for the control of gas emissions.

Alternatives G1 would comply with the above-mentioned ARARs only if the existing system was repaired so that it could be operated as originally intended, and maintained so that it could be operated continuously. This alternative, because it relies on dated technology (passive stick-type flares), may not be as efficient at managing LFG emissions.

Alternative G2, which combines the dated passive stick flare technology in the "new landfill" area, and an active system in the "old landfill" area, would potentially meet the ARARs if the "new landfill" system was repaired and maintained so that it could be continuously operated. However, the dated technology used in the "new landfill" may not be as efficient for controlling LFG emissions.

Alternative G3 satisfies the accepted presumptive remedy objectives for landfill gas management, which is gas collection and treatment. This alternative would satisfy 35 IAC 212 through 218 requirements through active gas control and treatment and would include monitoring to ensure continued compliance.

#### **4.4.2.3 Long-Term Effectiveness.**

Alternative G1, if maintained and operated continuously, could potentially provide long-term effectiveness. Over the years, LFG generation would decline and the LFG extraction system, if maintained, would continue to perform. The "old landfill" portion of the site is approximately 30 years old and gas generation is likely declining. The "new landfill" portion of the site is approximately 13 years old. LFG generation in this area of the Site is also declining, although it remains greater in this area than in the "old landfill". If the existing system were repaired and operated continuously, LFG in both areas could potentially be effectively controlled by this alternative.

Alternative G2, because of the use of the passive stick flare technology in the "new landfill" area, would potentially provide reduced long-term effectiveness, because there is evidence that the existing passive system used for LFG control in the "new landfill" area is not controlling landfill gas completely, and the "new landfill" area would be producing a greater quantity of LFG for a longer period of time than the "old landfill" area. However, if the existing system were repaired and operated continuously, this alternative would potentially control LFG emissions from the Site.

Alternative G3 provides increased long-term effectiveness. This alternative provides active extraction of LFG, thereby reducing the VOC concentrations within the waste mass. This active system utilizes Reasonably Available Control Technology (RACT) for control of LFG, and would be effective at eliminating LFG emissions from the Site.

#### **4.4.2.4 Reduction of Toxicity, Mobility or Volume Through Treatment.**

All of the alternatives reduce the volume of LFG via combustion. Alternative G1 utilizes the existing stick flares. These flares can be affected during periods of low gas flow, or under high winds. Keeping these flares lit requires increased monitoring and O&M. G2 uses a combination of passive and active control for LFG, incorporating both the benefits of an active system and the increased maintenance issues associated with G1. Alternative G3 would use an active system to collect LFG from the entire waste mass and would

feature combustion at a single point flare, allowing for less labor-intensive O&M. Reduction in toxicity through treatment would be addressed by G1, G2, and G3 provided the flares would stay lit. However, any of the alternatives could allow for periods of time when flares become extinguished and LFG can escape uncontrolled.

#### **4.4.2.5 Short-Term Effectiveness.**

The potential short-term impacts from Alternative G1 include minimal disturbance of the Site during repairs to the existing system. Both G2 and G3 involve the installation of LFG header piping and the potential installation of additional gas extraction wells and a blower/flare station. This work would result in an increase of noise, dust, and the potential for dermal contact with waste by construction workers. Measures can be taken to minimize dust and noise, as previously discussed. Personal protective equipment and decontamination of equipment can reduce the potential for dermal contact and inhalation.

#### **4.4.2.6 Implementability.**

Alternative G1 has already been implemented and would not require additional work beyond repair of existing vents, where necessary, and typical upkeep and periodic replacement of the existing vents and flares (as needed). Operation and maintenance activities (inspections of flares) for this LFG system are many and frequent; however, they are also easily performed.

Alternatives G2 and G3 would involve coordination of earthwork contractors and gas extraction system installation specialists. Materials required for the LFG system construction (piping, blower, flare, fittings, etc.) are readily available, as are the qualified contractors and subcontractors needed to perform the work. Operation and maintenance activities (inspections of flares, settings, controls, telemetry systems) for these LFG systems are required; however, they are also easily performed.

#### **4.4.2.7 Costs.**

Present worth costs of the estimated capital and long-term O&M activities associated with LFG control alternatives are shown in Table 3-2. The detailed cost estimates for these alternatives are presented in Appendix D. The long-term costs of alternatives G1 and G2 are approximately \$840,000 and \$1.2 million dollars respectively. G2 would cost more in capital expenditures. G3 would cost approximately \$1.5 million, because of the increased cost of capital improvements, but would also be the easiest system to maintain and the most reliable system. Alternative G3, because of the increased reliability and effectiveness of a totally active system, and because the additional costs to install a totally active system are relatively minimal (compared with the benefit and reliability of the system), is the most cost effective alternative.

#### **4.4.3 Leachate Collection Alternatives Analysis**

The leachate collection alternatives consist of: LC1 - No further action - Utilize existing system; LC2 - Toe-of-slope leachate collection; LC3 - Upgrade and/or supplement existing system; and LC4 - Active leachate extraction .

#### **4.4.3.1 Overall Protection of Human Health and Environment.**

Alternative LC1 would utilize the existing collection pipes and leachate extraction manholes. Collection of leachate would continue as it has, with approximately 1500 gallons per day (gpd) removed from the landfill. This alternative would not provide additional leachate collection, and would not directly address leachate seeps from the landfill side slopes. However, based on the results of the Baseline RA, the leachate seeps do not pose an unacceptable risk to human health or the environment.

LC2 extends the existing toe-of-slope leachate collection piping in both the "old" and "new landfill" areas. The extended toe-of-slope drains would be installed several feet below the soil cover/waste interface, but would not be installed at the base of the waste. The object of this system would be to maintain the "leachate maintenance level" in accordance with the Site Operational Permit. These additional collection pipes, in conjunction with a repaired or upgraded cap, would actively control leachate seeps on the side slopes of the facility.

Alternative LC3 proposes extension of the existing toe-of-slope collection piping and use of the existing leachate extraction wells in the "new landfill" area. In addition, five new leachate extraction wells (to be installed as part of this alternative) and the existing leachate piezometers, if necessary, will be used for leachate extraction in the "old landfill." Leachate levels within the "new landfill" area would not be expected to significantly decrease under this alternative, although they would be maintained at or below the "leachate maintenance level." This would achieve containment by inducing an inward gradient, which is consistent with the original design of the Site.

Alternative LC4, active extraction of leachate, provides a system in both the "new landfill" and "old landfill" to actively pump leachate from the entire waste mass. By actively extracting leachate from within the waste mass and maintaining an inward gradient, shallow groundwater in the immediate vicinity of the landfill perimeter would be captured. This active system would increase leachate collection volumes and control leachate head levels within the Site. By reducing head levels and maintaining the "leachate maintenance level" within the waste mass, the potential for leachate migration would be reduced and the potential impacts due to infiltration through the cap would be minimized. Capture and control of shallow groundwater from the on-site surficial sand aquifer (as part of the active leachate collection) would result in an increased margin of safety for protection of human health and the environment.

#### **4.4.3.2 Compliance with ARARs.**

The State of Illinois requirements for landfill leachate collection systems, 35 IAC 811.308, includes specifications and design criteria to prevent threats to human health and the environment from leachate releases. Although the Baseline RA indicates that risks posed by leachate seeps at the Site are not unacceptable, these leachate seeps are considered unacceptable under 35 IAC 807 or 35 IAC 811 requirements. Therefore, LC1, which includes the current practice of scheduled manual extraction of leachate from the existing collection pipes and extraction manholes, would not directly address the identified leachate seeps and thus may not comply with ARARs.



LC2, which would add the toe-of-slope leachate drains, would actively control the leachate seeps, but the potential for leachate breakouts or migration to the groundwater, due to the volume of leachate remaining in the landfill, would still be present. LC2, therefore, would be questionable with regard to ARAR compliance.

LC3, which would utilize both automated and manual methods to control leachate appears to comply with the ARARs because the potential for leachate seeps in the "new landfill" is addressed, but the potential for migration to groundwater in the "new landfill" would still exist.

LC4, active collection of leachate from the entire landfilled waste mass, would comply with ARARs by eliminating the potential for leachate seeps, and significantly reducing the likelihood of leachate migration to the groundwater.

#### **4.4.3.3 Long-Term Effectiveness.**

Alternative LC1 would not collect more leachate than is now being collected. Therefore, the increased effectiveness of this alternative for controlling leachate seeps and migration to groundwater would be minimal.

Alternative LC2 would result in an increase in leachate collection quantities in the short term, and also in the long term, if properly maintained. The leachate mound within the waste mass would likely remain, although the potential for seeps would be minimized. This alternative would be somewhat effective in the long-term for minimizing leachate migration to groundwater.

Alternative LC3 also represents an increase in long-term effectiveness, because leachate levels would be controlled within the waste mass in the "new landfill" area. However, the leachate levels would still remain in conformance with the requirements of the IEPA permit for the Site and the current total pathway risk from leachate seeps has been calculated to be well within acceptable limits. However, the minimization of leachate migration to groundwater is not generally addressed by this alternative.

Alternative LC4 would increase leachate collection quantities in the short term, and if maintained, should continue to operate effectively for many years. This increased leachate extraction would reduce leachate levels in the landfill and control the formation of leachate seeps. The reduction of leachate volume within the waste mass would serve to minimize the potential for migration of leachate to groundwater.

#### **4.4.3.4 Reduction of Toxicity, Mobility or Volume Through Treatment.**

Although active collection of leachate does reduce the mobility and volume of leachate within the landfill waste mass, toxicity, mobility and volume of contaminants are not addressed. Therefore, this criterion is not applicable for leachate collection systems.

#### **4.4.3.5 Short-Term Effectiveness.**

Because LC1 uses the existing system, no short term impacts are anticipated. The short-term impacts associated with the installation of leachate collection alternatives LC2 through LC4 would include increased dust, noise, and the potential for dermal contact with contaminants.

All three alternatives LC2, LC3, and LC4 would result in increased noise and dust during construction. In addition, the potential exists for construction workers to have dermal contact with contaminants. Personal protective measures can be taken to minimize these impacts, as discussed previously.

#### **4.4.3.6 Implementability.**

The equipment used for LC1 already exists, and therefore this alternative would be easily implemented. Existing wells and manholes would continue to be used, and upgrades or repairs to these components would be easily made, if necessary.

LC2 would require the installation, via trenching and possible excavation, of corrugated perforated piping at the toe of the landfill slopes. This activity is a standard construction technique and would be readily implemented. Coordination with an earthwork contractor and potentially a subsurface utility (yard piping) contractor would be required. Materials necessary for the installation are readily available in adequate quantities.

LC3 would require installation of wells, installation of header piping, and construction of a blower and flare system in the "old landfill." Coordination of earthwork, utility, and mechanical, and electrical contractors would be necessary. Materials necessary to construct these components (wells, piping, pumps, fittings, blower, instrumentation, etc.) are all readily available. Operation and maintenance activities (inspections of pumps, fittings, controls, telemetry systems, and monitoring of leachate volume) would all be necessary and are also easy to perform.

LC4 would require construction similar to LC3, although it would be implemented in both the "old landfill" and "new landfill." Therefore, coordination of contractors and use of materials similar to those used for LC3 would be necessary, but on a larger scale. Materials and labor necessary to construct this alternative are readily available in sufficient quantity. Operation and maintenance of this alternative would be similar to that for LC3, but on a larger scale.

#### **4.4.3.7 Costs.**

Estimated costs are included in Table 3-2 and include present worth of the one-time capital and long term O&M costs. The detailed cost estimates for these alternatives are presented in Appendix D. Alternative LC1, the lowest cost alternative, would cost approximately \$69,000, the total of which is for long-term O&M. Alternative LC2 would cost approximately \$1.3 million, of which \$230,000 is for capital expenditures and the balance is for long-term O&M for pumping and labor. LC3 and LC4 would cost \$1.6 and \$1.5 million, respectively. Although the highest capital cost is associated with LC4 (\$440,000),

the less intensive O&M requirements for pumping and upkeep of LC4 (\$1,040,000) make it more attractive than LC3, from a cost perspective. Therefore, because LC4 provides the greatest benefit (a fully automated leachate collection system with minimal O&M required) for \$1.5 million, which is only marginally more expensive than the LC2 alternative, LC4 is the most cost-effective alternative.

#### **4.4.4 Leachate Treatment Alternatives Analysis**

The leachate treatment alternatives consist of: LT1 - No further action - continue to directly discharge leachate to a POTW; LT2 - Pretreatment of leachate, discharge to POTW; LT3 - Treatment of leachate, surface water discharge.

##### **4.4.4.1 Overall Protection of Human Health and Environment.**

Alternative LT1 is currently operational at the Site. The leachate is pumped directly from the collection manholes, stored in a tanker truck, and transported to a POTW for treatment under an industrial discharge permit for the Site. This alternative is protective of human health and the environment, provided the leachate is discharged to the POTW in accordance with the industrial discharge permit.

Alternative LT2 proposes to pre-treat leachate onsite (if necessary) prior to discharge to a POTW. The leachate would be pre-treated to remove and/or reduce the concentrations of various constituents as required by the POTW (potentially BOD and metals, for example). The POTW would receive the treated water and complete the removal and/or reduction of concentrations of the remaining contaminants. This alternative would be protective of human health and the environment.

Alternative LT3 proposes construction of an on-site leachate treatment facility that would utilize various treatment technologies required to treat leachate to meet surface water discharge standards as required by a NPDES discharge permit. In order to implement LT3, easements, and rights-of-way would have to be obtained in order to construct the required piping from the treatment facility to the selected discharge point. Special property access rights would also have to be obtained, making this alternative the least implementable of the three. LT3 would protect human health and the environment, provided the NPDES limits were not violated.

##### **4.4.4.2 Compliance with ARARs.**

The 811.309 ARARs listed in Table 2-3 are associated with all leachate treatment alternatives involving prevention of leachate release to groundwater or surface water. All three alternatives, if properly implemented, would comply with the general requirement to prevent discharge of leachate to groundwater or surface waters such that threats to human health and the environment are eliminated. In addition, alternatives LT1 and LT2 would have to comply with the applicable sewer discharge criteria, and POTW pretreatment standards, if implemented. Both these alternatives would comply with the sewer discharge criteria and POTW discharge standards, if properly implemented.

LT3 would be required to comply with the Clean Water Act, utilize best available technology to control pollutants, and properly operate the discharge system, including monitoring, maintenance, analyses, and establishing effluent standards. Alternative LT3 includes the complete treatment and discharge of leachate to surface waters. Again, such treatment would be implemented in compliance with applicable state and federal standards.

#### **4.4.4.3 Long-Term Effectiveness.**

If properly maintained, any of the leachate treatment alternatives would provide long-term effective leachate treatment.

#### **4.4.4.4 Reduction of Toxicity, Mobility, or Volume Through Treatment.**

Each of the leachate treatment alternatives reduce the toxicity of the leachate by reducing and/or removing the contaminants of concern. Metals would possibly remain as a treatment by-product (sludge or concentrate) to be disposed of appropriately. These metals would appear in the POTW sludge or in the on-site treatment system sludge. Toxicity would be reduced for the majority of the contaminants, and for metals, the mobility and volume of contaminants would be significantly reduced.

#### **4.4.4.5 Short-Term Effectiveness.**

LT1 would require no additional disturbance of the Site, although the loading and transport of leachate would present noise and dust. Alternatives LT2 and LT3 could result in increased noise and dust during construction. Measures could be taken to minimize these impacts; for example, watering for dust control, the installation and maintenance of noise control devices on machinery, wearing noise protection equipment and wearing of dust masks.

#### **4.4.4.6 Implementability.**

LT1 would be easily implemented, as the existing treatment is conducted at a POTW, following transport from the Site. The existing pumps could be used, and a tanker truck would be required to periodically transport the leachate, if a direct connection to the POTW is not permitted.

LT2 would require the construction of a pretreatment plant and ongoing monitoring to verify that required pretreatment standards are met. This pretreatment alternative would require an on-site treatment facility be constructed and treatment chemicals to be maintained on site. In addition, continued operation and maintenance of the pretreatment facility would be necessary.

LT3 would also require construction, management, operation, and maintenance of a leachate treatment plant. An NPDES permit would be required before the leachate treatment system could begin operation and discharge of treated leachate to a surface water body of adequate assimilative capacity. Operation and maintenance of this type of treatment plant would be intense and continual and would require ongoing monitoring.

#### **4.4.4.7 Costs.**

Costs are included in Table 3-3 and include present worth capital and O&M costs. The detailed cost estimates for these alternatives are presented in Appendix D. LT1 would cost the least, approximately \$829K, all of which are O&M expenditures. Alternative LT2 would be the most expensive, at \$9.7 million. Approximately \$480,000 would be required for the capital costs of the treatment system, and the majority of the LT2 costs (\$9.2 M) are associated with O&M for the on-site treatment system. LT3 would be the second most expensive cost at \$9.2 million, depending on a range of possible costs for the leachate treatment processes that could be required. Approximately up to 1.8 million would be required to build a treatment and discharge system for LT3 so that the treated leachate could be discharged using an NPDES permit. Given the excessive costs associated with construction and operation of an on-site treatment system and the relative ease of directly discharging to a POTW, alternative LT1, which is equally protective of the environment, and the most readily implementable of the three alternatives, is also the most cost effective.

#### **4.4.5 Groundwater Monitoring Alternatives Evaluation**

The groundwater monitoring alternatives consist of: GW1 - No Further Action - continue to monitor groundwater with existing system; GW2 - Monitored Natural Attenuation.

##### **4.4.5.1 Overall Protection of Human Health and the Environment**

The Baseline RA demonstrated that the only risk to human health and the environment greater than  $1 \times 10^{-4}$  potentially associated with the Site is that posed by the ingestion of vinyl chloride-contaminated water from the off-site deep sand and gravel aquifer. No one is ingesting vinyl chloride-contaminated water at this time. There are no private wells immediately downgradient of the Site. The Village of Antioch provides potable water via a network of municipal wells which are routinely sampled and analyzed to ensure compliance with the Safe Drinking Water Act. The only potential downgradient receptor well is municipal well VW3. However, a detailed evaluation of the potential fate and transport of the vinyl chloride (which included modeling) indicates that, given the limited distribution and relatively low concentrations of vinyl chloride, VW3 is not, and will not be, adversely impacted. Furthermore, the potential for future exposure to groundwater in the vicinity of the Site is highly unlikely, given the prohibition against private residential well development by Village of Antioch Ordinance (Antioch Water Works and Sewage Ordinance) Sections 50.008, 52.009, and 52.0011.

Groundwater monitoring alternative GW1 is a suitable long-term monitoring program that will provide adequate warning of a potential change in conditions that could impact VW3. Groundwater monitoring alternative GW2 provides an additional measure of protection by monitoring the effectiveness of the natural attenuation processes. In addition, a pre-design investigation, consisting of one or two additional monitoring wells, will be implemented as part of GW2. Both monitoring programs would be capable of recording changes in groundwater contaminant concentrations over time and would provide an early warning system to effectively reduce the risk of future exposure of residents to impacted groundwater. Both monitoring programs will also be effective in demonstrating the efficacy of source control measures implemented at the H.O.D. Landfill.

#### **4.4.5.2 Compliance with ARARs**

35 IAC 811.319(a) and Part 811.318 apply to the groundwater monitoring alternatives. Both alternatives GW1 and GW2 meet the minimum groundwater monitoring requirements and thus comply with applicable ARARs. After a baseline analytical database is established, it is anticipated that some reduction in analytes or monitoring points would be appropriate, and the Agencies would be petitioned for such a reduction in accordance with 35 IAC 811.319(I)(A)(5)(d).

As stated in section 3.9.2, 35 IAC 620.250, which requires establishment of a Groundwater Management Zone, does not apply because a coherent contaminant plume requiring corrective action does not exist. However, compliance with Illinois Groundwater Quality Standards 35 IAC 620.410 will be monitored, and the effectiveness of source control actions in achieving the groundwater quality standards will be documented.

#### **4.4.5.3 Long-term Effectiveness and Permanence**

Both monitoring programs will be effective in measuring the long-term effectiveness and permanence of the required source control actions. Changes in groundwater quality will be monitored over time and would provide early notice of any change in groundwater quality.

#### **4.4.5.4 Reduction of Toxicity, Mobility, or Volume through Treatment**

The groundwater monitoring alternatives do not involve treatment and therefore can not be evaluated against this criterion.

#### **4.4.5.5 Short-term Effectiveness**

There is no current risk attributable to exposure to groundwater.

#### **4.4.5.6 Implementability**

Both groundwater monitoring programs are readily implementable.

#### **4.4.5.7 Cost**

Estimated costs are included in Table 3-3 and include the one time capital cost, the long-term O&M cost and the total present worth. The detailed cost estimates for these alternatives are presented in Appendix D. Alternative GW1 will cost approximately \$1.8 million dollars, and alternative GW2 will cost approximately \$2.35 million dollars. These costs represent the total present worth costs of implementing these groundwater monitoring programs for 30 years. The costs which have already been incurred include approximately \$39,400 to abandon Public Well VW4 and approximately \$652,800 to install a replacement municipal well, VW7. These costs are included in the capital cost for the groundwater monitoring alternatives.

ACC/TST/dlp/ JAD/TLH/emp/JAD  
J:\1252\035\03090210\Final FS 6-98\draft final fs.doc  
1252035.03090210



**Table 1-1**  
**Summary of Analytical Results**  
**Detected VOCs, SVOCs and Pesticides/PCBs**  
**Remedial Investigation - Leachate Samples**  
**H.O.D. Landfill**  
**Antioch, Illinois**

Compounds	Groundwater Standards			Sample Designation							
	MCL	Class I	Class II	HD-LCLP01-01	HD-LCLP01-91	HD-LCLP06-01	HD-LCLP08-01	HD-LCLP11-01	HD-LCMHE-01	HD-LCFB01-01	HD-LCTB02-01
<b>Detected VOCs</b>											
<i>Detection Limit</i>				25	50	250	1,000	500	10	10	10
Vinyl Chloride	2	2	10						18		
Chloroethane				45	46						
Methylene Chloride	5	5	50	160	180	58			44	1	3
Acetone		700	700	110		2,200	19,000	1,500	140	13	5
1,1-Dichloroethene	7	7	35						5		
1,1-Dichloroethane		700	3,500						13		
1,2-Dichloroethene	70	70	200	7				190	70		
1,2-Dichloroethane	5	5	25						22		
2-Butanone				190		3,200	12,000	3,900	120		
1,2-Dichloropropane	5	5	25						28		
Trichloroethene	5	5	25						14		
Benzene	5	5	25	12	13				22		
4-Methyl-2-Pentanone				22	22	160	450		43		
2-Hexanone				14							
Tetrachloroethene	5	5	25	9					9		
Toluene	1,000	1,000	2,500	330	450	210	260	740	62		
Ethylbenzene	700	700	1,000	52	46			130			
Xylenes (total)	10,000	10,000	10,000	100	90	170		330	41		
<b>Detected SVOCs</b>											
<i>Detection Limit</i>				50	54	10	52	10	10	10	
Phenol		100	100	160	170	83	840	5J	19		
1,4-Dichlorobenzene						5		20			
2-Methylphenol		350	350			16					
4-Methylphenol				730	760	1,300	2,200	48	5J		
2,4-Dimethylphenol		140	140	12J	11J	4J	20J	3J	6J		
Naphthalene		25	39	34J	34J	6J	26J	16			
Diethylphthalate		5,600	5,600	32J	31J			4J			
Di-n-butylphthalate		700	3,500							1J	
bis(2-ethylhexyl)phthalate		6	60					42			
<b>Detected Pesticides/PCBs</b>											
<i>Detection Limit</i>				1	1	1	1	1	1.1	1.1	
Aroclor-1016		0.5	2.5	4.6	6.3						

**Notes:**

TICs not reported in Table; TICs results presented in Appendix O-7

Concentrations reported in micrograms per liter (ug/L)

J - Estimated value below detection limit

Samples collected on May 12-13, 1993



**Table 1-2**  
**Summary of Detected VOCs**  
**Remedial Investigation - Landfill Gas Samples**  
**H.O.D. Landfill**  
**Antioch, Illinois**

Compounds	Sample Designation													
	HD-LGLP01-01	DL	HD-LGLP06-01	DL	HD-LGLP07-01	DL	HD-LGLP08-01	DL	HD-LGLP11-01	DL	HD-LGLP11-91	DL	HD-LGTB01-01	DL
Freon 12		4	6,300	80	1,800	400	2,100	400	9,100	400	8,600	200		
Chloromethane		5		6,000		500	720	500		500		250		
Freon 114		4	7,200	80		400	760	400	860	400	940	200		
Vinyl Chloride		5	4,900	100	21,000	500	13,000	500	1,100	500	1,300	250		
Chloroethane	47	10	810	200		1,000		1,000		1,000		500		
Freon 11	78	2	12,000	200	270	200		200	310	200	330	100		
cis-1,2-DCE	6.3	4	370	80	5,400	400	1,400	400	2,400	400	2,700	200		
Carbon Disulfide		20	690	400		2,000		2,000		2,000		1,000		
Acetone		20	730	400	3,900	2,000	15,000	2,000		2,000	520	1,000		
Methylene Chloride	95	8	220	160		800		800		800		400		
1,1-Dichloroethane		5	140	100	540	500		500		500		250		
1,1-Dichloroethene		4		80	480	400		400		400		200		
2-Butanone	21	6	1,800	120	5,200	600	22,000	600		600	600	300		
Benzene	10	6	420	120	970	600	670	600	630	600	690	300		
Trichloroethene		5	160	100	2,500	500	590	500	960	500	1,000	250		
Toluene	540	6	11,000	120	66,000	600	53,000	600	20,000	600	21,000	300		
Tetrachloroethene		6	270	120	4,400	600	830	600	2,700	600	2,800	300		
Chlorobenzene		5	180	100		500	4,500	500		500		250		
Ethylbenzene	34	5	3,700	100	11,000	500	9,700	500	3,200	500	3,400	250		
Xylenes (total)	52	10	7,600	200	30,000	1,000	24,000	1,000	7,000	1,000	7,100	500		
4-Ethyl toluene		8	520	160	1,300	800	2,600	800		800	490	400		
1,3,5-Trimethylbenzene		5	200	100	510	500	910	500		500		250		
1,2,4-Trimethylbenzene		6	440	120	1,200	600	2,100	600		600	420	300		

Notes:

Samples collected on June 4, 1993

Concentrations reported in parts per billion

Only detected compounds reported

No compounds detected in Trip Blank

DL = detection limit

**Table 1-3**  
**Summary of Analytical Results**  
**Detected VOCs, SVOCs and Pesticides/PCBs**  
**Remedial Investigation - Round 1 and 2 Groundwater Samples**  
**H.O.D. Landfill**  
**Antioch, Illinois**

Round I Groundwater Sampling						Round II Groundwater Sampling					
Sample Designation	Compounds					Sample Designation	Compound				
	Acetone	Carbon Disulfide	Vinyl Chloride	1,2-DCE	TCE		Acetone	Carbon Disulfide	Vinyl Chloride	1,2-DCE	TCE
MCL			2	70	5	MCL			2	70	5
Class I Std.	700	700	2	70	5	Class I Std.	700	700	2	70	5
Class II Std.	700	3500	10	200	25	Class II Std.	700	3500	10	200	25
G11S-01		0.8J				G11S-02		18			
G11D-01						G11D-02					
US01S-01						US01S-02					
US01D-01						US01D-02					
US03S-01						US03S-02					
US03I-01						US03I-02					
US03D-01			28	11		US03D-02			35	18	
US04S-01				35		US04S-02				44	
US04D-01						US04D-02					
US06S-01						US06S-02					
US06I-01					2J	US06I-02				1J	
US06D-01						US06D-02					
W3D-01						W3D-02					
W3SB-01						W3SB-02					
W4S-01						W4S-02					
W5S-01			19			W5S-02					
W6S-01				2J		W6S-02					
W7D-01						W7D-02					

**Notes:**

Round I Groundwater Samples collected in May/June 1993

Round II Groundwater Samples collected in March 1994

Concentrations reported in micrograms per liter (ug/L)

J - estimated value below detection limit

SVOCs and Pesticides/PCBs were not detected in groundwater samples and are therefore not reported in the Table

**Table 1-4**  
**Summary of Analytical Results**  
**Detected VOCs, SVOCs and Pesticides/PCBs**  
**Remedial Investigation - Private/Village Well Groundwater Samples**  
**H.O.D. Landfill**  
**Antioch, Illinois**

Compounds	Groundwater Standards			Sample Designation (Round 1 Sampling)						
	MCL	Class I	Class II	DL	VW3-01	VW5-01	PW1-01	PW2-01	PW3-01	PW5-01
<b>Detected VOCs</b>										
Carbon Disulfide		700	3500	1		0.6J				
<b>Detected SVOCs</b>										
2-Methylphenol		350	350	5		0.5J		0.9J		
4-Chloroaniline				5	0.7J					

Compounds	Groundwater Standards			Sample Designation (Round 2 Sampling)			
	MCL	Class I	Class II	DL	VW3-02	VW4-02	VW5-02
<b>Detected VOCs</b>							
Acetone		700	700	5	11J		
cis-1,2-DCE		70	200	1		6J	
1,2-DCE		70	200	1	0.7J	0.5J	0.8J
<b>Detected SVOCs</b>							
2-Methylphenol		350	350				0.5J
4-Chloroaniline					0.7J		

**Notes:**

Concentrations reported in micrograms per liter (ug/L)

1,2-DCE - 1,2-Dichloroethene

J - Estimated value below detection limit

Round 1 Samples collected in June/July 1993

Round 2 Samples collected in March 1994 (Private wells not sampled during Round 2 activities)

Pesticides/PCBs were not detected in Private or Village Well Groundwater samples

DL = detection limit

**Table 1-5**  
**Summary of Analytical Results**  
**Detected VOCs, SVOCs and Pesticides/PCBs**  
**Remedial Investigation - Round 1 and 2 Surface Water Samples**  
**H.O.D. Landfill**  
**Antioch, Illinois**

Detected VOCs	Round 1 Surface Water Samples		
	SWS101-01	SWS201-01	SWS301-01
2-Hexanone			3J
4-methyl-2-pentanone			2J

Detected VOCs	Round 2 Surface Water Samples							
	SWS101-02	SWS201-02	SWS301-02	SWS401-02	SWS501-02	SWS601-02	SWPSG1-02	SWPSG2-02
2-Hexanone								
4-methyl-2-pentanone								

**Notes:**

Tentatively Identified Compounds (TICs) not reported in Table

Concentrations reported in micrograms per kilogram (ug/kg)

J - Estimated value below detection limit

SVOCs and Pesticides/PCBs were not detected in Round 1 or 2 surface water samples

VOCs were not detected in samples other than SWS301-01

Round 1 Samples collected in May 1993

Round 2 samples collected in March 1994

The detection limit for all samples was 10 ug/l.

**Table 1-6**  
**Summary of Analytical Results**  
**Detected VOCs, SVOCs and Pesticides/PCBs**  
**Remedial Investigation - Round 2 Sediment Samples**  
**H.O.D. Landfill**  
**Antioch, Illinois**

	Sample Designation (Round 2 Sediment Samples)							
Detected VOCs	SDS101-02	SDS201-02	SDS301-02	SDS401-02	SDS501-02	SDS601-02	SDPSG1-02	SDPSG2-02
Detection Limit	520	1500	850	1100	490	690	2500	2100
Phenanthrene			310J					
Fluoranthene		380J	680J					
Pyrene		370J	580J					
Benzo (a) anthracene			250J					
Chrysene			300J					
bis(2-ethylhexyl)-phthalate		940J	1500J					
Benzo (b) fluoranthene			430J					
Benzo (a) pyrene			290J					

**Notes:**

Tentatively Identified Compounds (TICs) not reported in Table

Concentrations reported in micrograms per kilogram (ug/kg)

J - Estimated value below detection limit

VOCs and Pesticides/PCBs were not detected in sediment samples

SVOCs were not detected in samples other than SDS201 and SDS301

Samples collected in March 1994

Sediment samples not collected during Round 1 field activities

**Table 1-7**  
**Summary of Analytical Results**  
**Detected VOCs, SVOCs and Pesticides/PCBs**  
**Remedial Investigation - Round 1 Surface Soils Samples**  
**H.O.D. Landfill**  
**Antioch, Illinois**

Compounds	Sample Designation					
	HD-SU01-01	HD-SU02-01	HD-SU03-01	HD-SU04-01	HD-SU04-91	HD-SU05-01
<b>Detected VOCs</b>						
<i>Detection Limit</i>	62	14	13	64	13	12
Methylene Chloride	570	59	48	1200	210	
Acetone	140	17	8J		15	
Carbon Disulfide		6J				
Benzene	7J					
Toluene	55J	3J		2J		
Ethylbenzene	240	12J				
Xylenes	280	37				
<b>Detected SVOCs</b>						
<i>Detection Limit</i>	410	420	430	420	430	410
1,4-Dichlorobenzene	130J					
Naphthalene	320J	630				
2-Methylnaphthalene	61J	390J				
Acenaphthene	120J	1,000				
Dibenzofuran	59J	620				
Fluorene	68J	500				
Phenanthrene	250J	240J	120J	36J		51J
Anthracene	46J					
Fluoranthene			160J	59J		73J
Pyrene			110J	52J		54J
bis(2-ethylhexyl)-phthalate	160J	320J	280J	3,500	3,600	9,600
Benzo (b) fluoranthene			110J			
Carbazole	130J					
<b>Detected Pesticides/PCBs</b>						
<i>Detection Limit</i>	4.1	4.5	4.3	4.2	4.3	4.1
4,4'-DDE	4.3					

**Notes:**

Tentatively Identified Compounds (TICs) not reported in Table; TICs results presented in Appendix O-12

Concentrations reported in micrograms per kilogram (ug/kg)

J - Estimated value below detection limit

Surface Soils samples not collected during Round 2 RI sampling activities

Samples collected on May 14, 1993

**TABLE 1-8**  
**SUMMARY OF HISTORICAL MONITORING WELL VOC DATA**  
**H.O.D. Landfill RI/FS**

SAMPLE ID	Date	Trichloroethene	1,2-Dichloroethene (cis/trans)	Vinyl chloride	4-Methyl-2-pentanone	Acetone	Methylene chloride	Benzene	Toluene
US01D	8/11/87					7J			
US01D	4/19/88					2BJ	0.9BJ		
US01D	5/19/88						10		
US01S	8/11/87					6J			
US01S	4/19/88					1BJ	1BJ		
US01S	5/19/88					28JB			
US03D	5/8/90			12.3					
US03S	8/11/87								
US03S	4/19/88					3BJ	2BJ		
US04D	8/10/87					5BJ	5BJ		
US04D	8/10/87						3J		
US04S	8/10/87		71			21.5			
	4/18/88		69			3			
	5/9/90		41.1						
	7/26/90		41.5						
US06S	8/11/87					7J			
	4/18/88					5BJ	3BJ		
US06D	8/11/87					7			
	4/19/88					4BJ	2BJ		
	5/19/88	0.47					4.2		
	5/9/90	0.5							
	7/26/90	0.7							
US06I	8/12/87	7							
	4/18/88	5				5BJ	2BJ		2J
	5/19/88	5.3	1.2J				1.1J		
	8/18/88	5				5	2		2
US07S	8/11/87					5J		8	
	4/18/88						4BJ	2BJ	
G102	4/18/88					5BJ	2BJ		2J
	5/10/90			2.4					

**Notes:**

1. This table presents historical data for H.O.D Landfill samples collected from monitoring wells. Only wells and sampling rounds with VOC detects are presented in this table. Acetone and methylene chloride are often lab contaminants. Montgomery Watson did not perform data validation for the sampling rounds and has not assessed data quality.

2. All results are in units of ug/L.

3. The table shows a summary of historical detects and, as such, detection limits vary, and are not reported here.

J - Indicates and estimated value

B - Compound detected in the associated blank as well as the sample.

**TABLE 1-9**  
**Summary of Risk Assessment Results**  
**H.O.D. Landfill FS**

<b>Exposure Pathway</b>	<b>RME Excess Lifetime Cancer Risk</b>	<b>Contaminants of Concern (a)</b>
<b>Child/Teenage Site Trespasser</b>		
Incidental Surface Soil Ingestion	9.E-08	NA
Dermal Absorption from Surface Soil	1.E-05	Beryllium
Dermal Contact with Surface Water	NE	NA
Incidental Sediment Ingestion	2.E-07	NA
Dermal Absorption from Sediment	1.E-07	NA
Inhalation of Volatiles from Ambient Air	4.E-09	NA
Direct Contact with Carcinogenic PAHs		
Surface Soil	Cancer risk not likely	NA
Sediment	Cancer risk not likely	NA
<b>Total Risk</b>	1.E-05	Beryllium
<b>Nearby Adult Resident</b>		
<b>Ingestion of Groundwater</b>		
Off-Site Surficial Sand	5.E-05	Beryllium
Off-Site Deep Sand and Gravel	8.E-04	Vinyl Chloride
Municipal Wells	9.E-05	Arsenic
Private Wells	NE	NA
<b>Inhalation of Volatiles while Showering</b>		
Off-Site Deep Sand and Gravel	6.E-05	Vinyl Chloride
Municipal Wells	5.E-07	NA
<b>Dermal Absorption While Showering</b>		
Off-Site Surficial Sand	2.E-05	Beryllium
Off-Site Deep Sand and Gravel	3.E-05	Vinyl Chloride
Municipal Wells	2.E-07	NA
Private Wells	NE	NA
<b>Inhalation of Volatiles from Ambient Air</b>	5.E-07	NA
<b>Total Risk by Aquifer/Well Type</b>		
Off-Site Surficial Sand	7.E-05	Beryllium
Off-Site Deep Sand and Gravel	9.E-04	Vinyl Chloride
Municipal Wells	9.E-05	Arsenic
Private Wells	5.E-07	NA

Information taken from "Baseline Risk Assessment for the H.O.D. Landfill Site Antioch, Illinois,"  
The Weinberg Group, Inc./ICF Kaiser, 1997.

**Notes:**

NA = Not applicable

NE = Not evaluated since chemicals relevant for this health endpoint were not selected  
or detected in this data grouping.

(a) Contaminants of Concern are those with RME cancer risks greater than 1.E-06.



**TABLE 2-1: POTENTIAL CHEMICAL-SPECIFIC ARARS  
H.O.D. LANDFILL SUPERFUND SITE - ANTIOCH, ILLINOIS**

<b>MEDIA</b>	<b>REQUIREMENT</b>	<b>CITATION</b>
<b>Surface Water</b>	Protect State water for aquatic life, agricultural use, primary and secondary contact use, most industrial use, and to ensure aesthetic quality of aquatic environment.	Water Quality Standards 35 IAC 302.202-302.212
	Pretreatment Standards of State and local POTW	35 IAC 310.201-220, 35 IAC 307.1101-1103
	Effluent Guidelines and Standards	35 IAC 304.102-126
	Prohibition of discharge of oil or hazardous substances into or upon navigable waters	Federal Water Pollution Control Act Section 311(b)(3) 40 CFR 110.6, 117.21
	Comply with all applicable Federal and State water quality criteria.	CWA Section 304(a) and information published in the Federal Register pursuant to this section; 35 IAC 302.612-669
<b>Groundwater</b>	Meet State Groundwater Quality Standards using a Groundwater Management Zone, if appropriate	35 IAC 620.410 unless modified in accordance with the substantive requirements in 35 IAC 620.250 to 350
<b>Air</b>	Air Quality Standards	35 IAC 243.120-126

**TABLE 2-2: POTENTIAL LOCATION-SPECIFIC ARARS  
H.O.D. LANDFILL SUPERFUND SITE - ANTIOCH, ILLINOIS**

MEDIA	REQUIREMENT	CITATION
<b>Floodplains</b>	Action to avoid adverse effects, minimize potential harm, and restore and preserve natural and beneficial values (in relation to implementation of the RA).	Executive Order 11988, Floodplain Management, 40 CFR 6, Appendix A, Section 6(a)(5)
	Facility located in a 100-year floodplain must be designed, constructed, operated, and maintained to prevent washout of any hazardous waste by a 100-year flood	35 IAC 724.118(b)
	Governs construction and filling in the regulatory floodway of rivers, lakes, and streams of Cook, DuPage, Kane, Lake, McHenry, and Will Counties, excluding the City of Chicago	92 IAC Part 708
	Minimum requirements for stormwater management aspects of new development in Lake County	Lake County Stormwater Management Commission Watershed Development Ordinance
<b>Wetlands</b>	Action to minimize the destruction, loss, or degradation of wetlands	Executive Order 11990, Protection of Wetlands, 40 CFR 6, Appendix A, Section 6(a)(5)
	Action to minimize adverse effects of dredged or fill materials	CWA, 40 CFR 230.70-230.77
	Permits for Dredged or Fill Material	CWA Section 404

**TABLE 2-2: POTENTIAL LOCATION-SPECIFIC ARARS  
H.O.D. LANDFILL SUPERFUND SITE - ANTIOCH, ILLINOIS**

MEDIA	REQUIREMENT	CITATION
Stream	Requires Federal agencies involved in actions that will result in the control or structural modification of any stream or body of water for any purpose, to take action to protect the fish and wildlife resources which may be affected by the action	Fish and Wildlife Coordination Act, 40 CFR 6.302(g)
	Action to minimize adverse effects of dredged or fill materials	CWA, 40 CFR 230.70-230.77
	Permits for Dredged or Fill Material	CWA Section 404

**TABLE 2-3: POTENTIAL ACTION-SPECIFIC ARARS  
H.O.D. LANDFILL SUPERFUND SITE - ANTIOCH, ILLINOIS**

<b>MEDIA</b>	<b>REQUIREMENT</b>	<b>CITATION</b>
<b>Capping</b>	Final cover system: A compacted layer of not less than two feet of suitable material shall be placed over the entire surface of each portion of the final lift not later than 60 days following the placement of refuse in the final lift.	35 IAC 807.305(c)
	Cover stabilization: Residual settlement erosion control work; residual settlement and erosion control work; mowing	35 IAC 807.622(d)(3)
<b>Post Closure Care</b>	Post Closure Maintenance: Establishes minimum requirements for the maintenance and inspection of the final cover and vegetation	35 IAC 811.111(c)
	Groundwater Monitoring Program: Establishes minimum requirements for groundwater monitoring at the site	35 IAC 811.319(a) and Part 811.318
	Leachate Collection System: Establishes minimum requirements for a leachate collection system at the site	35 IAC 811.308(a)(c)(d)(e)(f)(g)(h)
	Landfill Gas Monitoring Program: Establishes minimum requirements for gas monitoring at the site	35 IAC 811.310
<b>Leachate Treatment Storage and Disposal</b>	Leachate Treatment and Disposal System: Establishes standards for on-site treatment and pre-treatment	35 IAC 811.309(c)(3)(4)(5)(6) Note that this is only applicable for scenario LT2 and LT3.
	Leachate Treatment and Disposal System: Establishes standards for leachate storage systems	35 IAC 811.309(d)
	Leachate Treatment and Disposal System: Establishes standards for discharge to an off-site treatment works	35 IAC 811.309(e)(1)(3)(4)(5)(6)

**TABLE 2-3: POTENTIAL ACTION-SPECIFIC ARARS  
H.O.D. LANDFILL SUPERFUND SITE - ANTIOCH, ILLINOIS**

<b>MEDIA</b>	<b>REQUIREMENT</b>	<b>CITATION</b>
<b>Leachate Treatment Storage and Disposal (continued)</b>	Leachate Treatment and Disposal System: Establishes standards for leachate monitoring	35 IAC 811.309(g)(1)(2)
<b>Landfill Gas Management</b>	Landfill Gas Management System: Establishes minimum requirements for gas venting and collection systems	35 IAC 811.311
	Visible and particulate matter emission standards and limitations	35 IAC 212.123 (visible) and 212.321 (particulate)
	Sulfur air emissions standards and limitations	35 IAC 214.162
	Organic material emissions standards and limitations	35 IAC 215.143
	Carbon monoxide emissions standards and limitations	35 IAC 216.121, 216.141
	Nitrogen oxide emissions standards	35 IAC 217.121
	Volatile Organic Material emission standards	35 IAC 218.143
	Verify that there is no "excessive release" of hydrogen sulfide emissions during landfill gas management. Verify that emissions of hazardous pollutants do not exceed levels expected from sources in compliance with hazardous air pollution regulations.	35 IAC 211.2090, 35 IAC 214.101 415 ILCS 5/9.1(b), CAA Section 112, 40 CFR 61.12-14
<b>Gas Collection</b>	Estimate emission rates for each pollutant expected.	35 IAC 291.202
	Develop a modeled impact analysis of source emissions.	35 IAC 291.206
	Use Reasonably Available Control Technology (RACT).	35 IAC 211.5370, 35 IAC Part 215, Appendix E

**TABLE 2-3: POTENTIAL ACTION-SPECIFIC ARARS  
H.O.D. LANDFILL SUPERFUND SITE - ANTIOCH, ILLINOIS**

<b>MEDIA</b>	<b>REQUIREMENT</b>	<b>CITATION</b>
<b>Landfill Gas Processing and Disposal</b>	Landfill Gas Processing and Disposal System: Establishes minimum requirements for landfill gas processing and disposal	35 IAC 811.312(a)(b)(c)(d)(e)
	Estimate emission rates for each pollutant expected.	35 IAC 291.202
	Develop a modeled impact analysis of source emissions.	35 IAC 291.206
	Use Reasonably Available Control Technology (RACT).	35 IAC 211.5370, 35 IAC Part 215, Appendix E
<b>Direct Discharge of Treatment System Effluent</b>	The discharge must be consistent with the relevant Water Quality Management Plan approved by EPA under Section 208(b) of the CWA, and developed by Illinois EPA.	CWA Section 208(b)
	Use of Best Available Technology (BAT) that is economically achievable is required to control toxic and nonconventional pollutants. Use of best conventional pollutant control technology (BCT) is required to control conventional pollutants. Technology-based limitations may be determined on a case-by-case basis.	CWA Section 306, 40 CFR 122.44(a), and 35 IAC 301.400
	Discharge limitations must be established for all toxic pollutants that are or may be discharged at levels greater than those that can be achieved by technology-based standards.	CWA Section 307(a), 40 CFR 122.44(e), and 35 IAC 309.152

**TABLE 2-3: POTENTIAL ACTION-SPECIFIC ARARS  
H.O.D. LANDFILL SUPERFUND SITE - ANTIOCH, ILLINOIS**

MEDIA	REQUIREMENT	CITATION
<b>Direct Discharge of Treatment System Effluent</b> (continued)	<p>The discharge must be monitored to assure compliance. The discharger will monitor:</p> <ul style="list-style-type: none"> <li>- The mass of each pollutant discharged,</li> <li>- The volume of effluent discharged, and</li> <li>- The frequency of discharge and other measurements as appropriate.</li> </ul>	40 CFR 122.44(I) and 35 IAC 309.146(a)
	Approved test methods for waste constituents to be monitored must be followed. Detailed requirements for analytical procedures and quality controls are provided.	CWA, 40 CFR 122.21
	Duty to mitigate any adverse effects of any discharge.	40 CFR 122.41(d)
	Proper operation and maintenance of treatment and control systems.	40 CFR 122.41(e)
	<p>Develop and implement a Best Management Practices (BMP) program to prevent the release of toxic constituents to surface waters.</p> <p>The BMP program must:</p> <ul style="list-style-type: none"> <li>- Establish specific procedures for the control of toxic and hazardous pollution spills,</li> <li>- Include a prediction of direction, rate of flow, and total quantity of toxic pollutants where experience indicates a reasonable potential for equipment failure, and</li> </ul>	CWA Section 304(e), 40 CFR 125.104

**TABLE 2-3: POTENTIAL ACTION-SPECIFIC ARARS  
H.O.D. LANDFILL SUPERFUND SITE - ANTIOCH, ILLINOIS**

<b>MEDIA</b>	<b>REQUIREMENT</b>	<b>CITATION</b>
<b>Direct Discharge of Treatment System Effluent (continued)</b>	- Assure proper management of solid and hazardous waste in accordance with regulations promulgated under RCRA.	
	Sample preservation procedures, container materials, and maximum allowable holding times are prescribed.	40 CFR 136.3
<b>Discharge to Surface Water</b>	Effluent standards which establish maximum contaminant concentrations that may be discharged to the waters of the State.	35 IAC 304.101-304.126
<b>Discharge to Sewers</b>	Sewer discharge criteria	35 IAC 307.1101-1103
<b>Discharge to POTW</b>	Prevent introduction of pollutants into POTW which will interfere with POTW operation.	35 IAC 310.201(a)(c) and 310.202, and local POTW regulations

JMS/jms/dlp/TLH/AHS  
J:\1252\035\03090210\US EPA Comments\arars\_response.doc  
1252035.03090210



**Table 3.1**  
**Summary of Remedial Action Alternatives**

Action Components	Description
<b>No Further Action</b>	
NFA	Under existing IEPA permit, cap maintenance, operation and maintenance of the existing LFG and manual leachate collection systems, and groundwater monitoring activities would be performed.
<b>Capping</b>	
C1	Restoration of Cap: The cap would be restored to the original grades established and approved by the IEPA in the Site Closure Plan. The existing soils would be regraded and/or off-site clay soils would be imported and compacted to fill low areas and repair leachate seeps.
C2	Augmentation of Cap: The existing cover soils would be reworked to form a uniform 35 IAC 807 compliant cap consisting of two feet of compacted clay and 2 feet of additional cover soil.
C3	Reconfiguration/Supplementation of Cap: Existing cover soils would be reworked and supplemented (if necessary) to form a 35 IAC 811 compliant cap with 3 feet of compacted clay and 3 feet of cover soil.
<b>LFG Collection and Treatment</b>	
G1	No Further Action: Continue to passively vent LFG with existing wells and stick flares.
G2	Supplement Existing System: Existing passive flares in new landfill would continue operation. LFG collection/treatment supplemented through addition of an active extraction system in old landfill. Pilot/Predesign investigation would be conducted.
G3	Activation of LFG System: Existing wells (passive) converted to active wells, additional wells installed in old portion of Site, and LFG conveyed to centralized blower/flare station. Pilot/Predesign investigation would be conducted.
<b>Leachate Collection</b>	
LC1	No Further Action: Continue to utilize existing leachate collection points (manual operation).
LC2	Toe-of-Slope Leachate Collection: Toe-of-slope collection piping extended along toe of both old and new section of landfill and existing extraction points used. Automated system.
LC3	Upgrade/Supplement Leachate System: Toe-of-slope piping extended in new section of landfill only. Dual extraction system (leachate/LFG) with blower/flare station constructed on old section of landfill. Pilot/Predesign investigation would be conducted.
LC4	Active Leachate Extraction: Existing gas and leachate wells in both sections converted to dual extraction wells. Blower/Flare station would be constructed. Pilot/Predesign investigation would be conducted.
<b>Leachate Treatment/Disposal</b>	
LT1	No Further Action: Continue to directly discharge to licensed POTW.
LT2	Pretreat/Discharge Leachate: Physical/chemical pretreatment of leachate followed by discharge to licensed POTW.
LT3	Pretreat/Surface Discharge Leachate: Full treatment of leachate to NPDES standards followed by remote surface discharge to surface water source (Fox River).
<b>Groundwater Monitoring</b>	
GW1	No Further Action: Continue Groundwater Monitoring Program.
GW2	Monitored Natural Attenuation.

**TABLE 3.2: POTW DISCHARGE REQUIREMENTS(1)**  
**H.O.D. LANDFILL**  
**ANTIOCH, ILLINOIS**

<b>Composite Sample Discharge Limits(2)</b>	
<b>Constituent</b>	<b>Maximum Concentration of User Discharge Permitted (mg/L)</b>
Cadmium	0.4
Chromium	5.0
Copper	3.6
Cyanide	1.0
Lead	1.0
Mercury	0.003
Nickel	3.0
Zinc	5.0
Chemical Oxygen Demand	6,500.0
Ammonia	600.0
Iron	250.0
Manganese	10.0
Fats, Oils, and Grease	250.0
<b>Grab Sample Discharge Limits(3)</b>	
<b>Constituent</b>	<b>Maximum Concentration of User Discharge Permitted (mg/L)</b>
Cadmium	0.8
Chromium	10.0
Copper	7.2
Cyanide	1.0
Lead	2.0
Mercury	0.006
Nickel	6.0
Zinc	10.0
Chemical Oxygen Demand	6,500.0
Ammonia	600.0
Iron	250.0
Manganese	10.0
Fats, Oils, and Grease	250.0

- Notes:
1. Requirements apply to WMII Fox River Water Reclamation District Wastewater Discharge Permit, Sanitary District of Elgin, Permit Nos. WDP1992257S and WPD1992257G
  2. Composite samples must be collected over a period of 18 hours or longer
  3. Grab samples can be collected over any duration

jms/emp/TAB

\\chi1\_server\jobs\1252035\03090210\Final FS 4-98\POTW Requirements.doc  
1252035.03090210

**TABLE 3-3**  
**Cost Estimate Summary**

	Capital	Annual O&M	P.W. O&M	Total P.W.
<b>No Further Action</b>				
NFA	\$0	\$154,860	\$1,921,670	\$1,921,670
<b>Capping</b>				
C1	\$1,370,000	\$72,000	\$900,000	\$2,270,000
C2	\$4,861,000	\$72,000	\$900,000	\$5,761,000
C3 (Supplemental Clay)	\$6,603,500	\$72,000	\$900,000	\$7,503,500
C3 (Replacement Clay)	\$8,783,500	\$72,000	\$900,000	\$9,683,500
<b>Gas Extraction / Treatment</b>				
G1 - No Further Action	\$231,000	\$35,000	\$434,400	\$665,400
G2	\$701,100	\$35,000	\$434,400	\$1,135,500
G3	\$924,000	\$35,000	\$434,400	\$1,358,400
<b>Leachate Extraction</b>				
LC1 - No Further Action	\$0	\$4,000	\$49,700	\$49,700
LC2	\$232,300	\$60,000	\$744,600	\$976,900
LC3	\$367,800	\$72,000	\$893,500	\$1,261,300
LC4	\$439,000	\$60,000	\$744,600	\$1,183,600
<b>Leachate Treatment</b>				
LT1 - No Further Action	\$0	\$66,800	\$1,156,000	\$1,156,000
LT2	\$476,000	\$747,000	\$9,270,000	\$9,750,000
LT3	\$1,843,000	\$595,000	\$7,384,000	\$9,227,000
<b>Groundwater Monitoring</b>				
GW1 - No Further Action*	\$693,900	\$63,000	\$781,800	\$1,475,700
GW2*	\$725,300	\$69,700	\$865,000	\$1,590,300

*Note: Present Worth calculated at i = 7%, n = 30 years, Factor = 12.41.*

*\*Capital cost for groundwater monitoring includes \$652,800 for VW4 Replacement/VW7 Installation, and an estimated \$39,400 to abandon VW4.*

**Table 3-4**  
**Leachate Treatment Processes**  
**H.O.D. Landfill**  
**Antioch, Illinois**

<u>Compounds to Treat</u>	<u>Treatment Processes (variations)</u>
VOCs	Air stripping <ul style="list-style-type: none"> <li>- tray</li> <li>- tower</li> </ul> Oxidation <ul style="list-style-type: none"> <li>- ozone</li> <li>- peroxide</li> <li>- UV</li> </ul> Granular activated carbon           Ultrafiltration           Reverse osmosis           Electrodialysis           Aerobic biological treatment           Anaerobic biological treatment           Fixed film biological treatment           Suspended growth biological treatment
SVOCs	Same as above, less air stripping
Ammonia	Air stripping           Biological treatment (requires aerobic and anoxic in series, e.g., SBR)           Reverse osmosis
Metals	Chemical precipitation <ul style="list-style-type: none"> <li>- lime</li> <li>- caustic</li> <li>- sulfide</li> </ul> Ion exchange <ul style="list-style-type: none"> <li>- cationic</li> <li>- anionic</li> </ul> Oxidation and filtration/clarification           Ultrafiltration           Reverse osmosis           Electrodialysis

**TABLE 4-1**  
**Summary of Vinyl Chloride Detected In**  
**Village Well No. 4**  
**H.O.D. Landfill FS**

<b>Date</b>	<b>Concentration of Vinyl chloride</b>
1-Feb-84	ND-6.7
22-Feb-84	--
16-Apr-84	--
9-Mar-89	3.6
23-Mar-89	0.4-1.8
24-Mar-89	0.8
22-Aug-89	ND
23-Aug-89	0.2
24-Aug-89	ND-0.2
28-Aug-89	ND-0.2
13-Sep-89	ND-0.2
14-Sep-89	ND
27-Sep-89	ND
26-Oct-89	ND
9-Nov-89	ND
13-Dec-89	ND
16-May-90	ND
7-Jan-92	ND
7-Apr-92	ND
4-Jun-92	ND
6-Jul-92	ND
3-Aug-92	ND
4-Aug-92	ND
16-Sep-92	ND
21-Oct-92	ND
3-Nov-92	ND
11-Jan-93	ND
8-Feb-93	ND
1-Mar-93	ND
6-Apr-93	ND
4-May-93	ND
31-Mar-94	ND


**Notes:**

1. This table presents all reported detects of volatile organic compounds in water samples collected from Village Well No. 4 finished water collected following treatment (i.e., chlorination and treatment with polyphosphates).
2. Sampling was conducted by the Village of Antioch.
3. Results are in ug/L.
4. - = Not analyzed
5. ND = not detected
6. Detection limits for vinyl chloride were variable, refer to the Baseline RA



—

—



This document has been developed for a specific application and may not be used without the written approval of Montgomery Watson.

QUALITY CONTROL	Graphic Standards CCM	4-B-97	Technical Review Project Manager	Management Review Other
-----------------	-----------------------	--------	----------------------------------	-------------------------

#### NOTE

BASE MAP DEVELOPED FROM THE ANTIOCH, ILLINOIS 7.5 MINUTE U.S.G.S. TOPOGRAPHIC QUADRANGLE MAP, DATED 1960, PHOTOREVISED 1972.






FIGURE 1

Developed By	SJC	Drawn By	CCM	<b>SITE LOCATION MAP</b>  FEASIBILITY STUDY H.O.D. LANDFILL WASTE MANAGEMENT OF ILLINOIS, INC. ANTIOCH, ILLINOIS	Drawing Number 1252035 03090210 <b>A1</b>
Approved By		Date			<b>MONTGOMERY WATSON</b> 
Reference					
Revisions					



# **LEGEND**

- APPROXIMATE PROPERTY LINE
- APPROXIMATE LIMITS OF LANDFILLED AREA
- 780- TOPOGRAPHIC CONTOUR LINE
- TREES, BRUSH
- ACCESS ROAD
- BUILDING
- SPOT ELEVATION
- FENCE LINE
- APPROXIMATE LIMIT OF SEQUOIT CREEK MARCH PRIOR TO CHANNELIZATION
- APPROXIMATE LOCATION OF AREA OPERATED USING "TRENCH FILL" METHOD
- APPROXIMATE LOCATION OF AREA OPERATED USING "AREA FILL" METHOD
- APPROXIMATE LOCATION OF PORTION OPERATED AS "DEEP TRENCH" AREA

## **NOTES**

1. BASE MAP DEVELOPED FROM AN AERO-METRIC ENGINEERING INC. SURVEY, DATED JULY 21, 1993.
2. TOPOGRAPHY IS BASED IN U.S.G.S. DATUM.
3. GRID BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM.



0 300 600  
SCALE IN FEET

FIGURE 2


**SITE FEATURES MAP**  
FEASIBILITY STUDY  
H.O.D. LANDFILL  
WASTE MANAGEMENT OF ILLINOIS, INC.  
ANTIOCH, ILLINOIS


Drawing Number  
1252035  
03090210 B1

**MONTGOMERY WATSON**

Developed By SJC  
Approved By  
Reference  
Revisions  
Drawn By CCM  
Date







# LEGEND

- APPROXIMATE PROPERTY LINE
- APPROXIMATE LIMITS OF LANDFILLED AREA
- TOPOGRAPHIC CONTOUR LINE
- TREES, BRUSH
- BUILDING
- FENCE LINE
- ◆ LP8 WARZYN LEACHATE PIEZOMETER LOCATION AND NUMBER
- GP6A WARZYN GAS PROBE LOCATION AND NUMBER
- MHW/ MHE LEACHATE COLLECTION MANHOLE WEST/ LEACHATE COLLECTION MANHOLE EAST
- ◆ P2A LEACHATE EXTRACTION WELL LOCATION AND NUMBER

# NOTES

1. BASE MAP DEVELOPED FROM AN AERO-METRIC ENGINEERING INC. SURVEY, DATED JULY 21, 1993.
2. LOCATION OF PELA STAFF GAGES PSG1 AND PSG2 ARE APPROXIMATE.
3. INVESTIGATION POINTS HAVE BEEN LOCATED BASED ON GENTILE AND ASSOCIATES, INC. SURVEY PERFORMED ON DURING JUNE AND JULY 1993.



FIGURE 4




FIGURE 5

Developed By	SJC	Drawn By	CCM
Approved By		Date	
Reference			
Revisions			


**SURFACE WATER/SEDIMENT AND SURFACE SOIL SAMPLING LOCATION MAP (ROUND I AND II)**

FEASIBILITY STUDY  
H.O.D. LANDFILL  
WASTE MANAGEMENT OF ILLINOIS, INC.  
ANTIOCH, ILLINOIS

Drawing Number  
1252035  
03090210 **B4**

**MONTGOMERY WATSON**

QUALITY CONTROL	Graphic Standards CCM	4-B-97	Technical Review	Management Review
	Lead Professional		Project Manager	Other




**LEGEND**

**VW1** VILLAGE WATER SUPPLY WELL LOCATION AND NUMBER

**NOTE**


BASE MAP DEVELOPED FROM THE ANTIOCH, ILLINOIS 7.5 MINUTE U.S.G.S. TOPOGRAPHIC QUADRANGLE MAP, DATED 1960, PHOTOREVISED 1972.



**FIGURE 6**

Developed By	SJC	Drawn By	CCM	<b>VILLAGE WATER SUPPLY WELL LOCATION MAP</b>  FEASIBILITY STUDY H.O.D. LANDFILL WASTE MANAGEMENT OF ILLINOIS, INC. ANTIOCH, ILLINOIS	Drawing Number 1252035 03090210 <b>A2</b>  <b>MONTGOMERY WATSON</b> 
Approved By		Date			
Reference					
Revisions					

This document has been developed for a specific application and may not be used without the written approval of Montgomery Watson.




**LEGEND**

- ▲PW1 PRIVATE WELL SAMPLING LOCATION AND NUMBER
- ▲RW6 RESIDENTIAL WELL SAMPLED DURING AUGUST 1987 PHASE OF USEPA ESI.

**NOTE**


1. BASE MAP DEVELOPED FROM THE ANTIOCH, ILLINOIS-WISCONSIN 7.5 MINUTE U.S.G.S. TOPOGRAPHIC QUADRANGLE MAP, DATED 1960, PHOTOREVISED 1972.
2. PW1 THROUGH PW5 CORRESPOND TO RW1 THROUGH RW5 LOCATIONS SAMPLED DURING THE AUGUST 1987 PHASE OF USEPA ESI.



**FIGURE 7**

Developed By SJC	Drawn By CCM	<b>PRIVATE WATER SUPPLY WELL SAMPLING LOCATIONS</b>  FEASIBILITY STUDY H.O.D. LANDFILL WASTE MANAGEMENT OF ILLINOIS, INC. ANTIOCH, ILLINOIS	Drawing Number 1252035 03090210 <b>A3</b>  <b>MONTGOMERY WATSON</b> 
Approved By	Date		
Reference			
Revisions			

This document has been developed for a specific application and may not be used without the written approval of Montgomery Watson.



# **LEGEND**

- APPROXIMATE PROPERTY LINE
- APPROXIMATE LIMITS OF LANDFILLED AREA
- 780 TOPOGRAPHIC CONTOUR LINE
- TREES, BRUSH
- ACCESS ROAD
- BUILDING
- FENCE LINE
- DOCUMENTED AREAS
- CROSS SECTION LOCATION

# **NOTES**

1. BASE MAP DEVELOPED FROM AN AERO-METRIC ENGINEERING INC. SURVEY, DATED JULY 21, 1993.
2. LANDFILL COVER SURVEY DOCUMENTED BY WARZYN INC. ON MARCH 23 AND 24, 1994.




FIGURE 8

EXISTING CONDITIONS - LANDFILL COVER

FEASIBILITY STUDY  
H.O.D. LANDFILL  
WASTE MANAGEMENT OF ILLINOIS, INC.  
ANTIOCH, ILLINOIS



Drawing Number  
1252035  
03090210 B5

**MONTGOMERY  
WATSON**




Developed By LAB  
Approved By  
Reference 2386 0096-B4  
Revisions

Drawn By LCL  
Date



1 CAP ALTERNATIVE C2-REWORK EXISTING  
2 NOT TO SCALE



2 CAP ALTERNATIVE C3-SUPPLEMENTING CLAY  
2 NOT TO SCALE

**NOTE**

REFER TO DRAWING B1 FOR CROSS SECTION LOCATION.

**CROSS SECTION SCALE**



SCALE IN FEET

VERTICAL EXAGGERATION: TWENTY TIMES

Drawn By DLF  
Date  
Developed By LAB  
Approved By  
Reference  
Revisions

CROSS SECTION A-A' and CONCEPTUAL DETAILS OF CAP ALTERNATIVES C2 & C3


FEASIBILITY STUDY  
H.O.D. LANDFILL  
WASTE MANAGEMENT OF ILLINOIS, INC.  
ANTIOCH, ILLINOIS

Drawing Number  
1252035  
031801


B2

MONTGOMERY  
WATSON

FIGURE 9







#### LEGEND (EXISTING)

- APPROXIMATE PROPERTY LINE
- APPROXIMATE LIMITS OF LANDFILLED AREA
- 780 TOPOGRAPHIC CONTOUR LINE
- TREES, BRUSH
- BUILDING
- FENCE LINE

- ▼ GWF1 GAS FLARE LOCATION AND NUMBER
- LP1 LEACHATE PIEZOMETER LOCATION AND NUMBER

#### LEGEND (PROPOSED)

- GE1 GAS EXTRACTION WELL LOCATION AND NUMBER

#### NOTES

1. BASE MAP DEVELOPED FROM AN AERO-METRIC ENGINEERING INC. SURVEY, DATED JULY 21, 1993.
2. INVESTIGATION POINTS HAVE BEEN LOCATED BASED ON GENTILE AND ASSOCIATES, INC. SURVEY PERFORMED ON DURING JUNE AND JULY 1993.


#### ALTERNATIVE G2 PROPOSES


1. USE OF EXISTING EXTRACTION DEVICES GWF1-GWF14 FOR LFG COLLECTION IN "NEW LANDFILL."
2. USE OF EXISTING LEACHATE PIEZOMETERS LP1-LP4 AND LP10-LP14 FOR LFG EXTRACTION IN "OLD LANDFILL."
3. CONSTRUCTION OF NEW LFG WELLS GE1-GE5.
4. CONSTRUCTION OF HEADER PIPING SYSTEM AND BLOWER/FLARE STATION IN "OLD LANDFILL."



FIGURE 11

ALTERNATIVE G2-UPGRADE/SUPPLEMENTATION OF LFG SYSTEM	
FEASIBILITY STUDY	
H.O.D. LANDFILL	
WASTE MANAGEMENT	
ANTIOCH, ILLINOIS	
Drawing Number	1252035
03090210	B11
MONTGOMERY WATSON	
Developed By	TST
Drawn By	DKP
Approved By	TAB
Date	2/5/98
Reference	2/132/035/03090210/AND05/811
Revisions	





#### LEGEND (EXISTING)

- APPROXIMATE PROPERTY LINE
- APPROXIMATE LIMITS OF LANDFILLED AREA
- 780 TOPOGRAPHIC CONTOUR LINE
- TREES, BRUSH
- BUILDING
- FENCE LINE
- MHW/ MHE LEACHATE COLLECTION MANHOLE WEST/ LEACHATE COLLECTION MANHOLE EAST
- ◆ P2A LEACHATE EXTRACTION WELL LOCATION AND NUMBER
- ◆ P8 LEACHATE PIEZOMETER LOCATION AND NUMBER
- EXISTING LEACHATE COLLECTION TOE DRAIN (LOCATION APPROXIMATE)

#### LEGEND (PROPOSED)

- PROPOSED LEACHATE TOE DRAIN EXTENSION
- PROPOSED LEACHATE STORAGE TANK

#### NOTES

1. BASE MAP DEVELOPED FROM AN AERO-METRIC ENGINEERING INC. SURVEY, DATED JULY 21, 1993.
2. INVESTIGATION POINTS HAVE BEEN LOCATED BASED ON GENTILE AND ASSOCIATES, INC. SURVEY PERFORMED ON DURING JUNE AND JULY 1993.

#### ALTERNATIVE LC2 PROPOSES

1. CONSTRUCTION OF NEW LEACHATE TOE DRAIN EXTENSIONS.
2. USE OF THE CURRENTLY-USED EXTRACTION DEVICES (MHE, MHW, P1, P2A, P3A, P8, P9, P10).
3. USE OF EXISTING WELLS (LP1-LP14) FOR LEACHATE EXTRACTION AS NECESSARY.



FIGURE 13

ALTERNATIVE LC2-TOE-OF-SLOPE LEACHATE COLLECTION

FEASIBILITY STUDY  
H.O.D. LANDFILL  
WASTE MANAGEMENT OF ILLINOIS, INC.  
ANTIOCH, ILLINOIS


Drawing Number  
1252035  
03090210

B13

MONTGOMERY  
WATSON



Developed By TST  
Approved By TAB  
Reference J-1152/035/03090210/ALTERNATIVE LC2  
Revisions  
Drawn By DKP  
Date 2/5/98



#### LEGEND (EXISTING)

- APPROXIMATE PROPERTY LINE
- .-.- APPROXIMATE LIMITS OF LANDFILLED AREA
- 780 TOPOGRAPHIC CONTOUR LINE
- TREES, BRUSH
- BUILDING
- FENCE LINE
- MHW/ MHE LEACHATE COLLECTION MANHOLE WEST/ LEACHATE COLLECTION MANHOLE EAST
- ◆ P2A LEACHATE EXTRACTION WELL LOCATION AND NUMBER
- ⊙ LP8 LEACHATE PIEZOMETER LOCATION AND NUMBER
- EXISTING LEACHATE COLLECTION TOE DRAIN

#### LEGEND (PROPOSED)

- GAS/LEACHATE HEADER PIPING
- .-.- PROPOSED LEACHATE TRANSPORT PIPE

#### NOTES

1. BASE MAP DEVELOPED FROM AN AERO-METRIC ENGINEERING INC. SURVEY, DATED JULY 21, 1993.
2. INVESTIGATION POINTS HAVE BEEN LOCATED BASED ON GENTILE AND ASSOCIATES, INC. SURVEY PERFORMED ON DURING JUNE AND JULY 1993.

#### ALTERNATIVE LC3 PROPOSES

1. CONSTRUCTION OF NEW LEACHATE COLLECTION PIPING IN NEW LANDFILL AREA.
2. USE OF THE CURRENTLY-USED EXTRACTION DEVICES (MHE, MHW, P1, P2A, P3A, P8, P9, P10).
3. USE OF EXISTING WELLS (LP1-LP14)
4. INSTALL ADDITIONAL LEACHATE HEADER PIPING CONNECTING DUAL EXTRACTION WELLS TO A CENTRALLY LOCATED STORAGE/TREATMENT FACILITY.



FIGURE 14

ALTERNATIVE LC3-UPGRADE/SUPPLEMENTATION OF LEACHATE SYSTEM

FEASIBILITY STUDY  
H.O.D. LANDFILL  
WASTE MANAGEMENT OF ILLINOIS, INC.  
ANTIOCH, ILLINOIS

Drawing Number  
1252035  
03090210 B14  
**MONTGOMERY WATSON**

Developed By TST  
Approved By TAB  
Reference J/1252/035/03090210/MWH02/B14.dwg  
Drawn By DKP  
Date 2/5/98  
Revisions



**FIGURE 15**



**ՀԱՅԿ-ՕԶՈՐԻ**

A



**APPENDIX A**  
**TSC TESTING REPORTS**





## TESTING SERVICE CORPORATION

Subsurface Exploration  
Geotechnical Engineering  
Construction Materials Engineering & Testing  
Environmental Engineering  
Geosciences & Hydrogeologic Studies  
Monitoring Wells

February 21, 1991

WASTE MANAGEMENT OF NORTH AMERICA, INC.  
Midwest Region  
Two Westbrook Corporate Center  
Suite 1000  
Westchester, Illinois 60153

Attention: Mr. March Smith

RE: L - 27,306  
H.O.D. LANDFILL  
Antioch, Illinois

Dear Mr. Smith:

TESTING SERVICE CORPORATION (TSC) has completed the work included in making shallow probes of final cover material placed across the entire site at H.O.D. Landfill. The probes were made for the purpose of determining the thickness of the final cover. Several visits to this site were made between July, 1989, and February, 1991, at which time a total of 75 cover probes were made.

The probes were placed on a grid pattern with 200 foot spacings north to south and 150 feet east to west. This allowed for a drilling density of approximately one probe for every 30,000 square feet or three-quarters of an acre. This was done to achieve random samples and yet obtain representative coverage of the final cover over the entire site. The locations and recorded thicknesses of final cover are listed in Table 1 included with this correspondence. Also enclosed is a boring location plan. The probes are numbered B-1 through B-75.

The probes were made according to currently recommended American Society for Testing and Materials procedures. The work was performed using hand auger equipment or with a truck mounted drill rig. When using the truck mounted drill rig, the probes were drilled using solid stem auger and samples were obtained with a split spoon sampling device. The samples were taken solely for the purpose of identifying the final cover and were discarded once they were identified and described. At the completion of drilling, the boreholes were sealed to ground surface with hydrated sodium bentonite pellets.

A minimum thickness of 4.0 feet has been established for the final cover at this site based on requirements of the operating permit and the corporate policy of Waste Management. To document this thickness, the probes were advanced until either a full 4.0 feet of final cover had been sampled or refuse was encountered. Final cover depths in excess of 4.0 feet were not documented. The field work was supervised by a geologist from Testing Service Corporation.

The results of the probes are listed in Table 1 included with this correspondence. The table shows that all 75 locations contained a minimum 4.0 feet of final cover material.

--- 22


WASTE MANAGEMENT OF NORTH AMERICA, INC.  
L - 27,306 --- February 21, 1991

It has been a pleasure to assist you with this work. Please call if there are any questions or when we can be of further service.

Respectfully submitted,

TESTING SERVICE CORPORATION

*Wayne W. Moky*  
Wayne W. Moky  
President and  
Registered Professional Engineer  
Illinois No. 35768



Prepared by:

*Jane E. Matheney*  
Jane E. Matheney  
Project Geologist

WWM:JEM:kw

Enclosures: Table 1  
Boring Location Plan

TABLE 1  
H.O.D. LANDFILL  
ANTIOCH, ILLINOIS  
FINAL COVER PROBES

<u>COVER PROBE NUMBER</u>	<u>LOCATION</u>	<u>COVER THICKNESS (FEET)</u>
1	1+00S/25+50W	4.0 +
2	1+00S/14+00W	4.0 +
3	1+00S/22+50W	4.0 +
4	1+00S/21+00W	4.0 +
5	1+00S/19+00W	4.0 +
6	3+00S/19+00W	4.0 +
7	3+00S/20+50W	4.0 +
8	3+00S/22+00W	4.0 +
9	3+00S/23+50W	4.0 +
10	3+00S/25+00W	4.0 +
11	5+00S/18+00W	4.0 +
12	5+00S/19+50W	4.0 +
13	5+00S/21+00W	4.0 +
14	5+00S/22+50W	4.0 +
15	5+00S/24+00W	4.0 +
16	7+00S/18+00W	4.0 +
17	6+00S/24+00W	4.0 +
18	6+00S/22+50W	4.0 +
19	6+00S/25+00W	4.0 +
20	7+50S/25+50W	4.0 +
21	9+00S/25+50W	4.0 +
22	10+50S/25+50W	4.0 +
23	11+50S/25+50W	4.0 +
24	10+50S/24+40W	4.0 +
25	12+00S/23+00W	4.0 +
26	12+35S/23+00W	4.0 +
27	12+35S/21+50W	4.0 +
28	12+35S/20+00W	4.0 +
29	9+00S/24+40W	4.0 +
30	10+65S/23+20W	4.0 +
31	10+65S/21+50W	4.0 +
32	10+65S/20+00W	4.0 +
33	9+40S/20+00W	4.0 +
34	9+40S/21+50W	4.0 +
35	9+40S/23+20W	4.0 +
36	0+50S/17+00W	4.0 +
37	0+50S/15+50W	4.0 +
38	0+50S/14+00W	4.0 +
39	0+50S/12+50W	4.0 +
40	0+50S/11+00W	4.0 +

(TABLE 1 CON'T)

<u>COVER PROBE NUMBER</u>	<u>LOCATION</u>	<u>COVER THICKNESS (FEET)</u>
41	0+50S/09+50W	4.0 +
42	0+50S/08+00W	4.0 +
43	0+50S/06+50W	4.0 +
44	0+50S/05+00W	4.0 +
45	2+50S/05+00W	4.0 +
46	2+50S/06+50W	4.0 +
47	2+50S/08+00W	4.0 +
48	2+50S/09+50W	4.0 +
49	2+50S/11+00W	4.0 +
50	2+50S/12+50W	4.0 +
51	2+50S/14+00W	4.0 +
52	2+50S/15+50W	4.0 +
53	2+50S/17+00W	4.0 +
54	4+50S/17+00W	4.0 +
55	4+50S/15+50W	4.0 +
56	4+50S/14+00W	4.0 +
57	4+50S/12+50W	4.0 +
58	4+50S/11+00W	4.0 +
59	4+50S/09+50W	4.0 +
60	4+50S/08+00W	4.0 +
61	4+50S/06+50W	4.0 +
62	4+50S/05+00W	4.0 +
63	6+50S/05+00W	4.0 +
64	6+50S/06+50W	4.0 +
65	6+50S/08+00W	4.0 +
66	6+50S/09+50W	4.0 +
67	6+50S/11+00W	4.0 +
68	6+50S/12+50W	4.0 +
69	6+50S/14+00W	4.0 +
70	6+50S/15+50W	4.0 +
71	6+50S/17+00W	4.0 +
72	8+50S/17+00W	4.0 +
73	8+50S/15+50W	4.0 +
74	8+50S/14+00W	4.0 +
75	8+00S/12+50W	4.0 +





## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DRIVE • CAROL STREAM, ILLINOIS 60188-2492 • FAX: (312) 653-2726 • Telephone 312 653-3920

September 28, 1989

WASTE MANAGEMENT OF NORTH AMERICA, INC.  
1300 Willow Road  
Northbrook, Illinois 60062

Attention: Mr. Ken Gelting

RE: L - 27,306  
H.O.D. LANDFILL  
Antioch, Illinois

Dear Mr. Gelting:

Testing Service Corporation has completed the work included in making shallow probes and taking compaction tests of the final cover material. The probes were made for the purpose of determining the thickness of the final cover. There were a total of 16 probes made.

The probes were placed in Area 1 on a grid pattern with 200 foot spacings north to south and 150 feet east to west. This allowed for a drilling density of approximately one probe for every 30,000 square feet or three-quarters of an acre. This was done to achieve random samples of the final cover over the area involved. The locations and cover thicknesses are listed in Table 1 included with this correspondence.

The probes were made according to currently recommended American Society for Testing and Materials procedures. (The probes were drilled with a small 4x4 truck with a mounted drill rig.) At the completion of drilling, the bore holes were filled with a high grade natural sodium based bentonite that forms a permanent yet flexible seal in the bore hole.

A minimum thickness of final cover of 4.0 feet has been established for this site based on requirements of the operating permit and the corporate policy of Waste Management. To document this thickness, the probes were drilled through the final cover material until a full 4 feet of cover material was documented or refuse was found. As can be noted from table 1, 32 of the 35 locations drilled had 4.0 feet or more of final cover material. The remaining three locations that had less than 4.0 feet of cover material were located at 300S/2500W, 1150S/2550W, and 1235S/2000W. These locations found 3.5, 3.5, 3.0 feet of final cover respectively. However, at these locations the cover was tapering off into an undeveloped area and will be reworked at a later date. The field work was supervised by a geologist from Testing Service Corporation.

In-place compaction tests were also performed using nuclear density equipment on a grid pattern with 100 foot spacings north to south as well as east to west. The tests were performed on a brown silty clay fill material being used as final cover. Moisture contents of the final cover documented in this correspondence are noted to be below the specified value of 3.0 - 5.0 percent above the optimum value. Testing of the seal was performed only at the time of completion of a predetermined amount

WASTE MANAGEMENT OF NORTH AMERICA, INC.  
L - 27,306 - September 28, 1989

of the final cover per procedure established by the client. Testing was not performed at the time of placement so moisture contents of the final cover at that time are unknown. The compaction testing was based on a laboratory compaction curve determined by ASTM D 698 (Standard) laboratory procedure. The values for the compaction curve as well as the results of the daily compaction testing are listed on the percent compaction forms included for each days work. Details of the work performed on each of the days are discussed in the following paragraphs.

July 19, 1989 - G. Hofer - Geologist - 4.0 Hours

On this date a bulk sample was obtained of brown silty clay which will be used as fill material to construct the final cover layer. The sample was returned to us by the TSC laboratory where a laboratory compaction curve was determined according to the ASTM D 698 procedure. The maximum dry unit weight was 113.2 pounds per cubic foot and the optimum moisture content was 15.2 percent. A copy of the compaction curve is included with this correspondence.

August 8, 1989 - T. Whipple - Senior Geologist - 8 1/4 Hours

On this date work was performed in the northern half of Area 1. Twenty-four (24) compaction tests were performed on the brown silty clay used as final cover material and acceptable compaction was found at all test locations.

August 9, 1989 - T. Whipple - Senior Geologist - 7.0 Hours

On this date work was performed in the northern half of Area 1. Twenty-five (25) compaction tests were performed on the brown silty clay used as final cover material. Acceptable compaction was found at all test locations.

August 21, 1989 - J. Matheney - Senior Geologist - 6.0 Hours

On this date work was performed in the southern half of Area 1. Thirteen (13) compaction tests were performed on brown silty clay used as final cover material. Acceptable compaction was found at all test locations.

September 5, 1989 - D. Cox - Senior Geologist - 6.0 Hours

On this date work was performed in an area defined by the coordinate locations 9+40S to 10+65S and 20+00W to 23+20W. Six (6) compaction tests were performed on a brown silty clay fill material, and each had acceptable results.

WASTE MANAGEMENT OF NORTH AMERICA, INC.  
L - 27,306 - September 28, 1989

It has been a pleasure to have assisted you with this work. Please call if there are any questions.

Respectfully submitted,

TESTING SERVICE CORPORATION

Wayne W. Moky  
Registered Professional Engineer  
Illinois #35768

Prepared by:

Jane E. Matheney

Jane E. Matheney  
Senior Geologist

BA:JEM:lt

Enclosures: Per Cent Compaction Report  
Laboratory Compaction Curve  
Cover Borings Table





## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

## CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

## PROJECT / LOCATION

H.O.D. LANDFILL - ANTIOCH, ILLINOIS

## ARCHITECT / ENGINEER / OWNER

## DATE

August 8, 1989

## JOB NUMBER

L - 27,306

## REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION/ DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION			
							TEST %	SPECIFICATION %	PASS	FAILS
1	2600W	100S		115.1	9.5	A	100+	90.0	x	
2	2500W	100S		117.0	10.7	A	100+	90.0	x	
3	2400W	100S		110.7	12.0	A	97.8	90.0	x	
4	2300W	100S		120.4	12.3	A	100+	90.0	x	
5	2200W	100S		115.5	12.0	A	100+	90.0	x	
6	2100W	100S		116.5	11.4	A	100+	90.0	x	
7	2000W	100S		115.0	13.9	A	100+	90.0	x	
8	1900W	100S		117.8	12.4	A	100+	90.0	x	
9	2000W	200S		114.1	14.5	A	100+	90.0	x	
10	2100W	200S		111.0	16.7	A	98.0	90.0	x	

## COMMENTS

Elevations were not determined as there are no elevation requirements for final cover.

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASTM D 698

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler	16079	Direct Transmission 9"

Reviewed By:

FIELD TECHNICIAN

Todd Whipple, Geologist

Brian Allen, Senior Engineering Geologist



## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

## CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

## PROJECT / LOCATION

H.O.D. LANDFILL - ANTIOCH, ILLINOIS

## ARCHITECT / ENGINEER / OWNER

## DATE

August 8, 1989

## JOB NUMBER

L - 27,306

## REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION/ DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION			
							TEST %	SPECIFICATION %	PASS	FAILS
11	2200W	200S		111.3	14.4	A	98.3	90.0	x	
12	2300W	200S		117.7	14.0	A	100+	90.0	x	
13	2400W	200S		117.9	12.8	A	100+	90.0	x	
14	2475W	200S		114.7	15.8	A	100+	90.0	x	
15	2450W	300S		117.7	13.8	A	100+	90.0	x	
16	2400W	300S		117.2	12.6	A	100+	90.0	x	
17	2300W	300S		120.5	13.7	A	100+	90.0	x	
18	2200W	300S		115.8	18.3	A	100+	90.0	x	
19	2100W	300S		115.3	12.6	A	100+	90.0	x	
20	2000W	300S		115.6	14.6	A	100+	90.0	x	

## COMMENTS

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASTM D 698

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler	15029	Direct Transmission 8"

Reviewed By:

FIELD TECHNICIAN

Todd Whipple, Geologist

Brian Allen, Senior Engineering Geologist



## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

## CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

## PROJECT / LOCATION

H.O.D. LANDFILL - ANTIOCH, ILLINOIS

## ARCHITECT / ENGINEER / OWNER

## DATE

August 8, 1989

## JOB NUMBER

L - 27,306

## REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION/ DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION		
							TEST %	SPECIFICATION %	PASS/FAIL
21	1900W	300S		119.8	13.1	A	100+	90.0	x
22	1900W	400S		114.3	14.3	A	100+	90.0	x
23	2000W	400S		113.8	14.0	A	100+	90.0	x
24	2100W	400S		112.8	16.2	A	99.6	90.0	x

## COMMENTS

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASTM D 638

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler	16029	Direct Transmission 8"

## FIELD TECHNICIAN

Todd Whipple

Reviewed By:

Brian Allen, Senior Engineering Geologist



## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

PROJECT / LOCATION

H.O.D. LANDFILL - ANTIOCH, ILLINOIS

ARCHITECT / ENGINEER / OWNER

DATE

August 9, 1989

JOB NUMBER

L - 27,306

REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION/ DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION			
							TEST %	SPECIFICATION %	PASS	FAILS
25	2200W	400S	Final Cover	117.7	14.0	A	100+	90.0	x	
26	2300W	400S	"	105.7	18.7	A	93.4	90.0	x	
27	2400W	400S	"	115.7	13.7	A	100+	90.0	x	
28	2475W	400S	"	112.8	11.3	A	99.6	90.0	x	
29	2475W	500S	"	119.7	13.2	A	100+	90.0	x	
30	2400W	500S	"	113.0	14.4	A	100+	90.0	x	
31	2300W	500S	"	115.2	14.3	A	100+	90.0	x	
32	2200W	500S	"	117.3	14.2	A	100+	90.0	x	
33	2100W	500S	"	116.0	13.2	A	100+	90.0	x	
34	2000W	500S	"	108.8	14.7	A	96.1	90.0	x	

## COMMENTS

Elevations were not determined as there are no specifications for elevation at final cover.

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASIM D 698

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler 3401-B	15029	Direct Transmission 8"

Reviewed By:

FIELD TECHNICIAN

Todd Whippie

Brian Allen, Senior Engineering Geologist



## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

## CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

## PROJECT / LOCATION

H.O.D. LANDFILL - ANTIOCH, ILLINOIS

## ARCHITECT / ENGINEER / OWNER

## DATE

August 9, 1989

## JOB NUMBER

L - 27,306

## REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION/ DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION			
							TEST %	SPECIFICATION %	PASS	FAILS
35	1900W	500S	Final Cover	116.8	13.5	A	100+	90.0	x	
	1800W	500S	"	113.3	17.2	A	100+	90.0	x	
37	1800W	600S	"	115.6	16.7	A	100+	90.0	x	
38	1900W	600S	"	116.0	14.2	A	100+	90.0	x	
39	2000W	600S	"	113.7	14.6	A	100+	90.0	x	
40	2100W	600S	"	112.7	14.9	A	99.6	90.0	x	
41	2200W	600S	"	117.5	14.5	A	100+	90.0	x	
42	2300W	600S	"	118.7	14.2	A	100+	90.0	x	
43	2400W	600S	"	118.9	13.0	A	100+	90.0	x	
44	1800W	700S	"	109.6	17.7	A	96.8	90.0	x	

## COMMENTS

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASTM D 698

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler 3401-B	16029	Direct Transmission 8"

Reviewed By:

FIELD TECHNICIAN

Todd Whipple

Brian Allen, Senior Engineering Geologist



## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

## CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

## PROJECT / LOCATION

H.O.D LANDFILL - ANTIOCH, ILLINOIS

## ARCHITECT / ENGINEER / OWNER

## DATE

August 9, 1989

## JOB NUMBER

L - 27,306

## REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION/ DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION			
							TEST %	SPECIFICATION %	PASS	FAILS
45	1900W	700S	Final Cover	118.4	13.3	A	100+	90.0	x	
46	2000W	700S	"	115.7	14.0	A	100+	90.0	x	
47	2100W	700S	"	122.4	13.1	A	100+	90.0	x	
48	2200W	670S	"	121.2	12.8	A	100+	90.0	x	
49	2300W	640S	"	124.9	10.9	A	100+	90.0	x	

## COMMENTS

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASTM D 698

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler 3401-B	16029	Direct Transmission 8"

Reviewed By:

Brian Allen, Senior Engineering Geologist

## FIELD TECHNICIAN

Todd Whipple



## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

## CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

## PROJECT / LOCATION

H.O.D. LANDFILL - ANTIOCH, ILLINOIS

## ARCHITECT / ENGINEER / OWNER

## DATE

August 21, 1989

## JOB NUMBER

L - 27,306

## REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION/ DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION			
							TEST %	SPECIFICATION %	PASS	FAILS
50	6+00S	24+00W	Final Cover	118.1	8.1	A	100+	90.0	x	
	6+00S	22+50W	"	124.2	9.4	A	100+	90.0	x	
52	6+00S	25+00W	"	115.1	9.7	A	100+	90.0	x	
53	7+50S	25+50W	"	127.4	9.9	A	100+	90.0	x	
54	9+00S	25+50W	"	114.6	11.2	A	100+	90.0	x	
55	10+50S	25+50W	"	114.6	12.5	A	100+	90.0	x	
56	11+50S	25+50W	"	119.2	10.9	A	100+	90.0	x	
57	10+50S	24+40W	"	118.0	13.6	A	100+	90.0	x	
58	12+00S	23+00W	"	106.6	11.0	A	94.2	90.0	x	
59	12+35S	23+00W	"	116.8	10.5	A	100+	90.0	x	

## COMMENTS

All tests passed 90% compaction specification. Elevations were not determined as there are no elevation requirements for final cover.

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASTM D 698

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler 3401-B	16502	Direct Transmission 8"

Reviewed By:

FIELD TECHNICIAN

J. Matheney, Geologist

Brian Allen, Senior Engineering Geologist



## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

## CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

## PROJECT / LOCATION

H.O.D. LANDFILL - ANTIOCH, ILLINOIS

## ARCHITECT / ENGINEER / OWNER

## DATE

August 21, 1989

## JOB NUMBER

L - 27,306

## REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION/ DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION			
							TEST %	SPECIFICATION %	PASS	FAILS
60	12+35S	21+50W	Final Cover	112.3	11.2	A	99.2	90.0	x	
61	12+35S	20+00W	"	112.9	13.4	A	99.7	90.0	x	
62	9+00S	24+40W	"	118.7	14.0	A	100+	90.0	x	

## COMMENTS

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASTM D 698

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler 3401-B	16502	Direct Transmission 8"

Reviewed By:

## FIELD TECHNICIAN

J. Matheney, Geologist

Brian Allen, Senior Engineering Geologist





## TESTING SERVICE CORPORATION

457 EAST GUNDERSEN DR. • CAROL STREAM, ILLINOIS 60188-2492

Telephone (312) 653-3920

## CLIENT

WASTE MANAGEMENT OF NORTH AMERICA, INC.

## PROJECT / LOCATION

H.O.D. LANDFILL - ANTIOCH, ILLINOIS

## ARCHITECT / ENGINEER / OWNER

## DATE

September 5, 1989

## JOB NUMBER

L - 27,306

## REPORT NUMBER

1

## FIELD DATA

TEST NO.	LOCATION		ELEVATION DEPTH	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	LCC	COMPACTION		
							TEST %	SPECIFICATION	PASS/FAILS
63	10+65S	23+20W	Final Cover	127.0	9.3	A	100+	95.0	x
64	10+65S	21+50W	"	122.3	11.9	A	100+	95.0	x
65	10+65S	20+00W	"	118.3	12.3	A	100+	95.0	x
66	9+40S	20+00W	"	116.5	9.3	A	100+	95.0	x
67	9+40S	21+50W	"	124.2	9.4	A	100+	95.0	x
68	9+40S	23+20W	"	118.2	10.5	A	100+	95.0	x

## COMMENTS

Elevations were not determined as there are no specifications for elevation of final cover.

## LABORATORY COMPACTION CURVES

LCC	SOIL / MATERIAL DESCRIPTION	DRY UNIT WEIGHT PCF	MOISTURE CONTENT %	PROCEDURE
A	Brown silty CLAY, trace sand and gravel	113.2	15.2	ASTM D 698

FIELD TEST PROCEDURE	MANUFACTURER / MODEL NUMBER	SERIAL NUMBER	MODE
Nuclear gauge	Troxler 3401-B	15205	Direct Transmission 8"


Reviewed By:

FIELD TECHNICIAN

D. Cox

Brian Allen, Senior Engineering Geologist

Unit Weight In Pounds Per Cubic Foot



Laboratory Compaction Curve For: Brown silty CLAY, with trace sand and gravel

Project: H.O.D. LANDFILL  
Antioch, Illinois

Client: WASTE MANAGEMENT

Laboratory Compaction Procedure

☐ ASTM D 1557-78

☒ AASHTO T 99-74

(ASTM D 698-79)

TESTING SERVICE CORPORATION  
457 EAST GUNDERSEN DRIVE  
CAROL STREAM, ILLINOIS 60158  
L- 27,306  
July 24, 1989

TABLE 1  
H.O.D. LANDFILL - ANTIOCH, ILLINOIS  
COVER PROBES

<u>PROBE #</u>	<u>LOCATION</u>		<u>COVER THICKNESS</u>
1	1+00S	25+50W	4'
2	1+00S	24+00W	4'
3	1+00S	22+50W	4'
4	1+00S	21+00W	4'
5	1+00S	19+00W	4'
6	3+00S	19+00W	4'
7	3+00S	20+50W	4'
8	3+00S	22+00W	4'
9	3+00S	23+50W	4'
10	3+00S	25+00W	3'6" - Rubber tire, garbage discolored CLAY
11	5+00S	18+00W	4'
12	5+00S	19+50W	4'
13	5+00S	21+00W	4'
14	5+00S	22+50W	4'
15	5+00S	24+00W	4'
16	7+00S	15+00W	4'
17	6+00S	24+00W	4'
18	6+00S	22+50W	4'
19	6+00S	25+00W	4'
20	7+50S	25+30W	4'
21	9+00S	25+50W	4'
22	10+50S	25+50W	4'
23	11+50S	25+50W	3 1/2' - hit garbage
24	10+50S	24+40W	4'
25	12+00S	23+00W	4'
26	12+35S	23+00W	4'
27	12+35S	21+50W	4'
28	12+35S	20+00W	3' - hit garbage
29	9+00S	24+40W	4'
30	10+65S	23+20W	4'
31	10+65S	21+50W	4'
32	10+65S	20+00W	4'
33	9+40S	20+00W	4'
34	9+40S	21+50W	4'

**B**



**APPENDIX B**  
**CAPPING TIMING ESTIMATE**

## CAPPING TIMING

C1: \*Assume 6,000 cubic yards/day can be moved, 5-day work week

All soil = 139,000 cubic yards

Time<sub>c1</sub> = (139,000 cubic yards)/6,000 cubic yards/day = 24 days

Allow 25% for contingencies such as rain, equip. delays, etc. = 

30 days
6 weeks

C2: \*Assume 6,000 cubic yards/day can be moved, 5-day work week

Total cover soils = 329,120 cubic yards

Total clay = 164,560 cubic yards

Total cap = 493,680 cubic yards

Time<sub>c2</sub> = (493,680 cubic yards)/6,000 cubic yards/day = 83 days

Allow 25% for contingencies such as rain, equip. delays, etc. = 

104 days
21 weeks

C3: Supplemental Clay Option -

Same as C2 with addition of an extra 105,000 cu.yd. of clay

83 days + (105,000 cubic yards/6,000 cubic yards/day) = 101 days

Allow 25% for contingencies such as rain, equip. delays, etc. = 

127 days
26 weeks

C3: New Off-Site Clay Option -

Same as C2 with addition of an extra 250,000 cu.yd. of clay

83 days + (250,000 cubic yards/6,000 cubic yards/day) = 125 days

Allow 25% for contingencies such as rain, equip. delays, etc. = 

157 days
32 weeks

*If the C3 option is selected, cap construction will take more than one construction season.*

**\*Estimation of amount of additional clay and cover soil needed to create 811 cap (for Alternative C3)**

**Given**

Old Landfill:	24 acres, 6" to 14" clay	avg. = 10"
New Landfill:	27 acres 25" to 63" clay	avg. = 44"
Total (both):	51 acres, 49" to 87" clay and cover material	avg. = 68"

$$\boxed{\text{Total Cap - Clay} = \text{Cover Soil}}$$

**Cover Soils Needed to Create 811 Cap**

Old Landfill:  $(24A) (43,560 \text{ sq.ft./A}) [68 \text{ ft}/12 - 10 \text{ ft}/12]/27$   
= 187,150 cu.yd.

New Landfill:  $(27A)(43,560 \text{ sq.ft./A}) [68 \text{ ft}/12 - 44 \text{ ft}/12 \text{ ft}]/27$   
= 87,120 cu.yd.

Total Cover Soils = 274,270 cu.yd.

Cover Soils Needed:  $(51A)(43,560 \text{ sq.ft./A}) (3 \text{ ft})/27$   
= 246,840 cu.yd.

Surplus Cover Soil = 27,430 cu.yd.

**No additional cover  
material needed**

**Clay Needed to Create 811 Cap**

Total Existing Clay =  $(24A) (43,560 \text{ sq.ft./A}) (10 \text{ ft}/12)/27 +$   
 $(27A) (43,560 \text{ sq.ft./A})(44 \text{ ft}/12)/27$   
= 191,990 cu.yd.

\*Assume only 75% of existing clay is reuseable for construction of new cap:

Total Available Clay = 143,993 cu.yd.

Additional Clay Needed = 246,840 cu.yd. - 143,993 cu.yd.

= **102,850 cu.yd. (Rounded up to 105,000 cu. yd.)**

C





**APPENDIX C**  
**HELP MODEL OUTPUT**


**HELP model output:  
infiltration (average annual totals)**

	currently	c1	c1 w/freeze of top 30 cm	c1 w/freeze of top 30 cm & lateral drainage
Precipitation (In.)	32.89 (100%)	32.89 (100%)	32.89 (100%)	32.89 (100%)
Runoff (In.(%))	2.97 (9.03%)	9.152 (27.8%)	9.154 (27.83%)	2.475 (7.525%)
Evapotranspiration (In.(%))	28.789 (87.53%)	22.103 (67.2%)	22.095 (67.18%)	22.621 (68.77%)
Percolation/Leakage through clay liner (In.(%))	3.95 (12.01%)	1.62455 (4.94%)	1.62966 (4.95%)	1.83317 (5.57%)
Lateral Drainage Collected (In.(%))	0 (0%)	0 (0%)	0 (0%)	5.867 (17.84%)


	c2	c2 w/freeze of top 30cm	c2 w/freeze of top 30cm & lateral drainage
Precipitation (In.)	32.89 (100%)	32.89 (100%)	32.89 (100%)
Runoff (In.(%))	5.927 (18.02%)	5.895 (17.92%)	2.009 (6.11%)
Evapotranspiration (In.(%))	24.86 (75.59%)	24.871 (75.62%)	24.923 (75.77%)
Percolation/Leakage through clay liner (In.(%))	2.024 (6.21%)	2.041 (6.21%)	1.864 (5.67%)
Lateral Drainage Collected (In.(%))	0 (0%)	0 (0%)	3.877 (11.79%)

	c3	c3 w/freeze of top 30cm	c3 w/freeze of top 30cm & lateral drainage
Precipitation (In.)	32.89 (100%)	32.89 (100%)	32.89 (100%)
Runoff (In.(%))	5.691 (17.3%)	5.669 (17.24%)	1.902 (5.78%)
Evapotranspiration (In.(%))	24.878 (75.64%)	24.88 (75.65%)	24.799 (75.4%)
Percolation/Leakage through clay liner (In.(%))	2.153 (6.55%)	2.169 (6.59%)	1.75 (5.32%)
Lateral Drainage Collected (In.(%))	0 (0%)	0 (0%)	4.20 (12.77%)


**HOD LANDFILL CAP ALTERNATIVE C1**



**HOD LANDFILL CAP ALTERNATIVE C2**



**HOD LANDFILL CAP ALTERNATIVE C3**



**MONTGOMERY WATSON**  
Chicago, Illinois

H.O.D. LANDFILL  
WASTE MANAGEMENT OF ILLINOIS, INC.  
ANTIOCH, ILLINOIS  
**CROSS-SECTION OF MODELED  
CAPPING ALTERNATIVES**  
FIGURE C1

▼

\* \*

TIME: 19: 7      DATE: 4/15/1998

Page 1

Existing.out

\*\*\*\*\*

TITLE: HOD landfill existing

\*\*\*\*\*  
\*\*\*\*\*

E NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WER  
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

-----

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 4

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4370	VOL/VOL
FIELD CAPACITY	=	0.1050	VOL/VOL
WILTING POINT	=	0.0470	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.2342	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.170000002000E-02	CM/SEC

LAYER 2

-----

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 10

THICKNESS	=	30.00	INCHES
POROSITY	=	0.3980	VOL/VOL
FIELD CAPACITY	=	0.2440	VOL/VOL
WILTING POINT	=	0.1360	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.3175	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.119999997000E-03	CM/SEC

LAYER 3

-----

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 16

	Existing.out		
THICKNESS	=	12.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4270	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.100000001000E-06	CM/SEC

#### GENERAL DESIGN AND EVAPORATIVE ZONE DATA

-----

NOTE: SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED.

SCS RUNOFF CURVE NUMBER	=	60.00	
FRACTION OF AREA ALLOWING RUNOFF	=	25.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	1.000	ACRES
EVAPORATIVE ZONE DEPTH	=	18.0	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	4.742	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	7.398	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	1.914	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	16.053	INCHES
TOTAL INITIAL WATER	=	16.053	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

#### EVAPOTRANSPIRATION AND WEATHER DATA

-----

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM  
chicago IL

MAXIMUM LEAF AREA INDEX	=	0.00
START OF GROWING SEASON (JULIAN DATE)	=	117
END OF GROWING SEASON (JULIAN DATE)	=	290
AVERAGE ANNUAL WIND SPEED	=	10.30 MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	71.00 %
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	65.00 %
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	70.00 %
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	72.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR CHICAGO ILLINOIS

Existing.out

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/
DEC	-----	-----	-----	-----	-----	-----
---						
	1.60	1.31	2.59	3.66	3.15	4.
08	3.63	3.53	3.35	2.28	2.06	2.
10						

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/
DEC	-----	-----	-----	-----	-----	-----
---						
	21.40	26.00	36.00	48.80	59.10	68.
60	73.00	71.90	64.70	53.50	39.80	27.
70						

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USIN  
G COEFFICIENTS FOR CHICAGO ILLINOIS

STATION LATITUDE = 41.78 DEGREES

\*\*\*\*\*  
\*\*\*\*\*

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 20

-----  
-----

JAN/JUL FEB/AUG MAR/SEP APR/OCT MAY/NOV

JUN/DEC	Existing.out				
-----	-----	-----	-----	-----	-----
PRECIPITATION					
-----					
TOTALS	1.56	1.42	2.51	3.11	3.62
3.94					
	3.78	2.92	3.50	2.24	2.23
2.08					
STD. DEVIATIONS	0.64	0.65	1.40	1.67	1.86
2.09					
	1.75	1.72	1.68	1.27	1.02
1.00					
RUNOFF					
-----					
TOTALS	0.226	0.459	0.646	0.260	0.242
0.211					
	0.139	0.128	0.147	0.051	0.237
0.222					
STD. DEVIATIONS	0.316	0.594	0.864	0.511	0.655
0.703					
	0.468	0.290	0.354	0.189	0.490
0.408					
EVAPOTRANSPIRATION					
-----					
TOTALS	0.690	0.877	2.182	2.896	3.270
3.296					
	3.320	2.686	2.523	1.946	1.276
0.829					
STD. DEVIATIONS	0.148	0.234	0.355	0.848	1.289
1.073					
	1.409	1.351	0.956	0.574	0.294
0.163					
PERCOLATION/LEAKAGE THROUGH LAYER 3					
-----					
TOTALS	0.2592	0.2351	0.2873	0.3486	0.3660
0.3463					
	0.3560	0.3520	0.3441	0.3675	0.3570
0.3302					
STD. DEVIATIONS	0.0300	0.0324	0.0479	0.0518	0.0429
0.0384					
	0.0439	0.0463	0.0455	0.0429	0.0429
0.0403					



## Existing.out

-----  
 -----  
 AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)  
 -----  
 -----

## DAILY AVERAGE HEAD ACROSS LAYER 3

AVERAGES	17.2517	17.6222	20.6895	28.9943	29.6543
28.7223					
	28.5100	28.0547	28.4655	29.8233	29.9848
25.5816					
STD. DEVIATIONS	3.2273	4.0824	5.4562	6.0910	4.8845
4.5202					
	4.9928	5.2736	5.3457	4.8836	5.0415
4.5810					

\*\*\*\*\*  
 \*\*\*\*\*

\*\*\*\*\*  
 \*\*\*\*\*

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH  
 20

PERCENT	INCHES	CU. FEET
-----	-----	-----
PRECIPITATION	32.89 ( 5.107)	119401.6
100.00		
RUNOFF	2.968 ( 2.6990)	10773.38
9.023		
EVAPOTRANSPIRATION	25.789 ( 3.0354)	93613.54
78.402		
PERCOLATION/LEAKAGE THROUGH	3.94934 ( 0.40005)	14336.111
12.00663		
FROM LAYER 3		
AVERAGE HEAD ACROSS TOP	26.113 ( 3.860)	
OF LAYER 3		

## Existing.out

CHANGE IN WATER STORAGE            0.187    ( 1.6310)            678.57  
0.568

\*\*\*\*\*  
\*\*\*\*\*

\*\*\*\*\*  
\*\*\*\*\*

## PEAK DAILY VALUES FOR YEARS      1 THROUGH      20

		(INCHES)	(CU. FT
00	PRECIPITATION	4.09	14846.7
215	RUNOFF	0.828	3005.0
8987	PERCOLATION/LEAKAGE THROUGH LAYER 3	0.013606	49.3
	AVERAGE HEAD ACROSS LAYER 3	36.000	
090	SNOW WATER	4.36	15834.7
	MAXIMUM VEG. SOIL WATER (VOL/VOL)		0.4110
	MINIMUM VEG. SOIL WATER (VOL/VOL)		0.1385

\*\*\*\*\*  
\*\*\*\*\*

\*\*\*\*\*  
\*\*\*\*\*

FINAL WATER STORAGE AT END OF YEAR      20

Existing.out

-----

LAYER	(INCHES)	(VOL/VOL)
-----	-----	-----
1	2.6220	0.4370
2	11.9399	0.3980
3	5.1240	0.4270
SNOW WATER	0.000	

\*\*\*\*\*  
 \*\*\*\*\*  
 \*\*\*\*\*  
 \*\*\*\*\*



\*\*\*\*\*

TITLE: HOD landfill c1 cap

\*\*\*\*\*  
\*\*\*\*\*

E NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WER  
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1  
-----

TYPE 1 - VERTICAL PERCOLATION LAYER  
MATERIAL TEXTURE NUMBER 4

THICKNESS	=	12.00	INCHES
POROSITY	=	0.4370	VOL/VOL
FIELD CAPACITY	=	0.1050	VOL/VOL
WILTING POINT	=	0.0470	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4118	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.170000002000E-02	CM/SEC

LAYER 2  
-----

TYPE 3 - BARRIER SOIL LINER  
MATERIAL TEXTURE NUMBER 16

THICKNESS	=	24.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4270	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.100000001000E-06	CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA  
-----

NOTE: SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED.

Clredo2.out

SCS RUNOFF CURVE NUMBER	=	70.00	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	1.000	ACRES
EVAPORATIVE ZONE DEPTH	=	12.0	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	4.942	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	5.244	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	0.564	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	15.190	INCHES
TOTAL INITIAL WATER	=	15.190	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM  
chicago IL

MAXIMUM LEAF AREA INDEX	=	0.00
START OF GROWING SEASON (JULIAN DATE)	=	117
END OF GROWING SEASON (JULIAN DATE)	=	290
AVERAGE ANNUAL WIND SPEED	=	10.30 MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	71.00 %
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	65.00 %
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	70.00 %
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	72.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/
DEC	-----	-----	-----	-----	-----	----
08	1.60	1.31	2.59	3.66	3.15	4.
10	3.63	3.53	3.35	2.28	2.06	2.

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING

C1redo2.out  
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/
DEC	-----	-----	-----	-----	-----	----
---						
60	21.40	26.00	36.00	48.80	59.10	68.
70	73.00	71.90	64.70	53.50	39.80	27.

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING

G COEFFICIENTS FOR CHICAGO ILLINOIS

STATION LATITUDE = 41.78 DEGREES

\*\*\*\*\*  
\*\*\*\*\*

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 20

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV
JUN/DEC	-----	-----	-----	-----	-----
-----					
PRECIPITATION					
-----					
TOTALS	1.56	1.42	2.51	3.11	3.62
3.94	3.78	2.92	3.50	2.24	2.23
2.08					
STD. DEVIATIONS	0.64	0.65	1.40	1.67	1.86
2.09	1.75	1.72	1.68	1.27	1.02
1.00					

	C1redo2.out				
RUNOFF					
-----					
TOTALS	0.723	0.961	1.330	0.562	0.524
0.631	0.891	0.713	1.001	0.502	0.636
0.678					
STD. DEVIATIONS	0.853	0.774	1.130	0.722	1.053
1.156	1.026	0.845	1.050	0.669	0.763
0.649					
EVAPOTRANSPIRATION					
-----					
TOTALS	0.688	0.842	1.542	2.406	2.862
2.994	2.762	2.164	2.151	1.666	1.231
0.795					
STD. DEVIATIONS	0.147	0.208	0.396	0.778	1.006
0.975	1.007	0.995	0.750	0.552	0.273
0.159					
PERCOLATION/LEAKAGE THROUGH LAYER 2					
-----					
TOTALS	0.1136	0.1004	0.1167	0.1376	0.1464
0.1421	0.1473	0.1471	0.1437	0.1489	0.1458
0.1350					
STD. DEVIATIONS	0.0017	0.0004	0.0073	0.0094	0.0047
0.0032	0.0030	0.0029	0.0027	0.0032	0.0036
0.0097					

-----  
 -----  
 AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)  
 -----  
 -----

DAILY AVERAGE HEAD ACROSS LAYER 2					
-----					
AVERAGES	1.6501	1.3012	2.5674	8.3508	9.3170
9.4311	9.5298	9.4812	9.7908	9.8788	10.2889
6.7222					



	C1redo2.out				
STD. DEVIATIONS	0.0872	0.0957	1.6685	2.2184	1.0590
0.7485					
	0.6737	0.6605	0.6235	0.7176	0.8358
2.2130					

\*\*\*\*\*  
\*\*\*\*\*

\*\*\*\*\*  
\*\*\*\*\*

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 20

PERCENT	INCHES	CU. FEET
PRECIPITATION	32.89 ( 5.107)	119401.6
100.00		
RUNOFF	9.152 ( 3.3817)	33220.92
27.823		
EVAPOTRANSPIRATION	22.103 ( 2.3707)	80233.81
67.197		
PERCOLATION/LEAKAGE THROUGH	1.62455 ( 0.01886)	5897.101
4.93888		
FROM LAYER 2		
AVERAGE HEAD ACROSS TOP	7.359 ( 0.368)	
OF LAYER 2		
CHANGE IN WATER STORAGE	0.014 ( 1.3309)	49.78
0.042		

\*\*\*\*\*  
\*\*\*\*\*

\*\*\*\*\*  
\*\*\*\*\*

PEAK DAILY VALUES FOR YEARS 1 THROUGH 20

C1redo2.out

		(INCHES)	(CU. FT)
00	PRECIPITATION	4.09	14846.7
936	RUNOFF	3.376	12254.8
2133	PERCOLATION/LEAKAGE THROUGH LAYER 2	0.005102	18.5
	AVERAGE HEAD ACROSS LAYER 2	12.000	
090	SNOW WATER	4.36	15834.7
	MAXIMUM VEG. SOIL WATER (VOL/VOL)		0.4370
	MINIMUM VEG. SOIL WATER (VOL/VOL)		0.0557

\*\*\*\*\*  
\*\*\*\*\*

\*\*\*\*\*  
\*\*\*\*\*

FINAL WATER STORAGE AT END OF YEAR 20

LAYER	(INCHES)	(VOL/VOL)
1	5.2162	0.4347
2	10.2480	0.4270
SNOW WATER	0.000	

\*\*\*\*\*  
\*\*\*\*\*  
\*\*\*\*\*  
\*\*\*\*\*

C1redo2.out

```

*****
*****
*****
*****
**
**
**
**
**
HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE
**
**
HELP MODEL VERSION 3.01      (14 OCTOBER 1994)
**
**
DEVELOPED BY ENVIRONMENTAL LABORATORY
**
**
USAE WATERWAYS EXPERIMENT STATION
**
**
FOR USEPA RISK REDUCTION ENGINEERING LABORATORY
**
**
**
*****
*****
*****
*****

```

TIME: 11:30      DATE: 4/ 3/1998

Page 1

\*\*\*\*\*

TITLE: HOD landfill cap c2

\*\*\*\*\*  
\*\*\*\*\*

E NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WER  
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

## LAYER 1

-----

## TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 4

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4370	VOL/VOL
FIELD CAPACITY	=	0.1050	VOL/VOL
WILTING POINT	=	0.0470	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.2281	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.170000002000E-02	CM/SEC

## LAYER 2

-----

## TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 10

THICKNESS	=	18.00	INCHES
POROSITY	=	0.3980	VOL/VOL
FIELD CAPACITY	=	0.2440	VOL/VOL
WILTING POINT	=	0.1360	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.3766	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.119999997000E-03	CM/SEC

## LAYER 3

-----

## TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 16

## C2run2.out

THICKNESS	=	24.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4270	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.100000001000E-06	CM/SEC

## GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED.

SCS RUNOFF CURVE NUMBER	=	70.00	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	1.000	ACRES
EVAPORATIVE ZONE DEPTH	=	18.0	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	5.815	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	7.398	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	1.914	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	18.396	INCHES
TOTAL INITIAL WATER	=	18.396	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

## EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM  
chicago IL

MAXIMUM LEAF AREA INDEX	=	0.00
START OF GROWING SEASON (JULIAN DATE)	=	117
END OF GROWING SEASON (JULIAN DATE)	=	290
AVERAGE ANNUAL WIND SPEED	=	10.30 MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	71.00 %
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	65.00 %
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	70.00 %
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	72.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR CHICAGO ILLINOIS

C2run2.out

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/
DEC	-----	-----	-----	-----	-----	----
---						
	1.60	1.31	2.59	3.66	3.15	4.
08						
	3.63	3.53	3.35	2.28	2.06	2.
10						

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/
DEC	-----	-----	-----	-----	-----	----
---						
	21.40	26.00	36.00	48.80	59.10	68.
60						
	73.00	71.90	64.70	53.50	39.80	27.
70						

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USIN  
G COEFFICIENTS FOR CHICAGO ILLINOIS

STATION LATITUDE = 41.78 DEGREES

\*\*\*\*\*  
\*\*\*\*\*

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 20

JAN/JUL FEB/AUG MAR/SEP APR/OCT MAY/NOV

JUN/DEC	C2run2.out				
-----	-----	-----	-----	-----	-----
PRECIPITATION					
-----					
TOTALS	1.56	1.42	2.51	3.11	3.62
3.94					
	3.78	2.92	3.50	2.24	2.23
2.08					
STD. DEVIATIONS	0.64	0.65	1.40	1.67	1.86
2.09					
	1.75	1.72	1.68	1.27	1.02
1.00					
RUNOFF					
-----					
TOTALS	0.631	0.881	1.241	0.318	0.320
0.330					
	0.316	0.304	0.424	0.245	0.379
0.538					
STD. DEVIATIONS	0.717	0.746	1.139	0.523	0.791
0.978					
	0.697	0.609	0.728	0.462	0.688
0.557					
EVAPOTRANSPIRATION					
-----					
TOTALS	0.688	0.872	1.937	2.657	3.164
3.295					
	3.233	2.592	2.441	1.881	1.282
0.818					
STD. DEVIATIONS	0.147	0.236	0.347	0.853	1.179
1.051					
	1.183	1.262	0.878	0.623	0.282
0.161					
PERCOLATION/LEAKAGE THROUGH LAYER 3					
-----					
TOTALS	0.1293	0.1127	0.1352	0.1746	0.1872
0.1794					
	0.1858	0.1860	0.1834	0.1934	0.1885
0.1689					
STD. DEVIATIONS	0.0020	0.0008	0.0146	0.0189	0.0108
0.0106					
	0.0116	0.0109	0.0102	0.0089	0.0116
0.0186					



-----  
 -----  
 AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)  
 -----  
 -----

## DAILY AVERAGE HEAD ACROSS LAYER 3

AVERAGES	5.1932	4.4077	6.7663	17.0749	18.6035
18.1820					
	18.2789	18.3289	19.1433	20.0225	20.3356
14.4402					
STD. DEVIATIONS	0.1998	0.1945	3.3266	4.4558	2.4489
2.4969					
	2.6448	2.4796	2.3948	2.0169	2.7337
4.2262					

\*\*\*\*\*  
 \*\*\*\*\*

\*\*\*\*\*  
 \*\*\*\*\*

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH  
 20

PERCENT	INCHES	CU. FEET
-----	-----	-----
PRECIPITATION	32.89 ( 5.107)	119401.6
100.00		
RUNOFF	5.927 ( 3.3374)	21514.00
18.018		
EVAPOTRANSPIRATION	24.860 ( 2.7618)	90242.34
75.579		
PERCOLATION/LEAKAGE THROUGH	2.02439 ( 0.08031)	7348.538
6.15447		
FROM LAYER 3		
AVERAGE HEAD ACROSS TOP	15.065 ( 1.553)	
OF LAYER 3		

C2run2.out

CHANGE IN WATER STORAGE            0.082    ( 1.4040)            296.74  
0.249

\*\*\*\*\*  
\*\*\*\*\*

✓  
\*\*\*\*\*  
\*\*\*\*\*

PEAK DAILY VALUES FOR YEARS		1 THROUGH	20
		(INCHES)	(CU. FT
00	PRECIPITATION	4.09	14846.7
545	RUNOFF	2.822	10242.8
9493	PERCOLATION/LEAKAGE THROUGH LAYER 3	0.006803	24.6
	AVERAGE HEAD ACROSS LAYER 3	24.000	
090	SNOW WATER	4.36	15834.7
	MAXIMUM VEG. SOIL WATER (VOL/VOL)		0.4110
	MINIMUM VEG. SOIL WATER (VOL/VOL)		0.1385

\*\*\*\*\*  
\*\*\*\*\*

✓  
\*\*\*\*\*  
\*\*\*\*\*

FINAL WATER STORAGE AT END OF YEAR    20

C2run2.out

-----

LAYER	(INCHES)	(VOL/VOL)
-----	-----	-----
1	2.6191	0.4365
2	7.1639	0.3980
3	10.2480	0.4270
SNOW WATER	0.000	

\*\*\*\*\*  
 \*\*\*\*\*  
 \*\*\*\*\*  
 \*\*\*\*\*

\*\*\*\*\*

TITLE: HOD landfill cap c3

\*\*\*\*\*  
\*\*\*\*\*

E NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WER  
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1  
-----TYPE 1 - VERTICAL PERCOLATION LAYER  
MATERIAL TEXTURE NUMBER 4

THICKNESS	=	6.00	INCHES
POROSITY	=	0.4370	VOL/VOL
FIELD CAPACITY	=	0.1050	VOL/VOL
WILTING POINT	=	0.0470	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.2316	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.170000002000E-02	CM/SEC

LAYER 2  
-----TYPE 1 - VERTICAL PERCOLATION LAYER  
MATERIAL TEXTURE NUMBER 10

THICKNESS	=	30.00	INCHES
POROSITY	=	0.3980	VOL/VOL
FIELD CAPACITY	=	0.2440	VOL/VOL
WILTING POINT	=	0.1360	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.3250	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.119999997000E-03	CM/SEC

LAYER 3  
-----TYPE 3 - BARRIER SOIL LINER  
MATERIAL TEXTURE NUMBER 16

C3r2.out

THICKNESS	=	36.00	INCHES
POROSITY	=	0.4270	VOL/VOL
FIELD CAPACITY	=	0.4180	VOL/VOL
WILTING POINT	=	0.3670	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4270	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.100000001000E-06	CM/SEC

#### GENERAL DESIGN AND EVAPORATIVE ZONE DATA

-----

NOTE: SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED.

SCS RUNOFF CURVE NUMBER	=	70.00	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	1.000	ACRES
EVAPORATIVE ZONE DEPTH	=	18.0	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	4.726	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	7.398	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	1.914	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	26.512	INCHES
TOTAL INITIAL WATER	=	26.512	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

#### EVAPOTRANSPIRATION AND WEATHER DATA

-----

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM  
chicago IL

MAXIMUM LEAF AREA INDEX	=	0.00
START OF GROWING SEASON (JULIAN DATE)	=	117
END OF GROWING SEASON (JULIAN DATE)	=	290
AVERAGE ANNUAL WIND SPEED	=	10.30 MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	71.00 %
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	65.00 %
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	70.00 %
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	72.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR CHICAGO ILLINOIS

C3r2.out

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/
DEC	-----	-----	-----	-----	-----	----
---						
	1.60	1.31	2.59	3.66	3.15	4.
08						
	3.63	3.53	3.35	2.28	2.06	2.
10						

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR CHICAGO ILLINOIS

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/
DEC	-----	-----	-----	-----	-----	----
---						
	21.40	26.00	36.00	48.80	59.10	68.
60						
	73.00	71.90	64.70	53.50	39.80	27.
70						

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USIN  
COEFFICIENTS FOR CHICAGO ILLINOIS

STATION LATITUDE = 41.78 DEGREES

\*\*\*\*\*  
\*\*\*\*\*

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 20

JAN/JUL FEB/AUG MAR/SEP APR/OCT MAY/NOV

JUN/DEC	C3r2.out				
-----	-----	-----	-----	-----	-----
PRECIPITATION					
TOTALS	1.56	1.42	2.51	3.11	3.62
3.94	3.78	2.92	3.50	2.24	2.23
2.08					
STD. DEVIATIONS	0.64	0.65	1.40	1.67	1.86
2.09	1.75	1.72	1.68	1.27	1.02
1.00					
RUNOFF					
TOTALS	0.616	0.861	1.207	0.258	0.305
0.325	0.298	0.300	0.408	0.221	0.377
0.517					
STD. DEVIATIONS	0.719	0.752	1.120	0.431	0.764
0.977	0.678	0.605	0.722	0.428	0.687
0.563					
EVAPOTRANSPIRATION					
TOTALS	0.688	0.872	1.945	2.678	3.168
3.281	3.233	2.592	2.441	1.881	1.282
0.818					
STD. DEVIATIONS	0.147	0.236	0.344	0.888	1.183
1.034	1.183	1.262	0.878	0.623	0.282
0.161					
PERCOLATION/LEAKAGE THROUGH LAYER 3					
TOTALS	0.1559	0.1372	0.1581	0.1810	0.1925
0.1855	0.1919	0.1919	0.1880	0.1972	0.1924
0.1818					
STD. DEVIATIONS	0.0039	0.0026	0.0107	0.0166	0.0123
0.0109	0.0120	0.0123	0.0116	0.0107	0.0106
0.0131					

-----  
 -----  
 AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)  
 -----  
 -----

## DAILY AVERAGE HEAD ACROSS LAYER 3

	16.8087	15.8572	17.9861	27.8478	29.7062
AVERAGES					
29.4391					
26.0562	29.5265	29.5081	30.3286	31.3360	31.8890
STD. DEVIATIONS	1.0045	0.9855	3.6540	5.8712	4.2154
3.8389	4.0928	4.1896	4.1097	3.6650	3.7384
4.4658					

\*\*\*\*\*  
 \*\*\*\*\*

\*\*\*\*\*  
 \*\*\*\*\*

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH  
 20

PERCENT	INCHES	CU. FEET
PRECIPITATION	32.89 ( 5.107)	119401.6
100.00		
RUNOFF	5.691 ( 3.3116)	20657.33
17.301		
EVAPOTRANSPIRATION	24.878 ( 2.7540)	90306.59
75.633		
PERCOLATION/LEAKAGE THROUGH	2.15346 ( 0.10213)	7817.062
6.54687		
FROM LAYER 3		
AVERAGE HEAD ACROSS TOP	26.357 ( 2.955)	
OF LAYER 3		



C3r2.out

CHANGE IN WATER STORAGE            0.171    ( 1.5566)            620.63  
0.520

\*\*\*\*\*  
\*\*\*\*\*

\*\*\*\*\*  
\*\*\*\*\*

PEAK DAILY VALUES FOR YEARS            1 THROUGH            20

		(INCHES)	(CU. FT
		-----	-----
00	PRECIPITATION	4.09	14846.7
225	RUNOFF	2.817	10227.5
9497	PERCOLATION/LEAKAGE THROUGH LAYER 3	0.006803	24.6
	AVERAGE HEAD ACROSS LAYER 3	36.000	
090	SNOW WATER	4.36	15834.7
	MAXIMUM VEG. SOIL WATER (VOL/VOL)		0.4110
	MINIMUM VEG. SOIL WATER (VOL/VOL)		0.1385

\*\*\*\*\*  
\*\*\*\*\*

\*\*\*\*\*  
\*\*\*\*\*

FINAL WATER STORAGE AT END OF YEAR            20

C3r2.out

-----

LAYER	(INCHES)	(VOL/VOL)
-----	-----	-----
1	2.6192	0.4365
2	11.9399	0.3980
3	15.3720	0.4270
SNOW WATER	0.000	

\*\*\*\*\*  
 \*\*\*\*\*  
 \*\*\*\*\*  
 \*\*\*\*\*

D



## APPENDIX D: COST ESTIMATES

### **SHEET**

#### **7% Discount Rate**

Sheet 1	No Further Action Cost Summary
Sheet 2	No Further Action Cost Backup
Sheet 3	Capping Costs - Summary
Sheet 4	Capping Costs - C1 Backup
Sheet 5	Capping Costs - C2 Backup
Sheet 6	Capping Costs - C3 Backup
Sheet 7	Gas Extraction/Treatment - Cost Summary
Sheet 8	Gas Extraction/Treatment - Cost Backup
Sheet 9	Gas Extraction/Treatment - G3 Cost Backup
Sheet 10	Leachate Extraction - Cost Summary
Sheets 11 and 12	Leachate Extraction - Cost Backup
Sheet 13	Leachate Extraction - LC4 Cost Backup
Sheet 14	Leachate Treatment - Alternative Assumptions
Sheet 15	Leachate Treatment - Cost Summary
Sheet 16	Leachate Treatment - LT1 Cost Backup
Sheets 17 and 18	Leachate Treatment - Volume Extraction for LT2, LT3
Sheets 19 through 24	Leachate Treatment - LT2 Cost Backup
Sheets 25 through 27	Leachate Treatment - LT3 Cost Backup
Sheet 28	Groundwater Monitoring - GW1 and GW2 Cost Summary, Backup
Sheet 29	Groundwater Monitoring - Costs for Abandoning/Replacing VW4

### **DESCRIPTION**

### **SHEET**

#### **3% Discount Rate**

Sheet 30	No Further Action Cost Summary
Sheet 31	No Further Action Cost Backup
Sheet 32	Capping Costs - Summary
Sheet 33	Capping Costs - C1 Backup
Sheet 34	Capping Costs - C2 Backup
Sheet 35	Capping Costs - C3 Backup
Sheet 36	Gas Extraction/Treatment - Cost Summary
Sheet 37	Gas Extraction/Treatment - Cost Backup
Sheet 38	Gas Extraction/Treatment - G3 Cost Backup
Sheet 39	Leachate Extraction - Cost Summary
Sheets 40 and 41	Leachate Extraction - Cost Backup
Sheet 42	Leachate Extraction - LC4 Cost Backup
Sheet 43	Leachate Treatment - Alternative Assumptions
Sheet 44	Leachate Treatment - Cost Summary
Sheet 45	Leachate Treatment - LT1 Cost Backup
Sheets 46 and 47	Leachate Treatment - Volume Extraction for LT2, LT3
Sheets 48 through 53	Leachate Treatment - LT2 Cost Backup
Sheets 54 through 56	Leachate Treatment - LT3 Cost Backup
Sheet 57	Groundwater Monitoring - GW1 and GW2 Cost Summary, Backup
Sheet 58	Groundwater Monitoring - Costs for Abandoning/Replacing VW4

### **DESCRIPTION**

## No Further Action

Objective: Determine capital and O&M costs for No Further Action alternative

### Cost Summary:

NFA	Capital		\$0
	Annual O&M	\$154,860	
	Present Worth O&M (7%, 30 Years)	12.41	<u>\$1,921,670</u>
	Total Cost		\$1,921,670

## No Further Action - Cost Backup

### O&M Costs Associated with the Existing Cap

Fence repairs and lock replacement - assume \$2,500 per year	\$2,500
Sign repairs/replacement - assume \$300 per year	\$300
Mowing - twice per year at \$30 per acre	\$3,060
Inspection of cover and swales - quarterly @ 8hr * \$50/hr	\$1,600
Cleaning of drainage features - quarterly @ 32hr * \$50/hr	\$6,400
Rework of cover soils (assume 5%/yr needs rework to a depth of 2 ft @ \$3.50/cu.yd.)	\$28,800
Engineering Oversight/Coordination - assume 15% of total O&M	\$6,400
ANNUAL TOTAL:	\$49,060

### O&M Costs Associated with Gas Collection & Treatment

Assume \$35,000 per year, which is typical for similar systems

ANNUAL TOTAL: \$ 35,000

### O&M Costs Associated with Leachate Extraction

Assume the same O&M cost as that presented under Alternative LC1

ANNUAL TOTAL: \$ 4,000

### O&M Costs Associated with Leachate Treatment

Assume the same O&M cost as that presented under Alternative LT1

ANNUAL TOTAL: \$ 66,800

Combined annual O&M cost = \$49,060 + \$35,000 + \$4,000 + \$66,800 =

**\$154,860**

## CAPPING COSTS - SUMMARY

Objective: Determine capital and O&M costs for capping alternatives.

### Alternatives:

- C1 - repair and maintain existing 807 cover over entire landfill
- C2 - 807 cover over entire landfill
- C3 - 811 cover over entire landfill (with supplemental clay and replacement clay options)

### Cost Summary:

C1	Capital Costs		\$	1,370,000
	Annual O&M:	\$ 72,000		
	Present Worth (7%, 30 years)	12.41	\$	900,000
	TOTAL:		\$	2,270,000
C2	Capital Costs		\$	4,720,000
	Pre-design investigation		\$	140,800
	Annual O&M:	\$ 72,000		
	Present Worth (7%, 30 years)	12.41	\$	900,000
	TOTAL:		\$	5,761,000
C3	Supplemental Clay Option Capital Costs		\$	6,603,500
	Replacement Clay Option Capital Costs		\$	8,783,500
	Annual O&M:	\$ 72,000		
	Present Worth O&M (same as C2)		\$	900,000
	TOTAL (using supplemental clay):		\$	7,503,500
	TOTAL (using replacement clay):		\$	9,683,500

## CAPPING COSTS

### C1 Capital Costs:

*Assume under this alternative that the existing cover soils will be regraded and that new vegetation will be established.*

Mobilization/Demobilization		\$15,000
Site Safety Plan		\$12,500
Clear/Grub (strip and stockpile topsoil)	(assume 40% of 51 acres @ \$1,500/acre)	\$30,600
Purchase & install existing well/piezometer protection	(assume \$500 per well * 75 wells)	\$37,500
Stripping/stockpiling existing soil in low areas (40 % of New LF area, 2' deep)	(34,600 CY * \$5 per yd <sup>3</sup> )	\$173,000
Place compacted clay in low area (40% of New LF area, 4' deep)	(69,200 CY * \$7 per yd <sup>3</sup> )	\$484,400
Regrade stockpiled soil (40% of New LF area, 2' deep)	(34,600 CY * \$5 per yd <sup>3</sup> )	\$173,000
Establish vegetation	(assume 40% of 51 acres @ \$1,500/acre)	\$30,600
Installation of temporary fencing, riprap, temporary access roads, etc.		\$100,000
Construction Completion Report		\$25,000
Engineering (10% of capital costs)		\$109,000
Estimating Contingency (material delays, weather, etc., assume 15% of total capital)		\$179,000

TOTAL: \$1,370,000

### C1 O&M Costs:

Fence repairs and lock replacement - assume \$2,500 per year		\$2,500
Sign repairs/replacement - assume \$300 per year		\$300
Mowing - twice per year @ \$30/acre		\$3,060
Inspection of cover and swales	quarterly @ 8/hr * \$50/hour	\$1,600
Cleaning of drainage features	quarterly @ 32/hr * \$50/hour	\$6,400
Rework of cover soils		\$48,400
	(assume 5%/year needs rework, 3 acres/year @ \$5 per yd <sup>3</sup> at 2' depth)	
Engineering Oversight/Coordination - assume 15% of total O&M)		\$9,400

TOTAL O&M/YR: \$72,000



## CAPPING COSTS

### C2 Capital Costs:

Mobilization/Demobilization		\$	50,000
Site Safety Plan		\$	12,500
Clear/Grub (strip and stockpile topsoil)	51 acres @ \$1,500/acre	\$	76,500
Purchase & install existing well/piezometer protection	\$500/well * 75 wells	\$	37,500
Regrading (working 2' soils)	164,560 cu.yd. * \$5/cubic yard	\$	822,800
Place/compact 2' soils	51 acres @ 2' * \$7/cubic yard	\$	1,151,920
Grading 2' cover soils	164,560 cubic yards * \$5/cu.yd.	\$	822,800
Establish vegetation	51 acres @ \$1,500/acre	\$	76,500
Installation of temporary fencing, riprap, temporary access roads, etc.		\$	205,000
Clay testing and documentation (6% of capital costs)		\$	200,000
Construction Completion Report		\$	25,000
Implementation of drainage systems, erosion controls (8% of capital costs)		\$	300,000
Engineering (10% of capital costs)		\$	379,000
Estimating Contingency (material delays, weather, etc., assume 15% of total capital)		\$	560,000
TOTAL:			<u>\$ 4,720,000</u>

### C2 Pre-Design Investigation

Wetlands pre-construction delineation & marking		\$	75,000
Geotech. borings: 4 per A*51A* 1d/30 borings*\$2,500/d+\$100/ana*204 ana+\$10,000 oversgt		\$	47,400
Estimating Contingency (weather, etc., assume 15% of total capital)		\$	18,360
TOTAL:			<u>\$ 140,800</u>

TOTAL CAPITAL:

\$ 4,861,000

Note: A = Acre, d = day, ana = analysis, oversgt = oversight

### C2 O&M

Fence repairs and lock replacement - assume \$2,500 per year		\$	2,500
Sign repairs/replacement - assume \$300 per year		\$	300
Mowing - twice per year @ \$30/acre		\$	3,060
Inspection of cover and swales	quarterly @ 8/hr * \$50/hour	\$	1,600
Cleaning of drainage features	quarterly @ 32/hr * \$50/hour	\$	6,400
Rework of cover soils		\$	48,400
(assume 5%/year needs rework, 3 acres/year @ \$5/yd3 assume 2' depth)			
Engineering Oversight/Coordination - assume 15% of total O&M)		\$	9,400

TOTAL O&M/YR:

\$ 72,000

## CAPPING COSTS

### C3 Capital Costs

Low Range Estimate: Assumes enough existing clay from the site is recoverable to construct 811 cap with some off-site clay supplementation.

(Refer to attached calculations.)

Same capital cost as C2 with the following additional costs:	\$ 4,861,000
Purchase, transport, place, compact 105,000 cu.yd of clay @ \$12/yd3	\$ 1,260,000
Borrow Study (assume 10% of place, compact price)	\$ 73,500
Additional mob/demob costs, attributable to moving materials from off-site	\$ 250,000
Estimating Contingency (material delays, weather, etc., assume 15% of add. capital)	\$ 159,000

TOTAL CAPITAL, LOW RANGE ESTIMATE: **\$ 6,603,500**

High Range Estimate: Assumes all 250,000 cu.yd. of new clay must be brought in from an off-site source.

Same capital cost as C2 with the following additional costs:	\$ 4,861,000
Purchase, transport, place, compact 250,000 cu.yd of clay @ \$12/yd3	\$ 3,000,000
2X additional mob/demob costs, attributable to moving materials from off-site (2 seasons)	\$ 500,000
Borrow Study (assume same as low range cost estimate)	\$ 73,500
Estimating Contingency (material delays, weather, etc., assume 15% of add. capital)	\$ 349,000

TOTAL CAPITAL, HIGH RANGE ESTIMATE: **\$ 8,783,500**

### C3 O&M

Same as C2:

TOTAL O&M/YR: **\$ 72,000**

## Gas Alternatives

Objective: Determine capital and O&M costs for gas extraction/treatment alternatives

### Alternatives:

G1 - No Action, utilize existing system

G2 - Combination of existing and new systems:

- \* Use existing stick flares without any upgrades

- \* Construct a new active system for the Old Landfill consisting of 5 new wells (in addition to the existing piezometers/vents) piping, blower/flare

G3 - Enhanced extraction system:

- \* Convert 14 existing stick flares to wells and use 14 existing leachate/gas wells

- \* Construct 6 new wells

- \* Construct header piping, driplegs, condensate piping, blower, and flare

### Cost Summary:

G1	Capital		\$231,000
	Annual O&M	\$35,000	
	Present Worth O&M		<u>\$434,400</u>
	Total Cost		\$665,400
G2	Capital		\$701,100
	Annual O&M	\$35,000	
	Present Worth O&M		<u>\$434,400</u>
	Total Cost		\$1,135,500
G3	Capital		\$924,000
	Annual O&M	\$35,000	
	Present Worth O&M		<u>\$434,400</u>
	Total Cost		\$1,358,400

## Gas Alternatives - Cost Backup

### G1 - No Action

#### Capital Costs

\* Assume 25% of the G3 capital cost for repair as needed.

#### O&M Costs

\* Assume \$35,000/yr, which is typical for similar systems.

Use a 30 yr timeframe to calculate present worth for O&M:

$$\$35,000 * 12.41(7\%, 30 \text{ yrs}) =$$

\$ 4,000

\$434,400

### G2 - Combination of existing and new systems

#### Capital Costs

Costs for G3 can be used except for a reduction to items as marked by "\*" on the calculation spreadsheet (which total \$445,800)

For this alternative, to remain conservative, use half of those costs:

$$\$924,000 - 0.5(\$21,000 + \$287,500 + \$17,000 + \$20,400 + \$60,000 + \$8,400 + \$31,500) =$$

\$701,100

#### O&M Costs

O&M on the active portion of the site would be approximately = \$25,000.

Maintenance on the existing gas flares may be \$10,000:

\$ 35,000

Use a 30 yr timeframe to calculate present worth for O&M:

$$\$35,000 * 12.41(7\%, 30 \text{ yrs}) =$$

\$434,400

### G3 - Enhanced extraction system

#### Capital Costs

See attached spreadsheet.

#### O&M Costs

\* Assume \$35,000/yr, which is typical for similar systems.

\$ 35,000

Use a 30 yr timeframe to calculate present worth for O&M:

$$\$35,000 * 12.41(7\%, 30 \text{ yrs}) =$$

\$434,400

\$434,400

**GAS COLLECTION SYSTEM  
H.O.D. Landfill**

**CAPITAL CONSTRUCTION COST ESTIMATE**

<b>Item</b>	<b>Type of Work</b>	<b>Estimated Quantities</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
1.	Mobilization/Demobilization	1	LS	\$50,000	\$50,000
2.	Site Safety Plan	1	LS	\$12,500	\$12,500
3.	Gas Wells*	210	LF	\$100	\$21,000
4.	Gas Pipe Trenches*	11,500	LF	\$25	\$287,500
5.	Header Riser/Cleanouts*	34	EACH	\$500	\$17,000
6.	Gas Wellheads*	34	EACH	\$600	\$20,400
7.	Knock-Out/Lift Station (KO/LS)*	3	LS	\$20,000	\$60,000
8.	Individual Control Wires (To KO/LSs)*	4,200	LF	\$2	\$8,400
9.	Condensate Pressure Conveyance Pipe*	4,200	LF	\$7.50	\$31,500
10.	Dripleg	1	EACH	\$6,000	\$6,000
11.	Condensate Holding Tank	1	LS	\$25,000	\$25,000
12.	Compressor and Control Station	1	LS	\$40,000	\$40,000
13.	Blower Station	1	LS	\$40,000	\$40,000
14.	Utility Flare Station	1	LS	\$40,000	\$40,000
15.	Clear and Grub	0.62	acres	\$1,200	\$744
16.	Access Road	3000	SY	\$5	\$15,000
17.	Chainlink Fencing	300	LF	\$10	\$3,000
18.	Electrical Service Supply	1	LS	\$15,000	\$15,000

**TOTAL Extended Capital Construction Price**

**\$694,000**

**ADDITIONAL CONSULTING SERVICES**

<b>Item</b>	<b>Type of Work</b>	<b>Estimated Quantities</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
1.	Construction Completion Report	1	LS	\$50,000	\$50,000
2.	Bid-Phase Assistance	5% of Cap. Cost	LS	\$34,700	\$34,700
3.	Construction Management	10% of Cap. Cost	LS	\$69,400	\$69,400
4.	Engineering	10% of Cap. Cost	LS	\$69,400	\$69,400

**TOTAL Additional Consulting Services Price**

**\$230,000**

**TOTAL Extended Price**

**\$924,000**

\* Refer to backup calculations. The costs for these items are lower for Alternative G2.

## Leachate Extraction

Objective: Determine capital and O&M costs for alternatives for leachate extraction

### Alternatives:

- LC1 - No action, utilize existing manholes/piping
- LC2 - Existing wells plus new collection piping
- LC3 - Combination, New LF = Alt. LC2, Old LF = Alt. LC3
- LC4 - Dual extraction

### Cost Summary:

LC1	Capital Costs		\$0
	Annual O&M	\$ 4,000	
	Present Worth O&M		\$ 49,700
	Total		\$49,700
LC2	Capital Costs		\$ 232,300
	Annual O&M	\$ 60,000	
	Present Worth O&M		\$ 744,600
	Total		\$ 976,900
LC3	Capital Costs		\$ 367,800
	Annual O&M	\$ 72,000	
	Present Worth O&M		\$ 893,500
	Total		\$ 1,261,300
LC4	Capital Costs		\$ 439,000
	Annual O&M	\$ 60,000	
	Present Worth O&M		\$ 744,600
	Total		\$ 1,183,600

## Leachate Extraction

### LC1 - No action

#### Capital Costs

Assume negligible capital cost, \$0

#### O&M Costs

\*Assume 4 times per year check manhole/pipes, clean pipes annually  
\$2,000 for cleaning & 32 hours @ \$60/hr = \$ 4,000

Present worth cost of O&M (7%, 30 yrs) = \$ 49,700

### LC2 - Existing wells plus new collection piping

#### Capital Costs

Assume capping work will occur concurrently so removal of clay to place pipe is negligible.

Addition of a 5,000 gallon storage tank is needed for temporary leachate storage = \$ 25,000

Automation of collection system, assume \$30,000 \$ 30,000

Pipe trenches, pipe, and backfill, approximately 4,200 ft of pipe @ \$35/ft = \$ 147,000

Engineering/Construction Management (15% of cap. costs) = \$ 30,300

Total \$ 232,300

#### O&M Costs

Assume \$60,000/year due to added pumping requirements. \$ 60,000

Present worth cost of O&M (7%, 30 yrs) = \$ 744,600

### LC3 - Combination, New LF = Toe drain, existing wells, Old LF = Dual extraction

#### Capital Costs

New LF: Use LC2 - 2,400' of pipe @ \$35/ft = \$ 148,300

Old LF: Use details for LC4, assume 1/2 LC4 = \$ 219,500

Total Capital Cost = \$ 367,800

#### O&M Costs

Assume, conservatively, sum of 60% of LC2 & LC4 O&M:

60% of LC2 & LC4 O&M \$ 72,000

Present worth cost of O&M (7%, 30 yrs) = \$ 893,500

#### LC4 - Dual extraction wells

##### Capital Costs

See attached spreadsheet. Total cost = \$1,363,000 for dual system; however, this is for both leachate and gas. The additional cost for leachate over and above that needed for gas is \$439,000 (Gas cost, assuming Alternative G3 is selected = \$924,000).

\$ 439,000

##### O&M Costs

Assume O&M costs of \$60,000 per year, based on previous experience.

\$ 60,000

Present worth of O&M = \$60,000 (7%, 30 yrs) =

\$ 744,600



**DUAL EXTRACTION SYSTEM  
H.O.D. LANDFILL**

**CAPITAL CONSTRUCTION COST ESTIMATE**

<b>Item</b>	<b>Type of Work</b>	<b>Estimated Quantities</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
1.	Mobilization/Demobilization	1	LS	\$50,000	\$50,000
2.	Site Safety Plan	1	LS	\$12,500	\$12,500
3.	Gas Wells	210	LF	\$100	\$21,000
4.	Gas Pipe Trenches	11,500	LF	\$25	\$287,500
5.	Leachate Gravity Conveyance Pipe	11,500	LF	\$5	\$57,500
6.	Header Riser/Cleanouts	34	EACH	\$500	\$17,000
7.	Gas/Leachate Wellheads	34	EACH	\$600	\$20,400
8.	Well Pumps w/ Transmitter /Controls	34	EACH	\$3,500	\$119,000
9.	Knock-Out/Lift Station (KO/LS)	3	LS	\$20,000	\$60,000
10.	Individual Control Wires (To KO/LSs)	4,200	LF	\$2	\$8,400
11.	Leachate Pressure Conveyance Pipe	4,200	LF	\$7.50	\$31,500
12.	Dripleg	1	EACH	\$6,000	\$6,000
13.	Condensate/Leachate Holding Tank	1	LS	\$25,000	\$25,000
14.	Compressor and Control Station	1	LS	\$40,000	\$40,000
15.	Blower Station	1	LS	\$40,000	\$40,000
16.	Utility Flare Station	1	LS	\$40,000	\$40,000
17.	Clear and Grub	0.62	acres	\$1,200	\$744
18.	Access Road	3000	SY	\$5	\$15,000
19.	Chainlink Fencing	300	LF	\$25	\$7,500
20.	Electrical Service Supply	300	LS	\$15,000	\$15,000
21.	System Automation	15% of Cap. Cost	LS	\$15,000	\$132,000

**TOTAL Extended Capital Construction Price**

**\$1,010,000**

**ADDITIONAL CONSULTING SERVICES**

<b>Item</b>	<b>Type of Work</b>	<b>Estimated Quantities</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
1.	Construction Completion Report	1	LS	\$50,000	\$50,000
2.	Bid-Phase Assistance	10% of Cap. Cost	LS	\$101,000	\$101,000
3.	Construction Management	10% of Cap. Cost	LS	\$101,000	\$101,000
4.	Engineering	10% of Cap. Cost	LS	\$101,000	\$101,000

**TOTAL Extended Capital Construction Price**

**\$353,000**

**TOTAL Extended Price**

**\$1,363,000**

BPG\bpg\TAB

J:\1252\035\03090210\Final FS 4-98\cost\_estimates\Leachate Extraction

1252035.03090210

## **Leachate Treatment Alternatives**

Objective: Identify and estimate costs of leachate management approaches.

### General Assumptions

- \* Future flow rate of 15 gpm to reach leachate maintenance level then pump  
@ 5 gpm to maintain leachate level
- \* Leachate quality will correspond to that identified in the RI

### LT1: No action

- \* Baseline, lowest cost option
- \* Existing cost from Waste Management

### LT2: Pretreat and discharge to POTW

- \* Primary objectives are to reduce copper and BOD levels
- \* Metals pretreatment options include chemical and physical (e.g., precipitation and clarification, ion exchange, oxidation, reverse osmosis)
- \* Assume BOD limit is based on carbonaceous demand (i.e., nitrogenous demand is inhibited, so exclude ammonia)

#### **Recommendation:**

Remove metals by lime or caustic precipitation and clarification, lower BOD by air stripping, press sludge.

#### **Key Assumptions:**

- \* Costs do not include costs associated with baseline (e.g. hauling treated water to POTW, subsequent disposal at POTW, extraction costs)

### LT3: Treatment and surface discharge

- \* Objective is to meet NPDES discharge limits
- \* Assumes appropriate discharge location exists
- \* Reverse osmosis would treat all compounds listed in Table 3-1 and is the worst case cost.

#### **Key Assumption:**

- \* Does not include baseline costs
- \* Assumes surface water source is available/acceptable.

## Leachate Treatment

Objective: Determine capital and O&M costs for treatment alternatives

Alternatives:

- LT1 - No Further Action
- LT2 - Pretreat and discharge to POTW
- LT3 - Treat and surface discharge

Cost Summary:

LT1	Capital		\$	-
	Annual O&M	\$	66,800	
	Present Worth O&M		\$	829,000
	Total Cost		\$	829,000
LT2	Capital		\$	476,000
	Annual O&M	\$	747,000	
	Present Worth O&M		\$	9,270,000
	Total Cost		\$	9,750,000
LT3	Capital		\$	1,843,000
	Annual O&M	\$	595,000	
	Present Worth O&M		\$	7,384,000
	Total Cost		\$	9,227,000

LT1 - No Action: Pump, Transport, & Dispose at Remote POTW

*Assume the total cost of pumping leachate from the existing manholes and wells is approximately equal to the present worth of transport/discharge costs for 30 years.*

*Assume that the current extraction rate is 1 gpm and that the cost for transport using a 5,000 gallon tanker truck and discharge to the POTW combined is \$0.09/gallon.*

**Annual O&M Costs:**

Annual O&M = (1 gal/min) \* (60 min/hr) \* (24 hr/day) \* (365 day/yr) \* \$0.09/gal \* 20% Contingency =  
Annual operation cost for this option is approximately: \$ 10,000

Annual O&M \$ 66,800

Calculate Present Worth of this option over 30 years

O&M P.W. (7%, 30 years) = \$829,000

**LEACHATE TREATMENT VOLUME / EXTRACTION RATE  
FOR ALTERNATIVES LT2 AND LT3.**

Leachate maintenance level (as described in RI) = 2 ft below the water level elevation contemporaneously measured in G11D.

$$\begin{aligned}\text{Average elevation of G11D (6/93 to 4/94)} &= (760.68 + 760.01 + 760.68 + 760.48 + 760.53 + 760.96) / 6 \\ &= 760.56 \text{ ft}\end{aligned}$$

* Leachate Maintenance Level = 758.57 ft
--

$$\begin{aligned}\text{Average leachate elevation (as of 4/25/94)} &= (766.7 + 769.3 + 764.53 + 772.15 + 760.82 + 779.37 + 774.72 + \\ &\quad 754.26 + 764.07 + 767.02 + 770.54 + 764.68 + 766.01 + 764.66) / 14 \\ &= 767.06 \text{ ft}\end{aligned}$$

\* Historically, leachate elevations have remained fairly constant; therefore, assume the average leachate elevation as of 4/94 is still representative. Let the amount of leachate to be removed at 30 gpm equal that necessary to achieve the "leachate maintenance level." Let any further extraction be at a rate that is high enough to account for annual infiltration. Based on HELP model results, assume 2 in/yr as a worst-case infiltration estimate. Assume refuse porosity = 0.45.

Amount of leachate to be removed at 15 gpm,  $V_{15}$   
(Before accounting for additional infiltration:)

$$V_{15} = (767.06 \text{ ft} - 758.57 \text{ ft}) \times (51 \text{ acres}) \times (43,560 \text{ sq ft/acre}) \times (7.48 \text{ gal/cu ft}) \times 0.45$$

$V_{15} = 63.5 \text{ MG}$
----------------------------

Amount of annual leachate production (assume 100% from infiltration, ignore storativity by cap and all other losses for worst case), VLP

$$V_{LP} = (2/12 \text{ ft}) \times (51 \text{ acres}) \times (43,560 \text{ sq ft/acre}) \times (7.48 \text{ gal/cu ft})$$

$V_{LP} = 2,769,545 \text{ gal}$
----------------------------------

Time to reach leachate maintenance level,  $t_{30}$  (yrs)

$$t_{30} = (63.5 \times 10^6 \text{ gal} + 2,769,545 \text{ gal/yr} \times t_{30}) \times (1 \text{ yr} / 7.884 \times 10^6 \text{ gal})$$

$$t_{30} = 8.054 + 0.351 t_{30}$$

$t_{30} = 12.4 \text{ yrs} = 12 \text{ yrs, 5 mo.}$
---

BPG\bpg\TAB

I:\1252\035\03090210\Final FS 4-98\cost\_estimates\LEACH\_TREAT  
1252035.03090210

- \* Actual volume that will be discharged up to  $t_{30}$ :

$$V_{t_{30}} = 63.5 \times 10^6 + 2,769,545 \text{ gal/yr} \times 12.4 \text{ yr}$$

$V_{t_{30}} =$	97.842 MG
----------------	-----------

- \* Extraction Rate needed after reaching leachate maintenance level,  $Q_{ML}$

$$Q_{ML} = V_{LP} = (2,628,000 \text{ gal/yr}) \times (1 \text{ yr} / 525,600 \text{ min})$$

$Q_{ML} =$	5.00 gpm
------------	----------

Will the leachate maintenance level of 756.57 ft cause dry bottoming of either the old or new landfill areas?

(Refer to attached supporting information from RI Report.)

- \* Spot check boring data from both sides of the landfill to determine bottom elevations. (Selected locations are highlighted on the attached figure.)

* Ground elevation - depth to base material = Bottom Elevation
--

OLD LF

LP2:	785.5 ft	- 40 ft	=	745.5 ft
LP3:	778.1 ft	- 28.5 ft	=	749.6 ft
LP12:	782.6 ft	- 25.5 ft	=	757.1 ft dry bot.
LP13:	779 ft	- 17 ft	=	762 ft dry bot.
LP11:	787.8 ft	- 33 ft	=	754.8 ft
LP4:	788.9 ft	- 40 ft	=	748.9 ft
B3:	773.7 ft	- 10.5 ft	=	763.2 ft dry bot.
LP2:	785.5 ft	- 40 ft	=	745.5 ft

NEW LF (deeper than OLD LF)

LP5:	796.6 ft	- 51 ft	=	745.6 ft
GW12:	792.5 ft	- 22+ ft	-->	770.5 INCONCLUSIVE
LP6:	794.6 ft	- 40 ft	=	754.6 ft
LP7:	794.7 ft	- 62 ft	=	732.7 ft
LP9:	785.5 ft	- 68.5 ft	=	717 ft

Leachate maintenance level of 756.57 ft would cause some amount of localized bottom drying near perimeter of old LF, but overall would not result in dry-bottoming of either the old or new landfills.

BPG\bpg\TAB

J:\1252\035\03090210\Final FS 4-98\cost\_estimates\LEACH\_TREAT  
1252035.03090210

TABLE 1

PROJECT: H.O.D. Leachate Management

PROJECT NO.: 1252035.031801

PRELIMINARY COST ESTIMATE

DATE: 2-Jun-98

OPTION: Pretreatment and POTW Discharge

DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
<b>I. INITIAL IMPLEMENTATION ESTIMATED COSTS</b>				
<b>A. Consulting Services</b>				
1. System Design (Drawings/Specs)	1	LS	\$10,500	\$10,500
2. Permitting (Building)	1	LS	\$1,000	\$1,000
3. Preconstruction				
a. Subcontractor procurement	1	LS	\$4,100	\$4,100
b. Construction coordination & preconstruction mtg	1	LS	\$1,200	\$1,200
c. Site safety plan	1	LS	\$12,500	\$12,500
4. Construction Oversight	15	DAYS	\$1,600	\$24,000
5. System Start-up	5	DAYS	\$875	\$4,375
6. Project Closeout				
a. O&M and long-term monitoring plan	1	LS	\$2,450	\$2,450
b. Construction documentation report	1	LS	\$4,300	\$4,300
7. Project Management/Meetings	1	LS	\$7,930	\$7,930
Subtotal				\$72,355
Estimating Contingency (15%)				\$10,900
Total Consulting Services Initial Implementation Estimated Cost				\$83,000
<b>B. Commodity Services</b>				
1. Mobilization/Demobilization	1	LS	\$50,000	\$50,000
2. Remediation Building				
a. Concrete foundation	25	CY	\$150	\$3,750
b. Building	1	EA	\$35,000	\$35,000
3. Mechanical Work				
a. Holding tank	2	EA	\$78,000	\$156,000
b. Transfer pump	2	EA	\$2,500	\$5,000
c. Lamella clarifier, mixers, sludge pumps	1	LS	\$23,000	\$23,000
d. Diffused air stripper, blower	1	EA	\$27,000	\$27,000
e. Contact tank	1	EA	\$500	\$500
f. Metering pump	3	EA	\$1,200	\$3,600
g. Filter press	1	EA	\$10,000	\$10,000
h. Sludge holding tank	1	EA	\$1,500	\$1,500
i. Piping within remediation building	1	LS	\$2,000	\$2,000
j. Gauges, valves, fittings, sample ports	1	LS	\$4,000	\$4,000
k. Exhaust fan and louver in treatment building	1	EA	\$1,000	\$1,000
4. Electrical Work				
a. Lights, switches, and outlets	1	LS	\$2,000	\$2,000
b. Controls and control panel	1	LS	\$8,000	\$8,000
c. Electric heater and thermostat	1	EA	\$1,500	\$1,500
d. Distribution panel, wiring, and conduit	1	LS	\$3,000	\$3,000
e. Electric meter and utility service to building	1	LS	\$5,000	\$5,000
Subtotal				\$341,850
Estimating Contingency (15%)				\$51,278
Total Commodity Services Initial Implementation Estimated Cost				\$393,000
<b>TOTAL INITIAL IMPLEMENTATION ESTIMATED COST</b>				<b>\$476,000</b>

BPG\bpg\TAB

J:\1252\035\03090210\Final FS 4-98\cost\_estimates\Leachate Treatment

1252035.03090210

**TABLE 1 (cont.)**

DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
<b>II. ANNUAL O&amp;M ESTIMATED COSTS</b>				
<b>A. Consulting Services</b>				
1. Operation Labor	416	HRS	\$60	\$24,960
2. Maintenance Labor	96	HRS	\$60	\$5,760
3. Maintenance Materials	1	LS	\$12,655	\$12,655
4. Effluent monitoring	12	HRS	\$60	\$720
5. Reporting to POTW	4	RPT	\$900	\$3,600
6. Project Management/Meetings	1	LS	\$6,200	\$6,200
Subtotal				\$53,895
Estimating Contingency (15%)				\$8,100
Total Consulting Services Annual O&M Estimated Cost				\$62,000
<b>B. Commodity Services</b>				
1. Electrical Power	55,550	Kw-Hrs	\$0.08	\$4,444
2. Effluent Monitoring Laboratory Analyses	12	EA	\$250	\$3,000
3. Caustic, polymer, and sulfuric	1	LS	\$5,000	\$5,000
4. Sludge Disposal	*	gal	\$0.40	\$39,100
5. Discharge to POTW	*	gal	\$0.09	\$544,000
Subtotal				\$595,544
Estimating Contingency (15%)				\$89,332
Total Commodity Services Annual O&M Estimated Cost				\$685,000
<b>TOTAL ANNUAL O&amp;M ESTIMATED COST</b>				<b>\$747,000</b>

**General Notes:**

1. Initial implementation and annual O&M estimated costs shown are approximate and for comparison only.
  2. Operation labor is based on an average of 8 hours of operating labor required every week.
  3. Maintenance labor is based on an average of 8 hours of maintenance labor required every month.
  4. Maintenance materials estimate is based on 5% of the electrical and mechanical equipment initial implementation costs
  5. Electrical power usage is based on one 5 hp blower and two 0.5 hp transfer pumps operating continuously and miscellaneous electrical equipment - lights, heat, etc.
- \* Refer to backup calculations. Sludge disposal and discharge amounts decrease significantly after the first five years of operation.



## LT2 - Pretreat and discharge to POTW: Cost Backup Calculations

### **I. Implementation**

#### A. Consulting

##### 1. Design

80 hrs * \$74/hr =	\$	5,920
12 hrs * \$92/hr =	\$	1,104
24 hrs * \$78/hr =	\$	1,872
4 hrs * \$106/hr =	\$	424
24 hrs * \$44/hr =	\$	1,056
	\$	<u>10,376</u>

##### 2. Building Permit

8 hrs * \$74/hr =	\$	592
2 hrs * \$92/hr =	\$	184
1 hr * \$106/hr =	\$	106
2 hrs * \$44/hr =	\$	88
	\$	<u>970</u>

##### 3. Preconstruction

###### a. Subcontractor Procurement

40 hrs * \$78/hr =		3,120
4 hrs * \$92/hr =		368
2 hrs * \$106/hr =		212
8 hrs * \$44/hr =		352
	\$	<u>4,052</u>

###### b. Meetings

8 hrs * \$78/hr =	\$	624
4 hrs * \$92/hr =	\$	368
4 hrs * \$44/hr =	\$	176
	\$	<u>1,168</u>

###### c. Health & Safety Plan

8 hrs * \$74/hr =	\$	592
1 hr * \$92/hr =	\$	92
4 hrs * \$44/hr =	\$	176
	\$	<u>860</u>

##### 4. Oversight - assume 15 days

15 hrs * \$78/hr =	\$	1,170
+25% office =	\$	293
+ mileage =	\$	100
	\$	<u>1,563</u>

5. Startup - assume 5 days

10 hrs * \$62/hr =	\$	620
+25% office =	\$	155
+ mileage =	\$	100
	\$	875

6. Project Closeout

a. O&M Plan

20 hrs * \$74/hr =	\$	1,480
4 hrs * \$92/hr =	\$	368
2 hrs * \$106/hr =	\$	212
8 hrs * \$44/hr =	\$	352
	\$	2,412

b. Documentation

* Same as O&M =	\$	2,412
+ 24 hrs * \$74/hr =	\$	1,776
	\$	4,188

7. Project Management

\* Assume %15 of other consulting costs

B. Commodity

1. Mobilization/Demobilization

\*Assume \$ 50,000

2. Building - assume 30' x 30'

a. Slab

30' x 30' x 3/4' = 25 cu.yd. concrete  
25 cu.yd. \* \$150/cu.yd. = \$ 3,750 (includes rebar & finish)

b. Building

\*Assume \$ 35,000

3. Mechanical

a. Holding Tank (influent & effluent)

Provide storage for 3 days @ 30 gpm = 129,600 gallons  
129,600 gallons \* \$0.6/gal for steel = \$ 77,760 each

b. Transfer Pumps - One each for influent holding tank and effluent holding tank

\*Assume \$ 2,500 each

c. Clarifier Package - includes rapid mix, floc and settling chambers, floc and flash mixers, sludge pumps and controls: \$ 23,000  
(Cost is per Graver Water (page 8).)

d. Air Stripper - \$ 27,000 per past experience

e. Contact Tank - for sulfuric @ 5 min. residence time

30 gpm \* 5 min = 150 gal

\*Assume \$ 500

f. Metering Pump - one each for caustic, polymer, sulfuric.

\*Assume \$ 1,200 each

g. Filter Press

\*Assume \$ 10,000

h. Sludge Holding Tank

\*Assume 1,000 gal ~ \$ 1,500

i-k. Assumed costs

#### 4. Electrical - Assumed costs

## II. Annual O&M

### A. Consulting

1. Operating Labor - Assume 8 hrs/wk \* 52 wks = 416 hrs

2. Maintenance Labor - Assume 8 hrs/mo. \* 12 mo. = 96 hrs

3. Maintenance Materials - Assume 5% of mechanical & electrical equipment cost

4. Effluent Monitoring - Assume monthly influent & effluent sampling - 1hr labor

5. Quarterly Reporting to POTW

8 hrs \* \$74/hr = \$ 592

1 hr \* \$92/hr = \$ 92

1 hr \* \$106/hr = \$ 106

2 hr \* \$44/hr = \$ 88

\$ 878

6. Project Management

\* Assume %15 of other consulting costs

### B. Commodity

1. Electrical

Approx. 2, 0.5 hp transfer pumps, 7.5 hp air stripper blowers

8.5 hp \* 0.746 kW/hp \* 24 hr/d \* 365d/yr = 55,550 kW-hr

2. Analytical

\* Assume monthly BOD and metals @ \$250/round

3. Caustic, polymer, sulfuric - assume \$5,000/yr.

4. Sludge Disposal - Assume sludge equals 2% of annual

volume treated, 157,700gal \* \$0.40/gal,

for each of first 12 years

\$63,080

for each year after 12th

\$22,156

Present worth of sludge disposal =

\$599,983

(7%, 12 yrs@15gpm, 18 yrs@5gpm)

Annualized cost of sludge disposal =

\$39,100

5. Discharge to POTW - Assume \$0.09 per gallon.

First 12 years (7,884,000 gal/yr (15 gal/min)@0.09\$/gal):

\$709,560

Each year after the 12th

(2,769,545 gal/yr (5 gal/min)@\$0.09/gal):

\$249,300

Present worth of discharge =

\$6,750,000

(7%, 12 yrs@15gpm, 18 yrs@5gpm)

Annualized cost of discharge =

\$544,000

TABLE 2

PROJECT: H.O.D. Leachate Management

PROJECT NO.: 1252035.031801

PRELIMINARY COST ESTIMATE

DATE: 2-Jun-98

OPTION: Treat and NPDES Discharge

DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
<b>I. INITIAL IMPLEMENTATION ESTIMATED COSTS</b>				
<b>A. Consulting Services</b>				
1. System Design	1	LS	\$50,000	\$50,000
2. Permitting				
a. Building	1	LS	\$5,000	\$5,000
b. NPDES	1	LS	\$21,000	\$21,000
3. Preconstruction				
a. Subcontractor procurement	1	LS	\$4,100	\$4,100
b. Construction coordination & preconstruction meeting	1	LS	\$1,200	\$1,200
c. Site safety plan	1	LS	\$12,500	\$12,500
4. Construction Oversight	15	DAYS	\$1,600	\$24,000
5. System Start-up	5	DAYS	\$875	\$4,375
6. Project Closeout				
a. O&M and long-term monitoring plan	1	LS	\$2,450	\$2,450
b. Construction documentation report	1	LS	\$4,300	\$4,300
7. Project Management/Meetings	1	LS	\$7,930	\$7,930
Subtotal				\$136,855
Estimating Contingency (15%)				\$20,600
Total Consulting Services Initial Implementation Estimated Cost				\$157,000
<b>B. Commodity Services</b>				
1. Mobilization/Demobilization	1	LS	\$50,000	\$50,000
2. Remediation Building Foundation	10	CY	\$150	\$1,500
3. Mechanical Work				
a. Holding tank	1	EA	\$78,000	\$78,000
b. Transfer pump	2	EA	\$2,500	\$5,000
c. Reverse osmosis package system	1	LS	\$500,000	\$500,000
d. Transfer tank	1	EA	\$500	\$500
e. Concentrate holding tank	1	EA	\$4,500	\$4,500
f. Piping to remediation building	1	LS	\$2,000	\$2,000
g. Gauges, valves, fittings, sample ports	1	LS	\$4,000	\$4,000
4. Electrical Work				
a. Controls and control panel	1	LS	\$8,000	\$8,000
b. Distribution panel, wiring, and conduit	1	LS	\$3,000	\$3,000
c. Electric meter and utility service to building	1	LS	\$5,000	\$5,000
5. Installation of 2-Mile Pipeline to Discharge Point				
Trenching	10,600	LF	\$30	\$318,000
Piping	10,600	LF	\$20	\$212,000
Costs associated w/ crossing roads, easmts. (based on installing 2 mi. of piping, permits & easements required to install pipe)	1	LS	\$275,000	\$275,000
Subtotal				\$1,466,500
Estimating Contingency (15%)				\$219,975
Total Commodity Services Initial Implementation Estimated Cost				\$1,686,000
<b>TOTAL INITIAL IMPLEMENTATION ESTIMATED COST</b>				<b>\$1,843,000</b>

TABLE 2 (cont.)

DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
<b>II. ANNUAL O&amp;M ESTIMATED COSTS</b>				
<b>A. Consulting Services</b>				
1. Operation & Maintenance Labor	1,560	HRS	\$60	\$93,600
2. Effluent monitoring	12	HRS	\$60	\$720
3. Reporting to IEPA	12	RPT	\$600	\$7,200
4. Project Management/Meetings	1	LS	\$15,228	\$15,228
Subtotal				\$116,748
Estimating Contingency (15%)				\$17,600
Total Consulting Services Annual O&M Estimated Cost				\$134,000
<b>B. Commodity Services</b>				
1. Electrical Power/Membranes/Cleaning Agents/etc.	4,876	KGal	\$50	\$243,790
2. Effluent Monitoring Laboratory Analyses	12	EA	\$800	\$9,600
3. Sludge Disposal	*	gal	\$0.40	\$39,100
4. Effluent conveyance/transport	5,400	KGal	\$20	\$108,000
Subtotal				\$400,490
Estimating Contingency (15%)				\$60,100
Total Commodity Services Annual O&M Estimated Cost				\$461,000
<b>TOTAL ANNUAL O&amp;M ESTIMATED COST</b>				<b>\$595,000</b>

**General Notes:**

1. Initial implementation and annual O&M estimated costs shown are approximate and for comparison only.
  2. Operation labor is based on an average of 8 hours of operating labor required every week.
  3. Maintenance labor is based on an average of 2 hours of maintenance labor required every week.
  4. Electrical power usage, cleaning agents, membrane replacement costs per Rochem Separation Systems.
  5. Effluent transport amount is an average value over thirty years.
- \* Sludge disposal amount varies after five years. Refer to the LT2 backup calculations for further details.

### LT3 - Treatment and surface discharge: Cost Backup Calculations

#### **I. Implementation**

##### A. Consulting

Same as LT2, except cost of system design and building permitting increase, add NPDES permit:

80 hrs * \$74/hr =	\$ 5,920
80 hrs * \$92/hr =	\$ 7,360
60 hrs * \$54/hr =	\$ 3,240
40 hrs * \$106/hr =	\$ 4,240
	<u>\$ 21,000</u>

##### B. Commodity

###### 3. Mechanical

a. Holding tank - only need one - continuous discharge.

c. Reverse Osmosis Units - \$500,000 capital per ROCHEM.

Includes enclosure, units, pretreat, controls. (page 9)

e. Concentrate holding tank - assume 5,000 gal to allow 1-tank truck disposal, ~ \$4,500

#### **II. Annual O&M**

##### A. Consulting

1. Assume 4 hrs/day for labor.

3. Reporting to IEPA - monthly discharge report.

4 hrs * \$74/hr =	\$ 296
1 hr * \$92/hr =	\$ 92
1 hr * \$106/hr =	\$ 106
2 hrs * \$44/hr =	\$ 88
	<u>\$ 600</u>

##### B. Commodity

1. Electrical/Membranes/Chemicals = \$0.05/gal - per ROCHEM.

2. Monitoring - assume VOC/SVOC/BOD/Metals

\*Assume \$800/event, monthly

3. Sludge Disposal - assume same as option 2 - \$51,400/yr

##### Effluent Conveyance and Transport

Assume \$0.02/gallon for pumping, maintenance on discharge and pipeline

BPG\bpg\TAB

J:\1252\035\03090210\Final FS 4-98\cost\_estimates\Leachate Treatment  
1252035.03090210

## Groundwater Monitoring Costs

### GW-1 - No Further Action

#### Capital Costs

Replacement of VW4 with VW7

	\$	693,900
<b>Total Capital Costs:</b>	\$	693,900

#### O&M Costs

Groundwater monitoring costs for No Further Action alternative

Quarterly; assumes current cost (\$41,500/yr) of GW sampling event, plus 50% for augmentation of existing program

\$	63,000
<b>Present Worth (7%, 30yrs) :</b>	\$ 781,800

**TOTAL:** \$ 1,475,700

### GW-2 - Monitored Natural Attenuation

#### Capital Costs

Replacement of VW4 with VW7

\$ 693,900

Pre-Design Investigation Monitoring Wells

Well Inst., 2 double cased wells\*85 ft.\*\$125/ft =

\$ 21,250

Field Oversight, 10 days\*10hr/day\*\$92/hr =

\$ 9,200

Contract Mgt./Admin., 10 hrs \* 92/hr =

\$ 920

**Total Capital Costs:** \$ 725,300

#### O&M Costs

Quarterly Sampling: Assume sampling of 20 wells

Labor, 20 wells\*(1d/8 wells)\*(8hr/d)\*(\$62/hr\*2)\*4/yr = \$

9,920

Travel Expenses, (5d \* \$40/d + \$40)\*4/yr = \$

960

Equipment/Supplies, assume 4\*\$700 = \$

2,800

Laboratory Analysis of Samples: Assume \$550/well

\$550/well \* 20 wells \* 4/yr = \$

44,000

Quarterly Reporting

Data Prep, (\$62/hr \* 8hrs)\*4 = \$

1,984

CAD/Admin, (\$44/hr \* 8hrs)\*4 = \$

1,408

Report Writing/Data Interpretation (\$74/hr \* 24)\*4 = \$

7,104

QA/QC (\$92/hr \* 4hrs) \*4 = \$

1,472

**Total Annual Cost** \$ 69,700

**Present Worth (7%, 30yrs) :** \$ 865,000

**TOTAL:** \$ 1,590,300



## Costs incurred to abandon and replace VW4

### Well Abandonment Cost

Engineering/Consulting ( $\$74/\text{hr} * 40\text{hrs} + \$92/\text{hr} * 20\text{hrs}$ )=	\$	4,800
CAD/Administrative Support ( $\$54/\text{hr} * 20\text{h} + \$44/\text{hr} * 20\text{h}$ ) =	\$	1,960
Bid-phase costs (Assume \$7,500)	\$	7,500
Mobilization/Demobilization/Labor ( $\$2,500 + \$50/\text{hr} * 2 * 50$ ) =	\$	7,500
Misc. material/subconsulting costs (Assume \$10,000)=	\$	10,000
Letter Report/Agency Communication ( $\$74/\text{hr} * 20\text{hr} +$		
$\$92/\text{hr} * 10\text{ hr}$ )=	\$	2,400

Assume a 15% contingency factor : \$ 5,200

**SUBTOTAL:** \$ 39,400

### Well Replacement Cost

*See attached cost information.*

Property purchase	\$	7,040
Well replacement	\$	76,012
Additional field investigation assistance	\$	1,355
Well production	\$	77,963
Well hook-up (includes capital & commodity charges)	\$	490,356

**SUBTOTAL:** \$ 652,800

**TOTAL:** \$ 693,900

## No Further Action

Objective: Determine capital and O&M costs for No Further Action alternative

### Cost Summary:

NFA	Capital		\$0
	Annual O&M	\$154,860	
	Present Worth O&M (3%, 30 Years)	19.60	\$3,036,000
	Total Cost		\$3,036,000

## No Further Action - Cost Backup

### O&M Costs Associated with the Existing Cap

Fence repairs and lock replacement - assume \$2,500 per year	\$2,500
Sign repairs/replacement - assume \$300 per year	\$300
Mowing - twice per year at \$30 per acre	\$3,060
Inspection of cover and swales - quarterly @ 8hr * \$50/hr	\$1,600
Cleaning of drainage features - quarterly @ 32hr * \$50/hr	\$6,400
Rework of cover soils (assume 5%/yr needs rework to a depth of 2 ft @ \$3.50/cu.yd.)	\$28,800
Engineering Oversight/Coordination - assume 15% of total O&M	\$6,400
ANNUAL TOTAL:	\$49,060

### O&M Costs Associated with Gas Collection & Treatment

Assume \$35,000 per year, which is typical for similar systems

ANNUAL TOTAL: \$ 35,000

### O&M Costs Associated with Leachate Extraction

Assume the same O&M cost as that presented under Alternative LC1

ANNUAL TOTAL: \$ 4,000

### O&M Costs Associated with Leachate Treatment

Assume the same O&M cost as that presented under Alternative LT1

ANNUAL TOTAL: \$ 66,800

Combined annual O&M cost = \$49,060 + \$35,000 + \$4,000 + \$66,800 =

**\$154,860**

## CAPPING COSTS - SUMMARY

Objective: Determine capital and O&M costs for capping alternatives.

### Alternatives:

- C1 - repair and maintain existing 807 cover over entire landfill
- C2 - 807 cover over entire landfill
- C3 - 811 cover over entire landfill (with supplemental clay and replacement clay options)

### Cost Summary:

C1	Capital Costs		\$	1,370,000
	Annual O&M:	\$ 72,000		
	Present Worth (3%, 30 years)	19.6	\$	1,412,000
	TOTAL:		\$	2,782,000
C2	Capital Costs		\$	4,720,000
	Pre-design investigation		\$	140,800
	Annual O&M:	\$ 72,000		
	Present Worth (3%, 30 years)	19.6	\$	1,412,000
	TOTAL:		\$	6,273,000
C3	Supplemental Clay Option Capital Costs		\$	6,603,500
	Replacement Clay Option Capital Costs		\$	8,783,500
	Annual O&M:	\$ 72,000		
	Present Worth O&M (same as C2)		\$	1,412,000
	TOTAL (using supplemental clay):		\$	8,015,500
	TOTAL (using replacement clay):		\$	10,195,500

## CAPPING COSTS

### C1 Capital Costs:

*Assume under this alternative that the existing cover soils will be regraded and that new vegetation will be established.*

Mobilization/Demobilization		\$15,000
Site Safety Plan		\$12,500
Clear/Grub (strip and stockpile topsoil)	(assume 40% of 51 acres @ \$1,500/acre)	\$30,600
Purchase & install existing well/piezometer protection	(assume \$500 per well * 75 wells)	\$37,500
Stripping/stockpiling existing soil in low areas (40 % of New LF area, 2' deep)	(34,600 CY * \$5 per yd <sup>3</sup> )	\$173,000
Place compacted clay in low area (40% of New LF area, 4' deep)	(69,200 CY * \$7 per yd <sup>3</sup> )	\$484,400
Regrade stockpiled soil (40% of New LF area, 2' deep)	(34,600 CY * \$5 per yd <sup>3</sup> )	\$173,000
Establish vegetation	(assume 40% of 51 acres @ \$1,500/acre)	\$30,600
Installation of temporary fencing, riprap, temporary access roads, etc.		\$100,000
Construction Completion Report		\$25,000
Engineering (10% of capital costs)		\$109,000
Estimating Contingency (material delays, weather, etc., assume 15% of total capital)		\$179,000

TOTAL: \$1,370,000

### C1 O&M Costs:

Fence repairs and lock replacement - assume \$2,500 per year		\$2,500
Sign repairs/replacement - assume \$300 per year		\$300
Mowing - twice per year @ \$30/acre		\$3,060
Inspection of cover and swales	quarterly @ 8/hr * \$50/hour	\$1,600
Cleaning of drainage features	quarterly @ 32/hr * \$50/hour	\$6,400
Rework of cover soils		\$48,400
(assume 5%/year needs rework, 3 acres/year @ \$5 per yd <sup>3</sup> at 2' depth)		
Engineering Oversight/Coordination - assume 15% of total O&M)		\$9,400

TOTAL O&M/YR: \$72,000

## CAPPING COSTS

### C2 Capital Costs:

Mobilization/Demobilization		\$	50,000
Site Safety Plan		\$	12,500
Clear/Grub (strip and stockpile topsoil)	51 acres @ \$1,500/acre	\$	76,500
Purchase & install existing well/piezometer protection	\$500/well * 75 wells	\$	37,500
Regrading (working 2' soils)	164,560 cu.yd. * \$5/cubic yard	\$	822,800
Place/compact 2' soils	51 acres @ 2' * \$7/cubic yard	\$	1,151,920
Grading 2' cover soils	164,560 cubic yards * \$5/cu.yd.	\$	822,800
Establish vegetation	51 acres @ \$1,500/acre	\$	76,500
Installation of temporary fencing, riprap, temporary access roads, etc.		\$	205,000
Clay testing and documentation (6% of capital costs)		\$	200,000
Construction Completion Report		\$	25,000
Implementation of drainage systems, erosion controls (8% of capital costs)		\$	300,000
Engineering (10% of capital costs)		\$	379,000
Estimating Contingency (material delays, weather, etc., assume 15% of total capital)		\$	560,000
TOTAL:			\$ 4,720,000

### C2 Pre-Design Investigation

Wetlands pre-construction delineation & marking		\$	75,000
Geotech. borings: 4 per A*51A* 1d/30 borings*\$2,500/d+\$100/ana*204 ana+\$10,000 oversgt		\$	47,400
Estimating Contingency (weather, etc., assume 15% of total capital)		\$	18,360
TOTAL:			\$ 140,800

TOTAL CAPITAL: \$ 4,861,000

Note: A = Acre, d = day, ana = analysis, oversgt = oversight

### C2 O&M

Fence repairs and lock replacement - assume \$2,500 per year		\$	2,500
Sign repairs/replacement - assume \$300 per year		\$	300
Mowing - twice per year @ \$30/acre		\$	3,060
Inspection of cover and swales	quarterly @ 8/hr * \$50/hour	\$	1,600
Cleaning of drainage features	quarterly @ 32/hr * \$50/hour	\$	6,400
Rework of cover soils		\$	48,400
(assume 5%/year needs rework, 3 acres/year @ \$5/yd3 assume 2' depth)			
Engineering Oversight/Coordination - assume 15% of total O&M)		\$	9,400

TOTAL O&M/YR: \$ 72,000

BPG/TAB/JAN

j:\1252\035\03090210\Final FS 4-98\cost\_email w\_3%

## CAPPING COSTS

### C3 Capital Costs

Low Range Estimate: Assumes enough existing clay from the site is recoverable to construct 811 cap with some off-site clay supplementation.

(Refer to attached calculations.)

Same capital cost as C2 with the following additional costs:	\$ 4,861,000
Purchase, transport, place, compact 105,000 cu.yd of clay @ \$12/yd3	\$ 1,260,000
Borrow Study (assume 10% of place, compact price)	\$ 73,500
Additional mob/demob costs, attributable to moving materials from off-site	\$ 250,000
Estimating Contingency (material delays, weather, etc., assume 15% of add. capital)	\$ 159,000

TOTAL CAPITAL, LOW RANGE ESTIMATE: **\$ 6,603,500**

High Range Estimate: Assumes all 250,000 cu.yd. of new clay must be brought in from an off-site source.

Same capital cost as C2 with the following additional costs:	\$ 4,861,000
Purchase, transport, place, compact 250,000 cu.yd of clay @ \$12/yd3	\$ 3,000,000
2X additional mob/demob costs, attributable to moving materials from off-site (2 seasons)	\$ 500,000
Borrow Study (assume same as low range cost estimate)	\$ 73,500
Estimating Contingency (material delays, weather, etc., assume 15% of add. capital)	\$ 349,000

TOTAL CAPITAL, HIGH RANGE ESTIMATE: **\$ 8,783,500**

### C3 O&M

Same as C2:

TOTAL O&M/YR: **\$ 72,000**

## Gas Alternatives

Objective: Determine capital and O&M costs for gas extraction/treatment alternatives

### Alternatives:

G1 - No Action, utilize existing system

G2 - Combination of existing and new systems:

- \* Use existing stick flares without any upgrades

- \* Construct a new active system for the Old Landfill consisting of 5 new wells (in addition to the existing piezometers/vents) piping, blower/flare

G3 - Enhanced extraction system:

- \* Convert 14 existing stick flares to wells and use 14 existing leachate/gas wells

- \* Construct 6 new wells

- \* Construct header piping, driplegs, condensate piping, blower, and flare

### Cost Summary:

G1	Capital		\$231,000
	Annual O&M	\$35,000	
	Present Worth O&M		\$686,000
	Total Cost		\$917,000
G2	Capital		\$701,100
	Annual O&M	\$35,000	
	Present Worth O&M		\$686,000
	Total Cost		\$1,387,100
G3	Capital		\$924,000
	Annual O&M	\$35,000	
	Present Worth O&M		\$686,000
	Total Cost		\$1,610,000



## Gas Alternatives - Cost Backup

### G1 - No Action

#### Capital Costs

\* Assume 25% of the G3 capital cost for repair as needed.

#### O&M Costs

\* Assume \$35,000/yr, which is typical for similar systems.

\$ 35,000

Use a 30 yr timeframe to calculate present worth for O&M:

$$\$35,000 * 19.6(3\%, 30 \text{ yrs}) =$$

\$686,000

### G2 - Combination of existing and new systems

#### Capital Costs

Costs for G3 can be used except for a reduction to items as marked by "\*" on the calculation spreadsheet (which total \$445,800)

For this alternative, to remain conservative, use half of those costs:

$$\$924,000 - 0.5(\$21,000 + \$287,500 + \$17,000 + \$20,400 + \$60,000 + \$8,400 + \$31,500) =$$

\$701,100

#### O&M Costs

O&M on the active portion of the site would be approximately = \$25,000.

Maintenance on the existing gas flares may be \$10,000:

\$ 35,000

Use a 30 yr timeframe to calculate present worth for O&M:

$$\$35,000 * 19.6(3\%, 30 \text{ yrs}) =$$

\$686,000

### G3 - Enhanced extraction system

#### Capital Costs

See attached spreadsheet.

#### O&M Costs

\* Assume \$35,000/yr, which is typical for similar systems.

\$ 35,000

Use a 30 yr timeframe to calculate present worth for O&M:

$$\$35,000 * 19.6(3\%, 30 \text{ yrs}) =$$

\$686,000

**GAS COLLECTION SYSTEM  
H.O.D. Landfill**

**CAPITAL CONSTRUCTION COST ESTIMATE**

<b>Item</b>	<b>Type of Work</b>	<b>Estimated Quantities</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
1.	Mobilization/Demobilization	1	LS	\$50,000	\$50,000
2.	Site Safety Plan	1	LS	\$12,500	\$12,500
3.	Gas Wells*	210	LF	\$100	\$21,000
4.	Gas Pipe Trenches*	11,500	LF	\$25	\$287,500
5.	Header Riser/Cleanouts*	34	EACH	\$500	\$17,000
6.	Gas Wellheads*	34	EACH	\$600	\$20,400
7.	Knock-Out/Lift Station (KO/LS)*	3	LS	\$20,000	\$60,000
8.	Individual Control Wires (To KO/LSs)*	4,200	LF	\$2	\$8,400
9.	Condensate Pressure Conveyance Pipe*	4,200	LF	\$7.50	\$31,500
10.	Dripleg	1	EACH	\$6,000	\$6,000
11.	Condensate Holding Tank	1	LS	\$25,000	\$25,000
12.	Compressor and Control Station	1	LS	\$40,000	\$40,000
13.	Blower Station	1	LS	\$40,000	\$40,000
14.	Utility Flare Station	1	LS	\$40,000	\$40,000
15.	Clear and Grub	0.62	acres	\$1,200	\$744
16.	Access Road	3000	SY	\$5	\$15,000
17.	Chainlink Fencing	300	LF	\$10	\$3,000
18.	Electrical Service Supply	1	LS	\$15,000	\$15,000

**TOTAL Extended Capital Construction Price**

**\$694,000**

**ADDITIONAL CONSULTING SERVICES**

<b>Item</b>	<b>Type of Work</b>	<b>Estimated Quantities</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
1.	Construction Completion Report	1	LS	\$50,000	\$50,000
2.	Bid-Phase Assistance	5% of Cap. Cost	LS	\$34,700	\$34,700
3.	Construction Management	10% of Cap. Cost	LS	\$69,400	\$69,400
4.	Engineering	10% of Cap. Cost	LS	\$69,400	\$69,400

**TOTAL Additional Consulting Services Price**

**\$230,000**

**TOTAL Extended Price**

**\$924,000**

\* Refer to backup calculations. The costs for these items are lower for Alternative G2.

## Leachate Extraction

Objective: Determine capital and O&M costs for alternatives for leachate extraction

### Alternatives:

- LC1 - No action, utilize existing manholes/piping
- LC2 - Existing wells plus new collection piping
- LC3 - Combination, New LF = Alt. LC2, Old LF = Alt. LC3
- LC4 - Dual extraction

### Cost Summary:

LC1	Capital Costs		\$0
	Annual O&M	\$ 4,000	
	Present Worth O&M		\$ 78,400
	Total		\$ 78,400
LC2	Capital Costs		\$ 232,300
	Annual O&M	\$ 60,000	
	Present Worth O&M		\$ 1,176,000
	Total		\$ 1,408,300
LC3	Capital Costs		\$ 367,800
	Annual O&M	\$ 72,000	
	Present Worth O&M		\$ 1,411,200
	Total		\$ 1,779,000
LC4	Capital Costs		\$ 439,000
	Annual O&M	\$ 60,000	
	Present Worth O&M		\$ 1,176,000
	Total		\$ 1,615,000

## Leachate Extraction

### LC1 - No action

#### Capital Costs

Assume negligible capital cost, \$0

#### O&M Costs

\*Assume 4 times per year check manhole/pipes, clean pipes annually

\$2,000 for cleaning & 32 hours @ \$60/hr = \$ 4,000

Present worth cost of O&M (3%, 30 yrs) = \$78,400

### LC2 - Existing wells plus new collection piping

#### Capital Costs

Assume capping work will occur concurrently so removal of clay to place pipe is negligible.

Addition of a 5,000 gallon storage tank is needed for temporary leachate storage = \$ 25,000

Automation of collection system, assume \$30,000 \$ 30,000

Pipe trenches, pipe, and backfill, approximately 4,200 ft of pipe @ \$35/ft = \$ 147,000

Engineering/Construction Management (15% of cap. costs) = \$ 30,300

Total \$ 232,300

#### O&M Costs

Assume \$60,000/year due to added pumping requirements. \$ 60,000

Present worth cost of O&M (3%, 30 yrs) = \$1,176,000

### LC3 - Combination, New LF = Toe drain, existing wells, Old LF = Dual extraction

#### Capital Costs

New LF: Use LC2 - 2,400' of pipe @ \$35/ft = \$ 148,300

Old LF: Use details for LC4, assume 1/2 LC4 = \$ 219,500

Total Capital Cost = \$ 367,800

#### O&M Costs

Assume, conservatively, sum of 60% of LC2 & LC4 O&M:

60% of LC2 & LC4 O&M \$ 72,000

Present worth cost of O&M (3%, 30 yrs) = \$1,412,000

#### LC4 - Dual extraction wells

##### Capital Costs

See attached spreadsheet. Total cost = \$1,363,000 for dual system; however, this is for both leachate and gas. The additional cost for leachate over and above that needed for gas is \$439,000 (Gas cost, assuming Alternative G3 is selected = \$924,000).

\$ 439,000

##### O&M Costs

Assume O&M costs of \$60,000 per year, based on previous experience.  
Present worth of O&M = \$60,000 (3%, 30 yrs) =

\$ 60,000

\$1,176,000

**DUAL EXTRACTION SYSTEM  
H.O.D. LANDFILL**

**CAPITAL CONSTRUCTION COST ESTIMATE**

<b>Item</b>	<b>Type of Work</b>	<b>Estimated Quantities</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
1.	Mobilization/Demobilization	1	LS	\$50,000	\$50,000
2.	Site Safety Plan	1	LS	\$12,500	\$12,500
3.	Gas Wells	210	LF	\$100	\$21,000
4.	Gas Pipe Trenches	11,500	LF	\$25	\$287,500
5.	Leachate Gravity Conveyance Pipe	11,500	LF	\$5	\$57,500
6.	Header Riser/Cleanouts	34	EACH	\$500	\$17,000
7.	Gas/Leachate Wellheads	34	EACH	\$600	\$20,400
8.	Well Pumps w/ Transmitter /Controls	34	EACH	\$3,500	\$119,000
9.	Knock-Out/Lift Station (KO/LS)	3	LS	\$20,000	\$60,000
10.	Individual Control Wires (To KO/LSs)	4,200	LF	\$2	\$8,400
11.	Leachate Pressure Conveyance Pipe	4,200	LF	\$7.50	\$31,500
12.	Dripleg	1	EACH	\$6,000	\$6,000
13.	Condensate/Leachate Holding Tank	1	LS	\$25,000	\$25,000
14.	Compressor and Control Station	1	LS	\$40,000	\$40,000
15.	Blower Station	1	LS	\$40,000	\$40,000
16.	Utility Flare Station	1	LS	\$40,000	\$40,000
17.	Clear and Grub	0.62	acres	\$1,200	\$744
18.	Access Road	3000	SY	\$5	\$15,000
19.	Chainlink Fencing	300	LF	\$25	\$7,500
20.	Electrical Service Supply	300	LS	\$15,000	\$15,000
21.	System Automation	15% of Cap. Cost	LS	\$15,000	\$132,000
<b>TOTAL Extended Capital Construction Price</b>					<b>\$1,010,000</b>

**ADDITIONAL CONSULTING SERVICES**

<b>Item</b>	<b>Type of Work</b>	<b>Estimated Quantities</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
1.	Construction Completion Report	1	LS	\$50,000	\$50,000
2.	Bid-Phase Assistance	10% of Cap. Cost	LS	\$101,000	\$101,000
3.	Construction Management	10% of Cap. Cost	LS	\$101,000	\$101,000
4.	Engineering	10% of Cap. Cost	LS	\$101,000	\$101,000
<b>TOTAL Extended Capital Construction Price</b>					<b>\$353,000</b>
<b>TOTAL Extended Price</b>					<b>\$1,363,000</b>

## **Leachate Treatment Alternatives**

Objective: Identify and estimate costs of leachate management approaches.

### General Assumptions

- \* Future flow rate of 15 gpm to reach leachate maintenance level then pump @ 5 gpm to maintain leachate level
- \* Leachate quality will correspond to that identified in the RI

### LT1: No action

- \* Baseline, lowest cost option
- \* Existing cost from Waste Management

### LT2: Pretreat and discharge to POTW

- \* Primary objectives are to reduce copper and BOD levels
- \* Metals pretreatment options include chemical and physical (e.g., precipitation and clarification, ion exchange, oxidation, reverse osmosis)
- \* Assume BOD limit is based on carbonaceous demand (i.e., nitrogenous demand is inhibited, so exclude ammonia)

#### **Recommendation:**

Remove metals by lime or caustic precipitation and clarification, lower BOD by air stripping, press sludge.

#### **Key Assumptions:**

- \* Costs do not include costs associated with baseline (e.g. hauling treated water to POTW, subsequent disposal at POTW, extraction costs)

### LT3: Treatment and surface discharge

- \* Objective is to meet NPDES discharge limits
- \* Assumes appropriate discharge location exists
- \* Reverse osmosis would treat all compounds listed in Table 3-1 and is the worst case cost.

#### **Key Assumption:**

- \* Does not include baseline costs
- \* Assumes surface water source is available/acceptable.

## Leachate Treatment

Objective: Determine capital and O&M costs for treatment alternatives

Alternatives:

- LT1 - No Further Action
- LT2 - Pretreat and discharge to POTW
- LT3 - Treat and surface discharge

Cost Summary:

LT1	Capital		\$	-
	Annual O&M	\$	66,800	
	Present Worth O&M		\$	1,310,000
	Total Cost		\$	1,310,000
LT2	Capital		\$	476,000
	Annual O&M	\$	681,000	
	Present Worth O&M		\$	13,347,600
	Total Cost		\$	13,823,600
LT3	Capital		\$	1,843,000
	Annual O&M	\$	599,000	
	Present Worth O&M		\$	11,740,400
	Total Cost		\$	13,583,400



LT1 - No Action: Pump, Transport, & Dispose at Remote POTW

*Assume the total cost of pumping leachate from the existing manholes and wells is approximately equal to the present worth of transport/discharge costs for 30 years.*

*Assume that the current extraction rate is 1 gpm and that the cost for transport using a 5,000 gallon tanker truck and discharge to the POTW combined is \$0.09/gallon.*

**Annual O&M Costs:**

Annual O&M = (1 gal/min) \* (60 min/hr) \* (24 hr/day) \* (365 day/yr) \* \$0.09/gal \* 20% Contingency = \$56,800  
Annual operation cost for this option is approximately: \$ 10,000

Annual O&M \$ 66,800

Calculate Present Worth of this option over 30 years

O&M P.W. (3%, 30 years) = \$1,310,000

**LEACHATE TREATMENT VOLUME / EXTRACTION RATE  
FOR ALTERNATIVES LT2 AND LT3.**

Leachate maintenance level (as described in RI) = 2 ft below the water level elevation contemporaneously measured in G11D.

$$\begin{aligned}\text{Average elevation of G11D (6/93 to 4/94)} &= (760.68 + 760.01 + 760.68 + 760.48 + 760.53 + 760.96) / 6 \\ &= 760.56 \text{ ft}\end{aligned}$$

* Leachate Maintenance Level = 758.57 ft
--

$$\begin{aligned}\text{Average leachate elevation (as of 4/25/94)} &= (766.7 + 769.3 + 764.53 + 772.15 + 760.82 + 779.37 + 774.72 + \\ &\quad 754.26 + 764.07 + 767.02 + 770.54 + 764.68 + 766.01 + 764.66) / 14 \\ &= 767.06 \text{ ft}\end{aligned}$$

\* Historically, leachate elevations have remained fairly constant; therefore, assume the average leachate elevation as of 4/94 is still representative. Let the amount of leachate to be removed at 30 gpm equal that necessary to achieve the "leachate maintenance level." Let any further extraction be at a rate that is high enough to account for annual infiltration. Based on HELP model results, assume 2 in/yr as a worst-case infiltration estimate. Assume refuse porosity = 0.45.

Amount of leachate to be removed at 15 gpm,  $V_{15}$   
(Before accounting for additional infiltration:)

$$V_{15} = (767.06 \text{ ft} - 758.57 \text{ ft}) \times (51 \text{ acres}) \times (43,560 \text{ sq ft/acre}) \times (7.48 \text{ gal/cu ft}) \times 0.45$$

$V_{15} = 63.5 \text{ MG}$
----------------------------

Amount of annual leachate production (assume 100% from infiltration, ignore storativity by cap and all other losses for worst case), VLP

$$V_{LP} = (2/12 \text{ ft}) \times (51 \text{ acres}) \times (43,560 \text{ sq ft/acre}) \times (7.48 \text{ gal/cu ft})$$

$V_{LP} = 2,769,545 \text{ gal}$
----------------------------------

Time to reach leachate maintenance level,  $t_{30}$  (yrs)

$$t_{30} = (63.5 \times 10^6 \text{ gal} + 2,769,545 \text{ gal/yr} \times t_{30}) \times (1 \text{ yr} / 7.884 \times 10^6 \text{ gal})$$

$$t_{30} = 8.054 + 0.351 t_{30}$$

$t_{30} = 12.4 \text{ yrs} = 12 \text{ yrs, 5 mo.}$
---

- \* Actual volume that will be discharged up to  $t_{30}$ :

$$V_{t_{30}} = 63.5 \times 10^6 + 2,769,545 \text{ gal/yr} \times 12.4 \text{ yr}$$

$V_{t_{30}} =$	97.842 MG
----------------	-----------

- \* Extraction Rate needed after reaching leachate maintenance level,  $Q_{ML}$

$$Q_{ML} = V_{LP} = (2,628,000 \text{ gal/yr}) \times (1 \text{ yr} / 525,600 \text{ min})$$

$Q_{ML} =$	5.00 gpm	
------------	----------	--

Will the leachate maintenance level of 756.57 ft cause dry bottoming of either the old or new landfill areas?

(Refer to attached supporting information from RI Report.)

- \* Spot check boring data from both sides of the landfill to determine bottom elevations. (Selected locations are highlighted on the attached figure.)

* Ground elevation - depth to base material = Bottom Elevation
--

OLD LF

LP2:	785.5 ft	- 40 ft	=	745.5 ft
LP3:	778.1 ft	- 28.5 ft	=	749.6 ft
LP12:	782.6 ft	- 25.5 ft	=	757.1 ft dry bot.
LP13:	779 ft	- 17 ft	=	762 ft dry bot.
LP11:	787.8 ft	- 33 ft	=	754.8 ft
LP4:	788.9 ft	- 40 ft	=	748.9 ft
B3:	773.7 ft	- 10.5 ft	=	763.2 ft dry bot.
LP2:	785.5 ft	- 40 ft	=	745.5 ft

NEW LF (deeper than OLD LF)

LP5:	796.6 ft	- 51 ft	=	745.6 ft
GWF12:	792.5 ft	- 22+ ft	-->	770.5 INCONCLUSIVE
LP6:	794.6 ft	- 40 ft	=	754.6 ft
LP7:	794.7 ft	- 62 ft	=	732.7 ft
LP9:	785.5 ft	- 68.5 ft	=	717 ft

Leachate maintenance level of 756.57 ft would cause some amount of localized bottom drying near perimeter of old LF, but overall would not result in dry-bottoming of either the old or new landfills.

BPG\bpg\TAB

J:\1252\035\03090210\Final FS 4-98\cost\_estimates\cost\_email w\_3%

1252035.03090210

TABLE 1

PROJECT: H.O.D. Leachate Management

PROJECT NO.: 1252035.031801

DATE: 2-Jun-98

## PRELIMINARY COST ESTIMATE

OPTION: Pretreatment and POTW Discharge

DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
<b>I. INITIAL IMPLEMENTATION ESTIMATED COSTS</b>				
A. Consulting Services				
1. System Design (Drawings/Specs)	1	LS	\$10,500	\$10,500
2. Permitting (Building)	1	LS	\$1,000	\$1,000
3. Preconstruction				
a. Subcontractor procurement	1	LS	\$4,100	\$4,100
b. Construction coordination & preconstruction mtg	1	LS	\$1,200	\$1,200
c. Site safety plan	1	LS	\$12,500	\$12,500
4. Construction Oversight	15	DAYS	\$1,600	\$24,000
5. System Start-up	5	DAYS	\$875	\$4,375
6. Project Closeout				
a. O&M and long-term monitoring plan	1	LS	\$2,450	\$2,450
b. Construction documentation report	1	LS	\$4,300	\$4,300
7. Project Management/Meetings	1	LS	\$7,930	\$7,930
			Subtotal	\$72,355
			Estimating Contingency (15%)	\$10,900
Total Consulting Services Initial Implementation Estimated Cost				\$83,000
B. Commodity Services				
1. Mobilization/Demobilization	1	LS	\$50,000	\$50,000
2. Remediation Building				
a. Concrete foundation	25	CY	\$150	\$3,750
b. Building	1	EA	\$35,000	\$35,000
3. Mechanical Work				
a. Holding tank	2	EA	\$78,000	\$156,000
b. Transfer pump	2	EA	\$2,500	\$5,000
c. Lamella clarifier, mixers, sludge pumps	1	LS	\$23,000	\$23,000
d. Diffused air stripper, blower	1	EA	\$27,000	\$27,000
e. Contact tank	1	EA	\$500	\$500
f. Metering pump	3	EA	\$1,200	\$3,600
g. Filter press	1	EA	\$10,000	\$10,000
h. Sludge holding tank	1	EA	\$1,500	\$1,500
i. Piping within remediation building	1	LS	\$2,000	\$2,000
j. Gauges, valves, fittings, sample ports	1	LS	\$4,000	\$4,000
k. Exhaust fan and louver in treatment building	1	EA	\$1,000	\$1,000
4. Electrical Work				
a. Lights, switches, and outlets	1	LS	\$2,000	\$2,000
b. Controls and control panel	1	LS	\$8,000	\$8,000
c. Electric heater and thermostat	1	EA	\$1,500	\$1,500
d. Distribution panel, wiring, and conduit	1	LS	\$3,000	\$3,000
e. Electric meter and utility service to building	1	LS	\$5,000	\$5,000
			Subtotal	\$341,850
			Estimating Contingency (15%)	\$51,278
Total Commodity Services Initial Implementation Estimated Cost				\$393,000
<b>TOTAL INITIAL IMPLEMENTATION ESTIMATED COST</b>				<b>\$476,000</b>

BPG\bpg\TAB

J:\1252\035\03090210\Final FS 4-98\cost\_estimates\cost\_email w\_3%  
1252035.03090210

TABLE 1 (cont.)

DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
<b>II. ANNUAL O&amp;M ESTIMATED COSTS</b>				
<b>A. Consulting Services</b>				
1. Operation Labor	416	HRS	\$60	\$24,960
2. Maintenance Labor	96	HRS	\$60	\$5,760
3. Maintenance Materials	1	LS	\$12,655	\$12,655
4. Effluent monitoring	12	HRS	\$60	\$720
5. Reporting to POTW	4	RPT	\$900	\$3,600
6. Project Management/Meetings	1	LS	\$6,200	\$6,200
Subtotal				\$53,895
Estimating Contingency (15%)				\$8,100
Total Consulting Services Annual O&M Estimated Cost				\$62,000
<b>B. Commodity Services</b>				
1. Electrical Power	55,550	Kw-Hrs	\$0.08	\$4,444
2. Effluent Monitoring Laboratory Analyses	12	EA	\$250	\$3,000
3. Caustic, polymer, and sulfuric	1	LS	\$5,000	\$5,000
4. Sludge Disposal	*	gal	\$0.40	\$43,000
5. Discharge to POTW	*	gal	\$0.09	\$483,000
Subtotal				\$538,444
Estimating Contingency (15%)				\$80,767
Total Commodity Services Annual O&M Estimated Cost				\$619,000
<b>TOTAL ANNUAL O&amp;M ESTIMATED COST</b>				<b>\$681,000</b>

General Notes:

1. Initial implementation and annual O&M estimated costs shown are approximate and for comparison only.
  2. Operation labor is based on an average of 8 hours of operating labor required every week.
  3. Maintenance labor is based on an average of 8 hours of maintenance labor required every month.
  4. Maintenance materials estimate is based on 5% of the electrical and mechanical equipment initial implementation costs
  5. Electrical power usage is based on one 5 hp blower and two 0.5 hp transfer pumps operating continuously and miscellaneous electrical equipment - lights, heat, etc.
- \* Refer to backup calculations. Sludge disposal and discharge amounts decrease significantly after the first five years of operation.

## LT2 - Pretreat and discharge to POTW: Cost Backup Calculations

### **I. Implementation**

#### A. Consulting

##### **1. Design**

80 hrs * \$74/hr =	\$	5,920
12 hrs * \$92/hr =	\$	1,104
24 hrs * \$78/hr =	\$	1,872
4 hrs * \$106/hr =	\$	424
24 hrs * \$44/hr =	\$	1,056
	\$	<u>10,376</u>

##### **2. Building Permit**

8 hrs * \$74/hr =	\$	592
2 hrs * \$92/hr =	\$	184
1 hr * \$106/hr =	\$	106
2 hrs * \$44/hr =	\$	88
	\$	<u>970</u>

##### **3. Preconstruction**

###### **a. Subcontractor Procurement**

40 hrs * \$78/hr =		3,120
4 hrs * \$92/hr =		368
2 hrs * \$106/hr =		212
8 hrs * \$44/hr =		352
	\$	<u>4,052</u>

###### **b. Meetings**

8 hrs * \$78/hr =	\$	624
4 hrs * \$92/hr =	\$	368
4 hrs * \$44/hr =	\$	176
	\$	<u>1,168</u>

###### **c. Health & Safety Plan**

8 hrs * \$74/hr =	\$	592
1 hr * \$92/hr =	\$	92
4 hrs * \$44/hr =	\$	176
	\$	<u>860</u>

##### **4. Oversight - assume 15 days**

15 hrs * \$78/hr =	\$	1,170
+25% office =	\$	293
+ mileage =	\$	100
	\$	<u>1,563</u>

5. Startup - assume 5 days

10 hrs * \$62/hr =	\$	620
+25% office =	\$	155
+ mileage =	\$	100
	\$	875

6. Project Closeout

a. O&M Plan

20 hrs * \$74/hr =	\$	1,480
4 hrs * \$92/hr =	\$	368
2 hrs * \$106/hr =	\$	212
8 hrs * \$44/hr =	\$	352
	\$	2,412

b. Documentation

* Same as O&M =	\$	2,412
+ 24 hrs * \$74/hr =	\$	1,776
	\$	4,188

7. Project Management

\* Assume 15% of other consulting costs

B. Commodity

1. Mobilization/Demobilization

\*Assume \$ 50,000

2. Building - assume 30' x 30'

a. Slab

30' x 30' x 3/4' = 25 cu.yd. concrete  
25 cu.yd. \* \$150/cu.yd. = \$ 3,750 (includes rebar & finish)

b. Building

\*Assume \$ 35,000

3. Mechanical

a. Holding Tank (influent & effluent)

Provide storage for 3 days @ 30 gpm = 129,600 gallons  
129,600 gallons \* \$0.6/gal for steel = \$ 77,760 each

b. Transfer Pumps - One each for influent holding tank and effluent holding tank

\*Assume \$ 2,500 each

c. Clarifier Package - includes rapid mix, floc and settling chambers, floc and flash mixers, sludge pumps and controls: \$ 23,000  
(Cost is per Graver Water (page 8).)

d. Air Stripper - \$ 27,000 per past experience

e. Contact Tank - for sulfuric @ 5 min. residence time

30 gpm \* 5 min = 150 gal

\*Assume \$ 500

f. Metering Pump - one each for caustic, polymer, sulfuric.

\*Assume \$ 1,200 each

g. Filter Press

\*Assume \$ 10,000

h. Sludge Holding Tank

\*Assume 1,000 gal ~ \$ 1,500

i-k. Assumed costs

4. Electrical - Assumed costs

**II. Annual O&M**

A. Consulting

1. Operating Labor - Assume 8 hrs/wk \* 52 wks = 416 hrs

2. Maintenance Labor - Assume 8 hrs/mo. \* 12 mo. = 96 hrs

3. Maintenance Materials - Assume 5% of mechanical & electrical equipment cost

4. Effluent Monitoring - Assume monthly influent & effluent sampling - 1 hr labor

5. Quarterly Reporting to POTW

8 hrs * \$74/hr =	\$	592
1 hr * \$92/hr =	\$	92
1 hr * \$106/hr =	\$	106
2 hr * \$44/hr =	\$	88
	\$	<u>878</u>

6. Project Management

\* Assume 15% of other consulting costs

B. Commodity

1. Electrical

Approx. 2, 0.5 hp transfer pumps, 7.5 hp air stripper blowers

8.5 hp \* 0.746 kW/hp \* 24 hr/d \* 365d/yr = 55,550 kW-hr

2. Analytical

\* Assume monthly BOD and metals @ \$250/round



3. Caustic, polymer, sulfuric - assume \$5,000/yr.

4. Sludge Disposal - Assume sludge equals 2% of annual  
volume treated, 157,700gal \* \$0.40/gal,

for each of first 12 years	\$63,080
for each year after 12th	\$22,156

Present worth of sludge disposal = (3%, 12 yrs@15gpm, 18 yrs@5gpm)	\$842,000
Annualized cost of sludge disposal =	\$43,000

5. Discharge to POTW - Assume \$0.09 per gallon.

First 12 years (7,884,000 gal/yr (15 gal/min)@0.09\$/gal):	\$709,560
Each year after the 12th (2,769,545 gal/yr (5 gal/min)@\$0.09/gal):	\$249,300

Present worth of discharge = (3%, 12 yrs@15gpm, 18 yrs@5gpm)	\$9,468,000
Annualized cost of discharge =	\$483,000

TABLE 2

PROJECT: H.O.D. Leachate Management	PROJECT NO.: 1252035.031801
PRELIMINARY COST ESTIMATE	DATE: 2-Jun-98

OPTION: Treat and NPDES Discharge

DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
<b>I. INITIAL IMPLEMENTATION ESTIMATED COSTS</b>				
<b>A. Consulting Services</b>				
1. System Design	1	LS	\$50,000	\$50,000
2. Permitting				
a. Building	1	LS	\$5,000	\$5,000
b. NPDES	1	LS	\$21,000	\$21,000
3. Preconstruction				
a. Subcontractor procurement	1	LS	\$4,100	\$4,100
b. Construction coordination & preconstruction meeting	1	LS	\$1,200	\$1,200
c. Site safety plan	1	LS	\$12,500	\$12,500
4. Construction Oversight	15	DAYS	\$1,600	\$24,000
5. System Start-up	5	DAYS	\$875	\$4,375
6. Project Closeout				
a. O&M and long-term monitoring plan	1	LS	\$2,450	\$2,450
b. Construction documentation report	1	LS	\$4,300	\$4,300
7. Project Management/Meetings	1	LS	\$7,930	\$7,930
			Subtotal	\$136,855
			Estimating Contingency (15%)	\$20,600
Total Consulting Services Initial Implementation Estimated Cost				\$157,000
<b>B. Commodity Services</b>				
1. Mobilization/Demobilization	1	LS	\$50,000	\$50,000
2. Remediation Building Foundation	10	CY	\$150	\$1,500
3. Mechanical Work				
a. Holding tank	1	EA	\$78,000	\$78,000
b. Transfer pump	2	EA	\$2,500	\$5,000
c. Reverse osmosis package system	1	LS	\$500,000	\$500,000
d. Transfer tank	1	EA	\$500	\$500
e. Concentrate holding tank	1	EA	\$4,500	\$4,500
f. Piping to remediation building	1	LS	\$2,000	\$2,000
g. Gauges, valves, fittings, sample ports	1	LS	\$4,000	\$4,000
4. Electrical Work				
a. Controls and control panel	1	LS	\$8,000	\$8,000
b. Distribution panel, wiring, and conduit	1	LS	\$3,000	\$3,000
c. Electric meter and utility service to building	1	LS	\$5,000	\$5,000
5. Installation of 2-Mile Pipeline to Discharge Point				
Trenching	10,600	LF	\$30	\$318,000
Piping	10,600	LF	\$20	\$212,000
Costs associated w/ crossing roads, easmts. (based on installing 2 mi. of piping, permits & easements required to install pipe)	1	LS	\$275,000	\$275,000
			Subtotal	\$1,466,500
			Estimating Contingency (15%)	\$219,975
Total Commodity Services Initial Implementation Estimated Cost				\$1,686,000
<b>TOTAL INITIAL IMPLEMENTATION ESTIMATED COST</b>				<b>\$1,843,000</b>

**TABLE 2 (cont.)**

DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
<b>II. ANNUAL O&amp;M ESTIMATED COSTS</b>				
A. Consulting Services				
1. Operation & Maintenance Labor	1,560	HRS	\$60	\$93,600
2. Effluent monitoring	12	HRS	\$60	\$720
3. Reporting to IEPA	12	RPT	\$600	\$7,200
4. Project Management/Meetings	1	LS	\$15,228	\$15,228
			Subtotal	\$116,748
			Estimating Contingency (15%)	\$17,600
			Total Consulting Services Annual O&M Estimated Cost	\$134,000
B. Commodity Services				
1. Electrical Power/Membranes/Cleaning Agents/etc.	4,876	KGal	\$50	\$243,790
2. Effluent Monitoring Laboratory Analyses	12	EA	\$800	\$9,600
3. Sludge Disposal	*	gal	\$0.40	\$43,000
4. Effluent conveyance/transport	5,400	KGal	\$20	\$108,000
			Subtotal	\$404,390
			Estimating Contingency (15%)	\$60,700
			Total Commodity Services Annual O&M Estimated Cost	\$465,000
			<b>TOTAL ANNUAL O&amp;M ESTIMATED COST</b>	<b>\$599,000</b>

General Notes:

1. Initial implementation and annual O&M estimated costs shown are approximate and for comparison only.
  2. Operation labor is based on an average of 8 hours of operating labor required every week.
  3. Maintenance labor is based on an average of 2 hours of maintenance labor required every week.
  4. Electrical power usage, cleaning agents, membrane replacement costs per Rochem Separation Systems.
  5. Effluent transport amount is an average value over thirty years.
- \* Sludge disposal amount varies after five years. Refer to the LT2 backup calculations for further details.

### LT3 - Treatment and surface discharge: Cost Backup Calculations

#### **I. Implementation**

##### A. Consulting

Same as LT2, except cost of system design and building permitting increase, add NPDES permit:

80 hrs * \$74/hr =	\$ 5,920
80 hrs * \$92/hr =	\$ 7,360
60 hrs * \$54/hr =	\$ 3,240
40 hrs * \$106/hr =	\$ 4,240
	<u>\$ 21,000</u>

##### B. Commodity

#### **3. Mechanical**

a. Holding tank - only need one - continuous discharge.

c. Reverse Osmosis Units - \$500,000 capital per ROCHEM.

Includes enclosure, units, pretreat, controls. (page 9)

e. Concentrate holding tank - assume 5,000 gal to allow 1-tank truck disposal, ~ \$4,500

#### **II. Annual O&M**

##### A. Consulting

1. Assume 4 hrs/day for labor.

3. Reporting to IEPA - monthly discharge report.

4 hrs * \$74/hr =	\$ 296
1 hr * \$92/hr =	\$ 92
1 hr * \$106/hr =	\$ 106
2 hrs * \$44/hr =	\$ 88
	<u>\$ 600</u>

##### B. Commodity

1. Electrical/Membranes/Chemicals = \$0.05/gal - per ROCHEM.

2. Monitoring - assume VOC/SVOC/BOD/Metals

\*Assume \$800/event, monthly

3. Sludge Disposal - assume same as option 2 - \$43,000/yr

##### Effluent Conveyance and Transport

Assume \$0.02/gallon for pumping, maintenance on discharge and pipeline

BPG\bpg\TAB

J:\1252\035\03090210\Final FS 4-98\cost\_estimates\Leachate Treatment  
1252035.03090210

## Groundwater Monitoring Costs

### GW-1 - No Further Action

#### Capital Costs

Replacement of VW4 with VW7

	\$	693,900
<b>Total Capital Costs:</b>	\$	693,900

#### O&M Costs

Groundwater monitoring costs for No Further Action alternative

Quarterly; assumes current cost (\$41,500/yr) of GW sampling event, plus 50% for augmentation of existing program

\$	63,000	
<b>Present Worth (3%, 30yrs) :</b>	\$	1,235,000

**TOTAL:** \$ 1,929,000

### GW-2 - Monitored Natural Attenuation

#### Capital Costs

Replacement of VW4 with VW7

\$ 693,900

Pre-Design Investigation Monitoring Wells

Well Inst., 2 double cased wells\*85 ft.\*\$125/ft =

\$ 21,250

Field Oversight, 10 days\*10hr/day\*\$92/hr =

\$ 9,200

Contract Mgt./Admin., 10 hrs \* 92/hr =

\$ 920

**Total Capital Costs:** \$ 725,300

#### O&M Costs

Quarterly Sampling: Assume sampling of 20 wells

Labor, 20 wells\*(1d/8 wells)\*(8hr/d)\*(\$62/hr\*2)\*4/yr \$ 9,920

Travel Expenses, (5d \* \$40/d + \$40)\*4/yr = \$ 960

Equipment/Supplies, assume 4\*\$700 = \$ 2,800

Laboratory Analysis of Samples: Assume \$550/well

\$550/well \* 20 wells \* 4/yr = \$ 44,000

Quarterly Reporting

Data Prep, (\$62/hr \* 8hrs)\*4 = \$ 1,984

CAD/Admin, (\$44/hr \* 8hrs)\*4 = \$ 1,408

Report Writing/Data Interpretation (\$74/hr \* 24)\*4 = \$ 7,104

QA/QC (\$92/hr \* 4hrs) \*4 = \$ 1,472

**\$ 69,700**

**Present Worth (3%, 30yrs) :** \$ 1,367,000

**TOTAL:** \$ 2,093,000

## Costs incurred to abandon and replace VW4

### Well Abandonment Cost

Engineering/Consulting ( $\$74/\text{hr} * 40\text{hrs} + \$92/\text{hr} * 20\text{hrs}$ )=	\$	4,800
CAD/Administrative Support ( $\$54/\text{hr} * 20\text{h} + \$44/\text{hr} * 20\text{h}$ ) =	\$	1,960
Bid-phase costs (Assume \$7,500)	\$	7,500
Mobilization/Demobilization/Labor ( $\$2,500 + \$50/\text{hr} * 2 * 50$ ) =	\$	7,500
Misc. material/subconsulting costs (Assume \$10,000)=	\$	10,000
Letter Report/Agency Communication ( $\$74/\text{hr} * 20\text{hr} +$		
$\$92/\text{hr} * 10\text{ hr}$ )=	\$	2,400

Assume a 15% contingency factor : \$ 5,200

**SUBTOTAL:** \$ 39,400

### Well Replacement Cost

Property purchase	\$	7,040
Well replacement	\$	76,012
Additional field investigation assistance	\$	1,355
Well production	\$	77,963
Well hook-up (includes capital & commodity charges)	\$	490,356

**SUBTOTAL:** \$ 652,800

**TOTAL:** \$ 693,900